



**REPORT**

**Kinloss Landfill Site**  
*2023 Annual Monitoring Report*

Submitted to:

**TOWNSHIP OF HURON-KINLOSS**

PO Box 130  
21 Queen Street  
Ripley, ON  
N0G 2R0

Submitted by:

**WSP Canada Inc.**

1450 1st Ave W #101 Owen Sound, Ontario, N4K 6W2, Canada

1 (519) 376-7612

101-16945-00 / 121-60018-16

March 31, 2024



# Table of Contents

<b>1.0</b>	<b>INTRODUCTION</b>	<b>1</b>
1.1	Background	1
1.2	Purpose	1
<b>2.0</b>	<b>SITE OPERATIONS</b>	<b>1</b>
2.1	Site Usage	1
2.2	Site Access	1
2.3	Site Life	2
2.4	Burning Operations	2
2.5	Recycling/Waste Reduction	3
2.5.1	Scrap Metal and Tires	3
2.5.2	Recyclable Materials	3
2.5.3	E-Waste and Mattresses	3
2.5.4	Summary of Recycling/Waste Reduction	3
<b>3.0</b>	<b>MONITORING</b>	<b>4</b>
3.1	Current Monitoring Program	4
3.2	Shallow Groundwater Configuration	6
3.3	Groundwater Monitoring Results	7
3.3.1	Background Groundwater Chemistry	7
3.3.2	Leachate Monitoring	8
3.3.3	Downgradient Groundwater Monitoring	8
3.4	Surface Water Monitoring	10
3.5	Reasonable Use	10
3.6	Buffer Lands	12
3.7	Combustible Gas	13
<b>4.0</b>	<b>PROPOSED FUTURE MONITORING PROGRAM</b>	<b>14</b>
<b>5.0</b>	<b>CONCLUSIONS</b>	<b>16</b>

**6.0 RECOMMENDATIONS.....16**

**TABLES**

Table 1 Kinloss Landfill Site Monitoring Well Security  
 Table 2 Leachate Indicator Parameters, Background and Leachate Wells  
 Table 3 Summary of Methane Monitoring Results  
 Table 4 Proposed Future Monitoring Program

**APPENDED TABLES**

Table 5 Summary of 2019 to 2023 Recycling Data  
 Table 6 Summary of Groundwater Elevations  
 Table 7 Reasonable Use Criteria – New Background Upgradient Monitor OW11-16

**APPENDED FIGURES**

Figure 1 Hydrograph – OW13  
 Figure 2 Hydrograph – All Wells Except OW13  
 Figure 3 Indicator Parameters – Spring  
 Figure 4a Chloride Vs. Time  
 Figure 4b Boron Vs. Time  
 Figure 4c Barium Vs. Time  
 Figure 4d Sulphate Vs. Time  
 Figure 4e Ammonia Vs. Time  
 Figure 4f Nitrate Vs. Time  
 Figure 4g Doc Vs. Time  
 Figure 5 Indicator Parameters – Surface Water

**MAPS**

Map 1 Regional Location Map  
 Map 2 Existing Conditions Map  
 Map 3 Groundwater Flow  
 Map 4 Section A-A

**APPENDICES**

**APPENDIX A**

Environmental Compliance Approval

**APPENDIX B**

BASWR Recycling Data

**APPENDIX C**

Cross Section and Borehole Logs

**APPENDIX D**

Certificate of Analysis and Lab Results

**APPENDIX E**

Summary of Groundwater Results

**APPENDIX F**

2023 Landfill Correspondence

**APPENDIX G**

Summary of Surface Water Results

**APPENDIX H**

Buffer Lands Certificate of Registration and Lease Agreement

**APPENDIX I**

Monitoring and Screening Checklist

## 1.0 INTRODUCTION

### 1.1 Background

The Kinloss Landfill Site (site) is located on the north half of Part Lot 16, Concession 6 in the former Township of Kinloss in the amalgamated Township of Huron-Kinloss (Township). Refer to **Map 1** for the regional location of the site.

The landfill site is 6.0 hectares in area, all of which is approved for landfilling by the Certificate of Approval. The primary landfilling area is 3.9 hectares in area and is located within the approved area. The Township also owns a 3.0-hectare parcel of land immediately south of the landfill site and holds a 99-year lease on a 12.3-hectare property abutting the eastern property boundary of the landfill site. The respective locations of the aforementioned properties are presented in **Map 2**, Existing Conditions.

The landfill site operates in accordance with Certificate of Approval No. A272801 issued on October 1, 1980, amended in February 1993 and February 1996, and is now referred to as Environmental Compliance Approval Number A272801 (ECA). The Kinloss Site remains temporarily closed, until closure of the Huron Landfill. The ECA and amendments are enclosed in **APPENDIX A**.

### 1.2 Purpose

The purpose of this report is to provide an annual report regarding the operation and monitoring of the landfill. The Annual Monitoring Report is a required condition of the ECA (**APPENDIX A**).

## 2.0 SITE OPERATIONS

### 2.1 Site Usage

The Kinloss Landfill Site continues to accept recyclable materials from the former Village of Lucknow and Township of Kinloss. The acceptance of household waste was discontinued on August 1, 2002. Household waste from the Township of Kinloss is landfilled at the Huron Landfill. The Huron Landfill (Certificate of Approval No. A272601) is owned and operated by the Township of Huron-Kinloss. The ability to accept waste from the former Township of Kinloss and former Village of Lucknow at the Huron Landfill was approved by the Ministry of the Environment, Conservation and Parks (MECP) in 2010.

### 2.2 Site Access

The Kinloss Landfill Site is open to residents during the months of April to October for the acceptance of recyclables, scrap metal, tires, burnable materials and brush. The operating hours during these months are on Saturdays from 10:00 a.m. to 2:00 p.m. The site is closed from November to the first Saturday in April.

The access road is gravel and well maintained by the Township. Access to the site is controlled by a lockable steel cable between a rigid steel frame. Fencing is in place around the entire perimeter of the site.

Signage at the front gate identifies who may use the site, hours of operation, ECA number, acceptable waste types and emergency contact information. The existing topography and vegetation provide screening.

Township staff indicated no complaints regarding the operation of the Kinloss Landfill were received in 2023.

## 2.3 Site Life

The acceptance of household waste at the Kinloss Landfill was discontinued in August 2002, with the waste being diverted to the Huron Landfill. The Kinloss Landfill Site continues to act as a transfer station, receiving recyclable and burnable materials from residents of the former Township of Kinloss and the Village of Lucknow.

A letter was issued with the 2002 Annual Monitoring Report (submitted in March 2003) indicating that the Township had decided to divert the waste from the Kinloss Landfill to the Huron Landfill, but no formal application for the temporary closure of the site was made to the MECP at that time.

The MECP conducted an inspection at the Kinloss Landfill on November 18, 2021. Details of the inspection are included in **APPENDIX F**. The inspection noted that the current closed status of the site should be included in the ECA and that an amendment to the existing ECA is required. The MECP has also noted that the current ECA does not include reference to the Contaminant Attenuation Zone (CAZ) and that those details should also be included in the amendment application. The November 2021 inspection asked for a written response providing documentation confirming the landfill is registered on file. The Township responded on February 15, 2022 and provided the title search results (**APPENDIX F**).

The MECP did not conduct an inspection at the Kinloss Landfill in 2023.

The MECP provided comments on the 2022 Annual Monitoring Report for the site regarding the surface water monitoring analysis via email (**APPENDIX F**) on June 12, 2023. The MECP was in agreement that surface water quality from Stations SW1 and SW2 do not suggest significant impact from landfill activities. The surface water monitoring program and reporting continue as per the existing ECA requirements.

WSP and the Township of Huron-Kinloss are currently working on an amendment application to ECA No. A272801 to reflect the temporarily closed status of the Kinloss site and to address the CAZ which was in question from the November 18, 2021 MECP inspection (**APPENDIX F**).

The Township intends to re-open the Kinloss Landfill site once the Huron Landfill site has reached capacity (estimated site life remaining is approximately 7 years). Based on information from the 2006 Annual Monitoring Report (R.J. Burnside & Associates Ltd.) the estimated remaining capacity of the Kinloss site is 137,000 m<sup>3</sup>. This estimate is based on a site survey completed in August 2003 that was based on a cross-sectional survey of the waste surface only, followed by end-method volumetric calculations. It should be noted that calculations and projections are subject to change as conditions change. It is recommended that annual topographic surveys be completed once landfilling resumes at the Kinloss Landfill site, following this period of temporary closure. The annual topographic surveys allow for the assessment of remaining landfill capacity. Data collected from these surveys, coupled with computer modelling, will allow for more accurate determination of annual landfilled volumes and remaining site life.

## 2.4 Burning Operations

Burning operations are conducted at the site. In accordance with MECP Guideline C-7 Burning at Landfill Sites, only segregated brush, lumber and clean wood may be burned at the site. Burning operations take place in a separate area, as shown in **Map 2**. Burning operations are conducted when the site is closed to the public and weather conditions are favourable. Township Staff ensure that only designated materials are in the burn pile before burning and supervise all burning operations.

## 2.5 Recycling/Waste Reduction

As of August 1, 2002, the Kinloss Landfill ceased acceptance of household waste. Recyclables, scrap metal, white goods, brush, tires and burnable materials from the former Township of Kinloss and the Village of Lucknow are still accepted. Household waste from the former Township of Kinloss is transported to the Huron Landfill via curbside pickup. Household waste from the Village of Lucknow is landfilled at the Huron Landfill as of July 2018.

Bruce Area Solid Waste Recycling (BASWR) has provided curbside waste and blue box collection for the municipality since August 2002. Residents of the former Township of Kinloss and the Village of Lucknow can also bring their recyclables and burnable materials to the landfill during open hours.

Combined 2023 waste diversion totals for all Township landfills are presented in **APPENDIX B**.

### 2.5.1 Scrap Metal and Tires

In 2023, 128.20 tonnes of scrap metal were removed from the Huron and Kinloss landfills by AOR Metals.

In 2023, the number of tires collected at the Huron and Kinloss landfills as part of the Ontario Tire Stewardship Program totalled 3,308 tires, at an approximate mass of 29.1169.71 tonnes.

It is recommended that scrap metal and tires be removed by a recycling contractor when the quantity of the segregated material justifies removal.

### 2.5.2 Recyclable Materials

The service area of the Kinloss Landfill is provided with regular Blue Box pickup on a bi-weekly basis, as is the whole of the Township of Huron-Kinloss. Blue Box pickup is provided by Bruce Area Solid Waste Recycling (BASWR).

Recycling bins are also located on-site as shown in **Map 2**. Cardboard recycling as well as regular Blue Box material recycling bins are available. BASWR removes the materials from these bins on a regular basis.

The 2023 recycling data summaries for the Township from BASWR are enclosed in **APPENDIX B**.

### 2.5.3 E-Waste and Mattresses

Electronic waste (E-waste) is diverted from landfilling within the Township as well. In 2023, a total of 20.93 tonnes of E-waste was diverted. E-waste is not accepted at the Kinloss Landfill Site.

Mattresses are segregated at the site and stockpiled in a sea container. The total number of mattresses shipped off site in 2023 was 537 (18.26 tonnes) for the Huron Landfill. The Kinloss Landfill Site does not accept mattresses.

### 2.5.4 Summary of Recycling/Waste Reduction

**Table 5** summarizes the recycling and diverted materials data for the Township (both the Kinloss and Huron Landfills are represented) over the past five years. As shown in **Table 5**, the recyclable tonnages have been relatively consistent over time. The 2023 tonnage of recyclables (404.21 tonnes) returned to within typical historical range following the historically low tonnage in 2022 (223.66 tonnes). When all segregated materials are included, the total tonnage diverted from both Township landfills (Kinloss and Huron) is 604.46 tonnes in 2023. This tonnage represents an 18% diversion rate for the Township. The estimated saving in landfill space for 2023 is approximately 1,208.92 m<sup>3</sup>.

### 3.0 MONITORING

#### 3.1 Current Monitoring Program

The current monitoring program at the Kinloss Landfill site is completed in accordance with the ECA for the site, Number A272801, issued October 1, 1980, and most recently amended on February 27, 1996. The monitoring of the groundwater and surface water at the Kinloss Landfill enables the determination of the flow direction and parameter concentrations of the landfill generated leachate plume. Samples are obtained twice per year (spring and fall) from the monitoring wells and surface water stations. In addition, water level elevations are obtained twice per year to confirm the groundwater flow direction. The monitoring program has been in existence since 1988. Currently, groundwater elevations are reported relative to a historical survey with an inferred benchmark.

The monitoring program dictates that each observation well sampled be purged prior to sampling to obtain a representative groundwater sample. To purge a well, a volume of water equivalent to three well casing volumes is removed from the well, or the well is purged dry and allowed to recover prior to sample collection.

The sampling and field filtering materials utilized to collect the groundwater samples are the Waterra polytube and foot valve and a disposable high turbidity 0.45 micron in-line filter. Each well is equipped with dedicated polytubing and a foot valve.

The monitoring well network is summarized in **Table 1** below. Monitoring wells OW4 to OW11 were installed by backhoe in 1985 and are relatively rudimentary in construction. The remaining wells were drilled in 1997 to 2004 and are constructed of 2" diameter PVC casing and 1.5 m long PVC well screens. In addition, these wells contain a sand filter pack around the screened area and are sealed with bentonite above the well screen. In October 2014, OW14 was replaced with OW14-14. In August 2016, OW11-85 was decommissioned and replaced with OW11-16. Additionally, OW15 and OW16 were drilled in August 2016. Borehole logs containing the construction details of the monitoring wells are enclosed in **APPENDIX C**. The wells are protected by a lockable steel casing.

Well inspections are conducted in conjunction with semi-annual sampling in spring and fall, as shown in **Table 1**.

Observation Well	Well Protection	Well Security		Condition	
		June 2023	November 2023	June 2023	November 2023
OW4	Steel Casing and Lid	Locked	Locked	Good	Good
OW5	Steel Casing and Lid	Locked	Locked	Good	Good
OW6	Steel Casing and Lid	Locked	Locked	Good	Good



<b>Table 1 Kinloss Landfill Site Monitoring Well Security</b>					
Observation Well	Well Protection	Well Security		Condition	
		June 2023	November 2023	June 2023	November 2023
OW7	Steel Casing and Lid	Locked	Locked	Good	Good
OW9	Steel Casing and Lid	Locked	Locked	N/A	N/A
OW11-16	Steel Casing and Lid	Locked	Locked	Good	Good
OW12	Steel Casing and Lid	Locked	Locked	Good	Good
OW13S	Steel Casing and Lid	Locked	Locked	Good	Good
OW13I	Steel Casing and Lid	Locked	Locked	Good	Good
OW13D	Steel Casing and Lid	Locked	Locked	Good	Good
OW14-14	Steel Casing and Lid	Locked	Locked	Good	Good
OW15	Steel Casing and Lid	Locked	Locked	Good	Good
OW16	Steel Casing and Lid	Locked	Locked	Good	Good

Notes: OW = Observation Well, S = Shallow, I = Intermediate and D = Deep  
 Wells OW4, OW5, OW6, OW7, OW9 & OW11 were installed by backhoe in 1985. Wells OW12 and OW13S were drilled in 1997. OW14 was drilled in 2003 and OW13I & OW13D were drilled in 2004. OW14-03 was decommissioned and replaced with OW14-14 on October 28, 2014.  
 OW9 is an inactive well on the site and is not part of the sampling program.  
 OW11-85 was decommissioned and replaced with OW11-16 on August 16, 2016.  
 OW15 and OW16 were drilled on August 15, 2016.

In addition to the monitoring wells, there are two surface water stations that are sampled semi-annually. These two stations are located on the creek immediately east of the site. SW1 is the upstream sampling location and SW2 is the downstream sampling location. The locations of both surface water stations are shown in **Map 2**, Existing Conditions.

In 2006, three gas probes were installed at the site. The locations of these three gas probes, designated GP1, GP2, and GP3, are illustrated in **Map 2**. Prior to the installation of these gas probes, methane readings were obtained from the headspace of the monitoring wells. Methane monitoring was conducted at gas probes GP1, GP2 and GP3 in February, May and September 2023. Frozen ground conditions were encountered during the February monitoring event.

In 2023, water level elevations were measured, and wells were purged and sampled, on May 16 and September 21. The samples collected during the monitoring program were transferred to coolers with ice and submitted under chain-of-custody via overnight courier to Caduceon Environmental Laboratories for analysis. The certificates of analysis and laboratory results are enclosed in **APPENDIX D**.

### 3.2 Shallow Groundwater Configuration

To determine the groundwater gradient and flow direction in 2023, water level measurements were obtained on May 16, 2023.

A summary of the water table elevation data from 1989 to 2023 is presented in appended **Table 6**. **Figure 1** is a hydrograph for monitoring wells OW13S, OW13I and OW13D. The water levels for the remaining wells are summarized in **Figure 2**. As shown in **Table 6** and **Figures 1** and **2**, there are seasonal fluctuations shown by many of the wells. In general, groundwater elevations were higher in the spring and lower in the fall. Upgradient wells OW7-85 and OW12-97, as well as OW14-14, which is screened below the waste, exhibit greater seasonal fluctuations than the other wells.

The groundwater flow system is a transporting medium for conveying potential contaminants away from the landfill area. As a result, the impact assessment of the site is dependent, to a large extent, on the groundwater flow rate, and flow pattern.

Flow in a hydrostatic unit occurs, under the influence of gravity, from points of high hydraulic potential to points of lower hydraulic potential. The actual flow path will follow a three-dimensional route along the strata of least resistance. Resistance to flow is measured in terms of the hydraulic conductivity of the deposit and the hydraulic gradient across the flow path. A cross-section of the site and borehole logs for each of the monitoring wells are enclosed in **APPENDIX C** for reference. The cross-section is also provided on **Map 4**.

As shown on the Groundwater Flow map, **Map 3**, and the Cross-Section, **Map 4**, the shallow groundwater flows in a general west to east direction below the waste. The groundwater contours are estimated based on groundwater level measurements obtained on May 15, 2023. It should be noted that the contours are considered reliable only in the vicinity of the wells; however, a reasonable interpretation of the contours can be made on the basis that the water table is generally a subdued reflection of surface topography. The flow pattern is consistent with past results. On May 15, 2023, the horizontal hydraulic gradient east of the landfill mound was observed to range from 0.021 m/m in the northeast corner to 0.008 m/m in the southeast, as shown in **Map 3**. Based on the cross-section in **Map 4**, the sand zone below the waste appears to be largely unsaturated. The capping of the landfill may be limiting infiltration. It is noted that the landfill is located on a topographic high which is limited in size.

Monitoring wells OW13S, OW13I and OW13D were constructed in close proximity to each other, which allows for the determination of vertical hydraulic gradients in this area of the site. OW13S is screened at the top of sand and gravel unit, OW13I is screened at the bottom of the sand and gravel unit, and OW13D is screened in the underlying silt till. The well logs for all three (3) wells are enclosed in **APPENDIX C**. As shown in **Table 6**, the groundwater elevations of OW13S and OW13I, and of OW13I and OW13D have only a negligible difference in

2023. During the May 15, 2023, water level monitoring, the vertical gradient was -0.031m/m (upward) between OW13S and OW13I. The vertical gradient between OW13I and OW13D on May 15, 2023 was -0.011 m/m (upward). The vertical gradient between OW13S and OW13I had been downward since monitoring began at OW13I in September 2004, and continued to remain downward until July 2008; however, since December 2008, the vertical gradient has generally been consistently upward.

### 3.3 Groundwater Monitoring Results

**Figure 3** is a summary of the spring 2023 concentrations of several indicator parameters that are commonly representative of the leachate characteristics at this site (chloride, hardness, dissolved organic carbon (DOC) and conductivity). **Figures 4a to 4g** are graphical representations for monitoring wells OW11-16 (upgradient); OW14; OW4; OW13-I; OW15 and OW16, that correspond to the primary flow path through the site. The graphs represent the concentration trend plots for the following indicator parameters: chloride, boron, barium, sulphate, ammonia, nitrate and DOC.

The entire set of leachate indicator parameters selected for this site includes alkalinity, boron, chloride, DOC, hardness, iron, nitrate, nitrite, manganese, sodium, and sulphate.

These parameters have been selected as the leachate indicator parameters for this site based on the leachate characteristics and recommendations from the MECP. The leachate indicator parameters are used to identify potential leachate impacts at downgradient monitoring locations.

Historical and current (2023) groundwater chemistry results are summarized in **APPENDIX E**.

#### 3.3.1 Background Groundwater Chemistry

To evaluate the influence of landfill leachate on the local groundwater system, it is necessary to determine background conditions. These background conditions reflect the naturally occurring levels of various parameters and provide a reference point to determine the magnitude of any leachate impacts. The background conditions reflect conditions unaffected by the landfill operation. Based on the groundwater flow configuration (**Map 3**), monitoring wells OW6, OW7 and OW12 are located upgradient or cross-gradient of the landfilled area.

In past reports, monitoring wells OW7 and OW12 have been considered as background monitors. The MECP recommended that a new background monitoring well be considered in a review of the 2006 Annual Monitoring Report (correspondence enclosed in **APPENDIX F**). The new background well was recommended due to difficulties with monitoring wells OW7 and OW12. Monitor OW7 is not an ideal background well as it is often dry during sampling events, while monitor OW12 has exhibited elevated indicator parameter concentrations with respect to the other monitoring wells. Historically, the MECP had recommended the consideration of using OW6 as a background well due to the historical groundwater quality and its cross-gradient location. The groundwater quality at OW6 relative to the other wells is illustrated in **Figure 3**. The groundwater elevations illustrated in **Map 3** confirm OW6 is in a cross-gradient location.

In August 2016, OW11-85 was decommissioned and replaced by OW11-16. The MECP reviewed the 2017 annual monitoring report (**APPENDIX F**) and approved the use of OW11-16 as the background monitoring well. OW11-16 will henceforth be referred to as the “background” monitoring well for the Reasonable Use Guideline Criteria (RUC).

As indicated above, the leachate indicator parameters selected for this site include alkalinity, boron, chloride, DOC, hardness, iron, nitrate, nitrite, manganese, sodium, and sulphate.

The results in 2023 for the leachate indicator parameters at the leachate Monitor OW4 and background Monitor OW11-16 (hereafter referred to simply as 'OW11') are summarized in the following table. As shown in the table, the concentration of each leachate indicator parameter was higher in OW4 in 2023 compared to OW11, with the exceptions of nitrate (higher at OW11) and nitrite (below detection limit at both wells).

Indicator Parameters (mg/L)	OW11 (background)		OW4 (leachate)	
	Spring 2023	Fall 2023	Spring 2023	Fall 2023
Alkalinity	357	338	690	732
Boron	0.005	0.024	0.382	0.468
Chloride	2.3	2.5	7.9	12.7
Dissolved Organic Carbon	1.0	4	9.9	15.2
Hardness	355	325	575	597
Iron	<0.005	0.006	16.7	16.2
Nitrate	2.05	1.66	<0.05	0.25
Nitrite	<0.05	<0.05	<0.05	<0.05
Manganese	<0.001	<0.001	0.606	0.616
Sodium	1.8	2.8	16.7	30.2
Sulphate	5	4	25	14

### 3.3.2 Leachate Monitoring

The analytical results from monitoring well OW4 are used to determine leachate strength and characteristics unique to the Kinloss Landfill. This well is one of the closest downgradient wells to the waste and historical monitoring data have indicated elevated concentrations of leachate indicator parameters compared to background levels.

### 3.3.3 Downgradient Groundwater Monitoring

As shown in **Map 3**, the following wells are located downgradient of the filled waste:

- OW4
- OW5
- OW13S
- OW13I
- OW13D
- OW14
- OW15
- OW16

**Figure 3a and Figure 3b** illustrate the indicator results for these wells for the spring and fall monitoring events. **Figures 4a to 4g** are plots of the following indicator results: chloride, boron, barium, sulphate, ammonia, nitrate and DOC. The plots are illustrated over time for the downgradient monitoring wells, excluding OW5, as per the MECP review of the 2017 Annual Monitoring Report (**APPENDIX F**).

Monitors OW4 and OW5 are located approximately 20 m and 50 m, respectively, downgradient of the fill area, as shown in **Map 3**. As shown in **Figures 3a and 3b**, the leachate indicator parameters for OW4 are generally similar to the concentrations at OW14, which is screened below the waste. The exception is chloride, where the concentration at OW14 is considerably higher compared to OW4. The OW4 concentrations are also similar to a number of other downgradient wells, but elevated compared to OW5. Leachate impacts are not unexpected at OW4 as the well is located immediately downgradient of the landfill mound (**Map 3**). As shown in **Figure 4a**, the concentration of chloride has been decreasing over time at OW4 since 2004, with occasional fluctuations, indicating leachate strength may be decreasing with time. The concentrations of conductivity and sodium have also decreased over time at OW4, and the DOC concentrations have decreased overall since 2002, with fluctuations over time. The results for OW5 are generally similar to background wells OW6 and OW11, indicating that leachate impacts have not migrated to the north or northeast.

In 2014, OW14-03 was replaced with OW14-14 and extended below the waste fill until it intersected the lower fall water table. OW14 is screened in silty fine sand. **Figures 3a and 3b** illustrates the May and September 2023 results for OW14-14 plotted against other wells. As shown in **Figures 3a and 3b**, the results for OW14-14 are higher than background (OW6 and OW11) but similar to downgradient well OW4 for the main leachate parameters, excluding chloride. As indicated above, the chloride concentrations at OW14 are considerably elevated compared to OW4. The 2007 to 2023 results for OW14 (**APPENDIX E**) indicate parameter concentrations are elevated relative to background concentrations. Based on the overall results, landfill impacts are present at monitor OW14.

As shown in the Cross-Section (**Map 4**), OW13S is screened at the top of the sand and gravel unit, OW13I is screened at the bottom of the sand and gravel unit, and OW13D is screened in the underlying silt till. Historically, leachate impacts in the silt till unit (at OW13D) are negligible. Continued monitoring will confirm the long-term trend at this location. The monitoring results for OW13D indicate near-background concentrations for leachate parameters and, as such, leachate does not appear to be impacting the silt till layer underlying the super-positioned landfill and sand overburden aquifer.

OW13S and OW13I continue to show elevated levels of several leachate indicator parameters compared to background groundwater quality.

Based on the interpreted slightly upward hydraulic gradient and the reported leachate parameter concentrations at OW13D, any leachate impacts in that area of the site are likely primarily moving in a near horizontal direction with no discernible impacts in the underlying silt till. It is also noted that the interpreted horizontal hydraulic gradient in the southeast area of the site is also relatively low (0.011 m/m as stated in **Section 3.2**). The groundwater migration in general will be relatively low in velocity.

Wells OW15 and OW16 are located in the buffer lands east of the OW13 nest. Elevated concentrations of leachate indicator parameters chloride, hardness, and conductivity (Spring 2023) and hardness and DOC (Fall 2023) compared to background and downgradient groundwater quality are observed at OW15. The DOC concentration at well OW15 was historically high in the fall of 2023. The leachate indicator parameter

concentrations at OW16 in 2023, however, are similar to background, with the exceptions of hardness (spring and fall), which are elevated compared to background but notably lower compared to OW15.

The MECP provided correspondence regarding the groundwater monitoring program on August 20, 2015. As part of this correspondence, an August 14, 2015, memorandum from MECP hydrogeologist, Mr. Simon Thuss, was forwarded to the Township. WSP responded to this memorandum on October 8, 2015. The comments brought forward in MECP correspondence have been largely addressed in WSP's response, with the exception being the reassessment of reasonable use criteria, which is discussed in **Section 3.5** of this report. In 2016, the Township completed the installation and deepening of wells discussed in correspondence in August 2016.

Topographic survey data are not available at the Kinloss Waste Disposal Site. WSP recommends that a topographic survey be completed to support the amendment to the ECA, including information related to the CAZ, and that the elevations of the groundwater monitoring network are included as part of this work. Previously, topographic surveys had not been completed due to the temporary closure of the site in 2002.

### 3.4 Surface Water Monitoring

Surface water samples were obtained on May 15 and September 21, 2023, at the two surface water stations. Both surface water stations are located on the creek adjacent to the eastern boundary of the site. This creek flows in a northerly direction and is a tributary of Kinloss Creek. Station SW1 is upstream of the landfill and is located at the south end of the culvert under Concession Road 5/6, as shown in **Map 2**. Station SW2 is downstream of the landfill and is located approximately 150 m north of the northeast corner of the site.

The results of the 2007 to 2023 surface water sampling are summarized in the Surface Water Results (**APPENDIX G**). The laboratory detection limits and Provincial Water Quality Objectives (PWQO) are also included in the summaries. Exceedances of PWQO are indicated by shaded cells. **Figure 5** compares leachate indicators for the May 15, 2023, sampling event.

The upstream station, SW1, showed an exceedance of the PWQO for total iron (507 ug/L) and total zinc (48 ug/L) in the fall 2023 sampling event. There were no PWQO exceedances related to SW2 in either the spring or fall 2023 sampling events. Historically, there have been some exceedances of the PWQO at both the upgradient and downgradient monitoring stations related to metals parameters, but there is no trend toward increasing concentrations of leachate indicator parameters. These results indicate that the landfill does not have a measurable adverse influence on water quality within the creek.

### 3.5 Reasonable Use

In accordance with the appropriate Reasonable Use Guideline criteria (RUC) for particular reasonable uses, a change in quality of the groundwater on an adjacent property will be accepted only as follows:

*The quality cannot be degraded by an amount in excess of 50% of the difference between background and the Ontario Drinking Water Standards for non-health related parameters and in excess of 25% of the difference between background and the Ontario Drinking Water Standards for health-related parameters. Background is considered to be the quality of the groundwater prior to any man-made contamination.*

In assessing the amount of degradation that is acceptable, consideration is given to the natural, uncontaminated quality of the water, the present quality of the groundwater and potential contamination of the groundwater from all sources.

The maximum concentration of a particular contaminant that would be acceptable in the groundwater beneath an adjacent property is calculated in accordance with the following relationship.

$$C_m = C_b + x (C_r - C_b)$$

Where  $C_m$  = maximum concentration accepted

$C_b$  = background concentration

$C_r$  = maximum concentration permitted in accordance with the Ontario Drinking Water Standards.

$x$  = a constant that reduces the contamination to a level that is considered by the MECP to have a negligible effect on the water use (i.e., 0.5 for non-health related parameters; 0.25 for health related parameters).

The MECP Landfill Guidelines state the following regarding establishing Background Concentration: *The background concentration of a contaminant in the ground water of receptor aquifer is the median value for that contaminant based on all ground water samples taken from the receptor aquifer in accordance with the following rules:*

- 1) *At least five samples must be taken.*
- 2) *The samples must be taken at or near the site boundary where potential impact is being examined.*
- 3) *The samples must not be taken from locations known to be or likely to be contaminated by human activity.*

Monitor OW11-16 meets the above requirements. In order to determine potential Reasonable Use parameters, the median values of the following parameters (all within Ontario Drinking Water Standards (ODWS)) were calculated using concentrations reported since 2007:

- Alkalinity
- Boron
- Chloride
- Dissolved Organic Carbon (DOC)
- Sodium

In their August 14, 2015, memorandum (**APPENDIX F**), the MECP recommended the inclusion of hardness, iron, manganese, sulphate, nitrate, and nitrite in the RUC annual evaluation.

The leachate indicator parameters now selected for this site include alkalinity, boron, chloride, DOC, hardness, iron, nitrate, nitrite, manganese, sodium, and sulphate.

The Township understands the intent of the RUC evaluation as a tool to determine if groundwater downgradient of the landfill is being impacted beyond reasonable criteria. At the Kinloss Waste Disposal Site, the RUC evaluation is being used to determine the extent of leachate migration off-site.

Correspondence from the MECP was received August 18, 2016, regarding the MECP review of the “Annual Monitoring Report – 2015, Kinloss Landfill Site”. A copy of this letter is provided in **APPENDIX F**. The MECP continues to recommend that additional parameters (including at least hardness, manganese, and sulphate) be included in the RUC annual evaluation.

In August 2016, a new upgradient background monitor (OW11-16) was drilled. Additionally, two new monitors, OW15 and OW16, were drilled (east of the OW13 nest) in the buffer lands to further define the extent of the leachate plume at the Kinloss Landfill Site.

The results of the RUC evaluation for 2023 have been summarized in **Table 7** using OW11-16 to represent the background concentration conditions, which was decided upon in correspondence between WSP and the MECP dated December 13, 2018 (**APPENDIX F**). It is noted that the requirement for a landfill site to be in compliance with the RUC applies to groundwater quality at the property boundary (OW13 nest, OW15 and OW16). Monitor OW11-16 now satisfies the requirements for a suitable background concentration, as at least five samples have been collected from the well. The parameters hardness, manganese and sulphate have been included in the assessment.

**Table 7** has been updated using the OW11-16 monitoring data from 2016 to 2023.

The RUC exceedances are shaded in **Table 7**. As shown in **Table 7**, the groundwater concentrations at monitoring wells OW13S, OW13I and OW15 exceeded the RUC for alkalinity, DOC, hardness and manganese during both spring and fall monitoring events. OW15 also exceeded the RUC for iron in the spring and fall monitoring events and sulphate during the spring. The groundwater quality at OW13D exceeded the RUC for DOC and iron in September 2023. OW16 exceeded the RUC for DOC and manganese in May and September and iron during the September monitoring event. .

In 2023, concentrations of RUC parameters remained elevated at OW13S and OW13I. OW13S and OW13I continue to be influenced by leachate, as evidenced by the elevated leachate indicator parameter concentrations and RUC exceedances. Continued monitoring is recommended to confirm the long-term trend at this location. The shallow aquifer in the southeast corner of the property remains influenced by leachate. Monitor OW13D does not appear to be influenced by leachate, which is likely a result of the fine soil conditions and upward gradient below the Kinloss Waste Disposal Site. Only DOC and iron concentrations exceeded the RUC at OW13D in 2023, which is consistent with historic results and likely representative of natural groundwater conditions in the till.

RUC exceedances related to DOC, iron and manganese occurred at least once in 2023 at wells OW15 and OW16. Additionally, RUC exceedances related to sulphate (spring only), alkalinity, and hardness occurred at OW15. , A leachate influence is likely occurring at OW15 and OW16, although the leachate indicator parameter concentrations are considerably higher at OW15 compared to the slightly further downgradient OW16.

As shown in **Map 2**, there are substantial buffer lands downgradient of OW13S, which are leased by the Township. In its review of the 2006 Annual Monitoring Report, the MECP requested additional information regarding the buffer property. The following section provides additional information and discussion on leachate impacts within this area.

### 3.6 Buffer Lands

In its review of the 2006 Annual Monitoring Report, the MECP asked the following question regarding the buffer lands:



*Are the lands to the east leased by the Township a part of a formal Contaminant Attenuation Zone?*

The buffer lands are shown in **Map 2**. The lands are approximately 12.1 hectares (30 acres) in area and are located on Part Lot 17, Concession 6, former Township of Kinloss, County of Bruce.

These buffer lands provide approximately 130 m of downgradient property to allow for additional leachate attenuation before the groundwater migrates off Township controlled property.

**APPENDIX H** contains a copy of the legal agreement between the Township and the owners of the buffer lands. A copy of the Certificate of Registration, lease agreement and legal survey are enclosed in **APPENDIX H**. The lease agreement allows the lands to be used for contaminant attenuation. Access to the property for monitoring purposes is permitted through the agreement. The lease agreement was in effect as of January 1, 1999, and has a 99-year term.

Therefore, the buffer lands east of the landfill site meet the requirements of a formal CAZ.

Correspondence from the MECP on August 14, 2015, acknowledged WSP’s identification of leachate impacts at the site boundary in wells OW13S and OW13I. This correspondence also noted that since leachate has been identified within the CAZ, the Township must work to delineate the plume within the CAZ and ensure that it remains confined within this area.

In August 2016, the Township installed additional wells (OW15 and OW16) within the CAZ. These wells are used to define the extent of the plume within the CAZ and assess the potential for leachate migration beyond the boundaries of the CAZ.

As noted previously, the Township is working on an ECA amendment application that will include the status of the Kinloss Landfill as temporarily closed, as well as the presence of the formal CAZ on the buffer lands east of the landfill site.

**3.7 Combustible Gas**

In 2006, three gas probes were installed on-site to allow for the monitoring of combustible gas in the unsaturated overburden. The locations of these three gas probes, designated GP1, GP2, and GP3, are illustrated in **Map 2**.

The combustible monitoring results for 2007 to 2023 have been included in **Table 3**.

<b>Table 3</b>			
<b>Summary of Methane Monitoring Results</b>			
<b>Date</b>	<b>GP1</b>	<b>GP2</b>	<b>GP3</b>
<b>July/07</b>	0	0	0
<b>Jan/08</b>	0	0	0
<b>Jul/ 08</b>	0	0	0
<b>Jan/09</b>	0	0	0
<b>Dec/09</b>	0	0	0
<b>Mar/10</b>	0	0	0
<b>Feb/11</b>	0	0	0
<b>Mar/12</b>	0	0	0
<b>Feb/13</b>	0	0	0

<b>Table 3</b>			
<b>Summary of Methane Monitoring Results</b>			
<b>Date</b>	<b>GP1</b>	<b>GP2</b>	<b>GP3</b>
<b>Jan/14</b>	0	0	0
<b>May/15</b>	0	0	0
<b>Oct/15</b>	0	0	0
<b>Feb/16</b>	0	0	0
<b>June/16</b>	0	0	0
<b>Nov/16</b>	0	0	0
<b>Feb/17</b>	0	0	0
<b>Jun/17</b>	0	0	0
<b>Nov/17</b>	0	0	0
<b>Feb/18</b>	0	0	0
<b>May/18</b>	0	0	0
<b>Nov/18</b>	0	0	0
<b>Feb/19</b>	0	0	0
<b>June/19</b>	0	0	0
<b>Nov/19</b>	0	0	0
<b>Feb/20</b>	0	0	0
<b>July/20</b>	0	0	0
<b>Nov/20</b>	0	0	0
<b>Feb/21</b>	0	0	0
<b>June/21</b>	0	0	0
<b>Nov/21</b>	0	0	0
<b>Feb/22</b>	0	0	0
<b>June/22</b>	0	0	0
<b>Nov/22</b>	0	0	0
<b>May/23</b>	0	0	0
<b>Sept/23</b>	0	0	0
<b>Feb/23</b>	0	0	0

**Notes:** 1. All readings shown in % gas by volume in air.

The principal combustible gas associated with municipal landfills is methane. Since methane is less dense than air, methane typically migrates upwards from the refuse into the unsaturated soil cover and dissipates by venting to the atmosphere. During periods of frost and/or snow cover, venting is reduced or inhibited, and the primary direction of methane migration is lateral.

Based on the monitoring results, there is no indication of combustible gas migration within the unsaturated overburden at the site.

#### **4.0 PROPOSED FUTURE MONITORING PROGRAM**

A summary of the proposed monitoring program is presented in **Table 4**. This proposed program is based on the program required under the current ECA for the site. The parameters outlined in **Table 4** include the leachate indicator parameters selected for this site: alkalinity, boron, chloride, DOC, hardness, iron, nitrate, nitrite,

manganese, sodium, and sulphate, as well as additional parameters to characterize the quality and extent of the leachate plume. If changes in leachate characteristics are observed in the future, this list of parameters can be modified.

<b>Table 4 Kinloss Landfill Site Monitoring Program</b>		
<b>Monitoring Location</b>	<b>Proposed Sampling Spring 2024</b>	<b>Proposed Sampling Fall 2024</b>
OW4	✓	✓
OW5	✓	✓
OW6	✓	✓
OW7	✓	✓
OW11-16	✓	✓
OW12	✓	✓
OW13S	✓	✓
OW13I	✓	✓
OW13D	✓	✓
OW14-14	✓	✓
OW15	✓	✓
OW16	✓	✓
SW1	✓	✓
SW2	✓	✓

**Notes:**

1. ✓ indicates to be sampled.
2. The laboratory parameter suites for groundwater and surface water samples will include:
  - Alkalinity
  - Ammonia
  - Anions – Cl, NO<sub>2</sub>, NO<sub>3</sub>, SO<sub>4</sub>
  - Conductivity
  - Dissolved metals by ICPMS (include boron, iron, manganese, sodium)
  - Total phosphorus (SW only)
  - DOC
  - Hardness
  - Phenols
  - pH
  - TKN
3. At all monitoring wells and SW stations the following field measurements should be obtained:
  - Temperature
  - pH
  - Conductivity
4. In addition, methane measurements from GP1, GP2 and GP3 will be obtained in spring, fall and once under frozen conditions.

## 5.0 CONCLUSIONS

- 1) Currently, the Kinloss Landfill site is only accepting recyclable and burnable materials. The site does not receive domestic waste.
- 2) The Kinloss Landfill site is temporarily closed and has an estimated remaining capacity of 137,000 m<sup>3</sup>. The Township plans to re-open the site to accept municipal waste when the capacity of the Huron Landfill is expended (remaining site life estimated at approximately 7 years ).
- 3) Burning operations in 2023 were conducted in accordance with MECP Guideline C-7.
- 4) Security and control of the site in 2023 continued to be successful.
- 5) The Blue Box Recycling Program diverted 404 tonnes of recyclable materials and approximately 200 tonnes of scrap metal, tires, E-waste and mattresses from the Township of Huron-Kinloss. Including all of the segregated waste, a total of 604 tonnes of materials were diverted from both Township landfills (Kinloss and Huron) in 2023.
- 6) In 2023, horizontal groundwater flow on the site was to the east, which is consistent with historical results. A slight upward vertical gradient is present.
- 7) Leachate influences are observed in the shallow aquifer downgradient of the landfill (OW4, OW13S, OW13I, OW15, OW16). Leachate influences are not observed in the silt till underlying the sand and gravel aquifer (OW13D).
- 8) Surface water monitoring indicates the downstream (SW2) water quality east of the landfill is comparable to the upstream (SW1) water quality. For the parameters that were analyzed, PWQO exceedances related to total iron and zinc (SW1) occurred in September 2023. There were no PWQO exceedances in the downstream station SW2 in 2023. It is interpreted that the landfill site does not have a measurable adverse influence on water quality within the creek.
- 9) Reasonable Use parameters and criteria have been developed based on the background results of monitor OW11-16. RUC exceedances related to alkalinity, DOC, hardness and manganese were observed at OW13S, OW13I and OW15. At OW13D, RUC exceedances related to DOC and iron in September 2023 and are attributed to natural groundwater conditions. OW15 also exceeded the RUC for iron in spring and fall 2023. Additionally, DOC and manganese concentrations exceeded the RUC at OW16 in May and September and iron during the September monitoring events.
- 10) Combustible gas monitoring indicates no evidence of the presence of methane gas within the unsaturated overburden at the site.

## 6.0 RECOMMENDATIONS

Based on the foregoing, the following is recommended.

- 1) No remedial measures are required for the site at the present time.
- 2) The monitoring program of semi-annual sampling of the 12 monitoring wells and two surface water stations should continue in 2024. Gas probes GP1, GP2 and GP3 should also continue to be monitored for the presence of combustible gas, including under frozen conditions.

- 3) This report is to be submitted to the MECP for review and comment by March 31, 2024.
- 4) The Township should proceed with the application to amend the current ECA for the site. WSP recommends the following steps.
  - a) Complete a topographic survey of the site, including the CAZ boundaries and tying in the monitoring well network to a geodetic reference point (in metres above sea level).
  - b) Apply for an amendment to the existing ECA for the site, including details related to the temporary closure of the site, estimated remaining site capacity and the CAZ.

## Signature Page

**WSP Canada Inc.**



Kaurel Tamasauskas  
*Environmental Technologist, Earth & Environment*



Jenna McVitty M.A.Sc., P.Eng.  
*Team Lead, Senior Engineer*

KT/JM/kt

## Tables

<b>TABLE 5 SUMMARY OF RECYCLING DATA HURON and KINLOSS LANDFILLS</b>										
Recyclable Product	2019		2020		2021		2022		2023	
	Weight (Tonnes)	Volume Saved (m <sup>3</sup> )	Weight (Tonnes)	Volume Saved (m <sup>3</sup> )	Weight (Tonnes)	Volume Saved (m <sup>3</sup> )	Weight (Tonnes)	Volume Saved (m <sup>3</sup> )	Weight (Tonnes)	Volume Saved (m <sup>3</sup> )
Newspaper	130.31	260.62	128.74	257.48	99.79	199.58	49.60	99.20	79.68	159.36
Steel (Cans, etc.)	27.57	55.14	32.66	65.32	31.38	62.76	15.60	31.20	25.39	50.78
Aluminum	8.51	17.02	16.00	32.00	16.41	32.82	8.16	16.32	17.22	34.44
Glass (Flint & Coloured)	56.33	112.66	80.74	161.48	73.00	146.00	36.28	72.56	80.95	161.90
Plastic (HDPE & PET)	63.52	127.04	76.25	152.50	78.10	156.20	38.81	77.62	35.67	71.34
White Paper	4.45	8.90	3.15	6.30	6.77	13.54	3.37	6.74		0.00
Boxboard	44.62	89.24	44.65	89.30	54.97	109.94	27.32	54.64	62.31	124.62
Corrugated Cardboard	94.48	188.96	94.26	188.52	107.12	214.24	44.52	89.04	102.99	205.98
<b>Total Recyclables</b>	<b>429.79</b>	<b>859.58</b>	<b>476.45</b>	<b>952.90</b>	<b>467.54</b>	<b>935.08</b>	<b>223.66</b>	<b>447.32</b>	<b>404.21</b>	<b>808.42</b>
Tires	63.13	126.26	110.50	221.00	135.38	270.76	69.71	139.42	29.11	58.22
Scrap Metal	167.96	335.92	148.35	296.70	177.77	355.54	150.59	301.18	128.20	256.40
Bale Wrap	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	3.75	7.50
E-waste	14.95	29.90	11.37	22.74	8.36	16.72	11.45	22.90	20.93	41.86
Mattresses	15.88	31.76	17.17	34.34	35.29	70.58	53.34	106.68	18.26	36.52
<b>Total Segregated</b>	<b>261.92</b>	<b>523.84</b>	<b>287.39</b>	<b>574.78</b>	<b>356.80</b>	<b>713.60</b>	<b>285.09</b>	<b>570.18</b>	<b>200.25</b>	<b>400.50</b>
<b>Total Diverted</b>	<b>691.71</b>	<b>1383.42</b>	<b>763.84</b>	<b>1527.68</b>	<b>824.34</b>	<b>1648.68</b>	<b>508.75</b>	<b>1017.50</b>	<b>604.46</b>	<b>1208.92</b>
Notes:	<ol style="list-style-type: none"> <li>1. Data obtained from BASWRA and Township.</li> <li>2. Assumed compaction density is 500 kg/m<sup>3</sup>.</li> <li>3. Tires are converted to a volume by a factor of 8 tires/m<sup>3</sup>.</li> <li>4. Recyclable tonnages are for the entire Township excluding Lucknow.</li> <li>5. Tonnages of scrap metal and tires are combined totals for Kinloss and Huron Landfills.</li> <li>6. 3,308 tires received in 2023, weights provided by e-tracks (AOR)</li> <li>7. 537 mattresses received in 2023 at 29.4 mattresses/tonne</li> <li>8. Volume Saved - defined as waste diverted from the landfill through recycling programs.</li> </ol>									



**TABLE 6**  
**Summary of Groundwater Elevations**  
**Kinloss Landfill**

	OW4	OW5	OW6	OW7	OW11-16	OW12	OW13S	OW13I	OW13D	OW14	OW15	OW16
<b>Ground Elevation (m)</b>	81.1	80.3	79.7	83	96.18	97.9	80.4	80.4	80.4	91.9	80.00	79.99
<b>Top of Casing (m)</b>	81.3	80.5	80	83.2	96.98	98.7	81.2	81.1	81.1	92.8	81.01	80.83
<b>Date of Water Level Measurement</b>												
<b>Nov-85</b>	80.89	80.21	79.6	82.21								
<b>Dec-87</b>	80.61	80.33	79.61	82.57								
<b>Nov-89</b>	80.66	80.25	79.53	81.86								
<b>Dec-89</b>	80.51	80.25	79.56	81.95								
<b>Aug-90</b>	80.34	79.88	79.16	81.34								
<b>Jan-91</b>		80.31	79.6									
<b>Apr-91</b>	80.77	80.41	79.61	82.66								
<b>Jun-91</b>	80.73	80.29	79.58	81.76								
<b>Oct-91</b>	80.59	80.17	79.56	81.35								
<b>Jul-92</b>	80.48	80.04	79.13	81.52								
<b>Oct-92</b>	80.55	79.97	79.49	81.84								
<b>Jun-93</b>	80.67	80.08	79.5	81.69								
<b>Sep-93</b>	80.45	79.95	79.46	81.18								
<b>Jun-94</b>	80.65	80.03	79.51	81.97								
<b>Oct-94</b>	80.52	79.97	79.47	81.66								
<b>May-95</b>	80.56	80.02	79.44	81.81								
<b>Sep-95</b>	80.37	79.92	79.23	81.54								
<b>May-96</b>	80.9	80.32	79.63	82.78								
<b>Sep-96</b>	80.77	80.11	79.53	81.56								
<b>May-97</b>	80.82	80.18	79.57	82.17								
<b>Sep-97</b>	80.52	80.06	79.38	81.18		81.45	80.16					
<b>May-98</b>	80.71	80.09	79.33	81.74		82	80.25					
<b>Sep-98</b>	80.28	80.13	78.99	DRY		81	79.99					
<b>May-99</b>	80.56	80.05	79.4	81.8		81.09	80.19					
<b>Sep-99</b>	79.95	79.51	78.66	DRY		80.57	79.86					
<b>May-00</b>	80.52	79.96	79.35	81.91		81.09	80.15					
<b>Sep-00</b>	80.73	80.14	79.5	82.01		81.45	80.22					
<b>May-01</b>	80.84	80.19	79.49	81.83		82.53	80.28					
<b>Sep-01</b>	80.44	79.9	79.26	DRY		81.36	80.12					
<b>May-02</b>	80.84	79.86	79.28	82.11		82.51	80.31					
<b>Sep-02</b>	80.15	79.55	78.91	DRY		81.31	79.94					
<b>May-03</b>	80.79	80.11	79.56	82.43		81.23	80.3					
<b>Oct-03</b>	80.62	80.04	79.52	81.87		80.96	80.22			80.8		
<b>May-04</b>	80.82	80.11	79.63	82.37		82.52	80.28			81.68		
<b>Sep-04</b>	80.35	79.82	79.02	81.22		81.44	80.12	80.09	80.12	81.04		
<b>May-05</b>	80.58	80.04	79.43	81.89		81.89	80.32	80.26	80.31	81.4		
<b>Sep-05</b>	80.42	80.02	79.38	DRY		80.93	80.22	80.16	80.14	DRY		
<b>Apr-06</b>	80.72	80.19	79.48	82.57		82.32	80.39	80.35	80.41	81.61		
<b>Oct-06</b>	80.35	79.97	79.41	DRY		81	80.21	80.15	80.09	80.7		
<b>Jul-07</b>	NA	79.36	77.95	81.18		81.62	80.02	79.67	79.83	81.18		
<b>Dec-07</b>	80.68	79.69	79.2	DRY		80.53	79.9	79.89	80.01	80.42		
<b>Jul-08</b>	80.42	79.62	79.06	81.74		81.94	80.02	79.83	80.15	81.44		
<b>Dec-08</b>	80.66	80.04	79.47	82.34		81.44	80.2	80.24	80.28	DRY		
<b>Jul-09</b>	80.48	79.71	79.19	81.62		82.32	80.17	80.28	80.25	81.66		
<b>Dec-09</b>	80.47	80.07	79.15	81.98		80.82	80.15	80.28	80.24	DRY		
<b>Mar-10</b>	80.69	80.15	79.56	82.35		81.14	80.25	80.23	80.36	80.97		
<b>Jun-11</b>	80.67	79.88	79.40	81.76		82.15	80.25	80.36	80.38	81.57		
<b>Oct-11</b>	80.50	80.15	79.50	Dry		80.80	80.18	80.28	80.26	80.81		
<b>Jun-12</b>	80.32	79.78	79.12	81.47		81.42	80.05	80.14	80.16	81.06		
<b>Oct-12</b>	80.25	80.07	79.38	Dry		80.53	80.06	80.13	80.10	80.30		
<b>Jun-13</b>	80.58	80.17	79.46	81.83		82.13	80.26	80.35	80.39	81.55		
<b>Nov-13</b>	80.68	80.04	79.55	82.66		81.24	80.31	80.40	80.41	81.10		
<b>Jul-14</b>	80.66	79.99	79.51	81.71		82.33	80.31	80.40	80.41	81.66		
<b>Oct-14</b>	80.75	80.33	79.57	81.92		81.39	80.31	80.39	80.38	81.02		
<b>May-15</b>	80.61	79.94	79.41	81.82		81.78	80.25	80.34	80.35	81.32		
<b>Oct-15</b>	80.22	79.87	79.35	Dry		80.73	80.06	80.13	80.10	80.53		
<b>Jun-16</b>	80.53	79.77	79.16	81.68		82.20	80.17	80.26	80.30	81.54		
<b>Nov-16</b>	80.28	79.86	79.23	Dry	80.44	80.72	80.02	80.10	80.09	80.52	79.91	79.66
<b>Jun-17</b>	80.48	79.84	79.23	81.81	81.55	81.88	80.19	80.27	80.32	81.36	79.95	79.79
<b>Nov-17</b>	80.51	80.04	79.53	81.83	80.82	81.11	80.23	80.31	80.30	80.83	79.99	79.86
<b>May-18</b>	80.67	80.11	79.43	81.94	82.06	82.45	80.32	80.40	80.44	81.70	79.98	79.93
<b>Nov-18</b>	80.47	80.14	79.51	81.62	80.73	81.04	80.23	80.31	80.28	80.77	79.98	79.90
<b>Jun-19</b>	80.71	80.11	79.52	81.96	81.91	82.27	80.34	80.42	80.45	81.62	80.01	79.92
<b>Nov-19</b>	80.47	80.09	79.51	81.46	80.65	80.92	80.22	80.30	80.27	80.73	79.97	79.95
<b>Jul-20</b>	80.33	79.72	79.04	81.55	81.14	81.45	80.2	80.15	80.16	81.08	79.84	79.82
<b>Nov-20</b>	80.40	80.05	79.46	81.12	80.45	80.70	80.17	80.25	80.23	80.55	79.91	79.88
<b>Jun-21</b>	80.34	79.78	79.09	81.62	81.04	81.33	80.09	80.17	80.21	81.00	79.85	79.87
<b>Nov-21</b>	80.50	80.21	79.55	82.20	80.58	80.75	80.25	80.33	80.30	80.59	79.95	79.94
<b>Jun-22</b>	80.57	79.93	79.32	81.76	81.66	81.99	80.25	80.27	80.35	81.43	79.82	79.78
<b>Nov-22</b>	80.35	80.03	79.44	81.49	80.63	80.91	80.15	80.21	80.20	80.68	79.89	79.87
<b>May-23</b>	80.67	80.21	79.48	82.02	81.71	82.00	80.30	80.39	80.42	81.44	79.93	79.97
<b>Sep-23</b>	80.30	79.95	79.26	81.43	80.82	81.14	80.10	80.17	80.17	80.82	79.84	79.85

Note: Elevations are not geodetic and relate to an inferred benchmark.

**Table 7**  
**Reasonable Use Criteria - New Background Upgradient Monitor OW11-16**  
**Kinloss Landfill**


Chemical Parameter	Standard / Objective	Type	Reference		RUC										
			Average	n		OW13S		OW13I		OW13D		OW15		OW16	
						May-23	Sep-23	May-23	Sep-23	May-23	Sep-23	May-23	Sep-23	May-23	Sep-23
Alkalinity	30 - 500	OG	322	13	411	445	526	593	545	243	265	493	450	295	311
Boron	5	IMAC	0.014	13	1.3	0.449	0.515	0.550	0.534	0.043	0.07	0.313	0.075	0.008	0.018
Chloride	250	AO	3.8	13	127	7	10.2	15.7	12.4	7.1	7.8	55	6.6	7.7	6.9
DOC	5	AO	1.8	13	3.4	4.4	8.7	5.8	9.3	2.0	3.6	4.4	22.0	4.6	8.3
Iron	0.3	AO	0.0173846	13	0.16	<0.005	0.006	<0.005	<0.005	0.066	0.458	0.427	2.49	0.052	0.177
Hardness	80-100	OG	362	13	362 *	463	508	601	538	221	243	680	439	300	327
Manganese	0.05	AO	0.002	13	0.026	0.127	0.218	0.305	0.241	0.016	0.015	0.374	0.404	0.108	0.193
Sulphate	500	AO	6	13	253	90	76	101	90	48	51	256	3	15	16

**Notes:**


1. Result concentrations reported in mg/L, unless otherwise indicated.
2. Shaded cell indicates parameter exceeded RUC.
3. Standard/Objective determined from Ontario Drinking Water Standards, Objectives and Guidelines (Revised June 2006).
4. OG = Operational Guideline  
AO = Aesthetic Objective  
IMAC = Interim Maximum Acceptable Concentration
5. Reference average based on the average concentrations for reference monitor OW11-16 since 2016.  
n - Indicates number of sample results included in the calculation of the reference average.
6. \* indicates reference concentration used as RUC since reference concentration is greater than the Standard/Objective.

## Figures


**FIGURE 1**  
**HYDROGRAPH - OW13**  
**KINLOSS LANDFILL**




**FIGURE 2**  
**HYDROGRAPH (excluding OW13)**  
**KINLOSS LANDFILL**




**FIGURE 3a**  
**INDICATOR PARAMETERS - SPRING 2023 - MONITORING WELLS**  
**KINLOSS LANDFILL**



**FIGURE 3b**  
**INDICATOR PARAMETERS - FALL 2023 - MONITORING WELLS**  
**KINLOSS LANDFILL**




**FIGURE 4a**  
**CHLORIDE VS TIME - PRELIMINARY FLOW PATH MONITORING WELLS**  
**KINLOSS LANDFILL**







**FIGURE 4b**  
**BORON VS TIME - PRELIMINARY FLOW PATH MONITORING WELLS**  
**KINLOSS LANDFILL**




**FIGURE 4c**  
**BARIUM VS TIME - PRELIMINARY FLOW PATH MONITORING WELLS**  
**KINLOSS LANDFILL**




**FIGURE 4d**  
**SULPHATE VS TIME - PRELIMINARY FLOW PATH MONITORING WELLS**  
**KINLOSS LANDFILL**




**FIGURE 4e**  
**AMMONIA VS TIME - PRELIMINARY FLOW PATH MONITORING WELLS**  
**KINLOSS LANDFILL**




**FIGURE 4f**  
**NITRATE VS TIME - PRELIMINARY FLOW PATH MONITORING WELLS**  
**KINLOSS LANDFILL**



**FIGURE 4g**  
**DOC VS TIME - PRELIMINARY FLOW PATH MONITORING WELLS**  
**KINLOSS LANDFILL**





**FIGURE 5**  
**INDICATOR PARAMETERS - MAY 2023- SURFACE WATER**  
**KINLOSS LANDFILL**



Maps






SOURCE: MAPART CORP. 1:250,000 MAP OF WEST CENTRAL ONTARIO 1990/1991

## REGIONAL LOCATION MAP KINLOSS LANDFILL SITE TOWNSHIP OF HURON-KINLOSS



1450 1st Ave W. Suite 101, Owen Sound ON, N4K 6W2  
Telephone: (519) 376-7612 / Fax: (519) 376-8008  
Toll Free: 1-888-376-7612

DESIGN	-----
DRAWN	T C G
APPROVED	J L M
DATE	MARCH 2024
SCALE	1 : 200,000
FILE No.	121-60018-16
FIG. No.	<b>MAP 1</b>



**LEGEND**

- OW 6-85**  
OBSERVATION WELL LOCATION
- OW 1-85**  
INACTIVE OR DECOMMISSIONED WELL LOCATION
- SW1**  
APPROXIMATE LOCATION OF SURFACE WATER SAMPLE
- GP 2**  
LOCATION OF GAS PROBE
- 3 ha AREA PURCHASED DECEMBER, 1989**  
APPROXIMATE TOTAL SITE BOUNDARY
- APPROXIMATE EXTENT OF REFUSE**
- APPROXIMATE EXTENT OF REFUSE**

**NOTES:**


1. INFORMATION ON THIS DRAWING DERIVED FROM DRAWINGS CONTAINED IN THE TOWNSHIP OF HURON-KINLOSS 2006 ANNUAL OPERATIONS AND MONITORING REPORT, KINLOSS LANDFILL SITE PREPARED BY R.J. BURNSIDE & ASSOCIATES LIMITED.
2. LANDS DESCRIBED AS PART OF LOT 17, CONCESSION 6, FORMER TOWNSHIP OF KINLOSS, COUNTY OF BRUCE (PART 3, PLAN 3R-4858), LEASED BY THE TOWNSHIP OF KINLOSS (NOVEMBER 30, 1989), TOTALING 12.26 ha (30.3 Acres)
3. WASTE NO LONGER ACCEPTED AT KINLOSS LANDFILL SITE. ONLY RECYCLABLES AND BURNABLE MATERIALS ACCEPTED. CURRENT FILLING AREA USED FOR DISPOSAL OF BURN PIT ASHES.
4. CORRECTED SITE BOUNDARIES PROVIDED BY THE TOWNSHIP OF HURON-KINLOSS.

THE CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS. DO NOT SCALE THE DRAWING - ANY ERRORS OR OMISSIONS SHOULD BE REPORTED TO WSP. THE COPYRIGHTS TO ALL DESIGNS AND DRAWINGS ARE THE PROPERTY OF WSP. REPRODUCTION OR USE FOR OTHER THAN THAT AUTHORIZED BY WSP IS FORBIDDEN.

<b>EXISTING CONDITIONS MAP KINLOSS LANDFILL SITE TOWNSHIP OF HURON-KINLOSS</b>	
<b>DESIGN</b>	
<b>DRAWN</b>	TCG
<b>APPROVED</b>	J L M
<b>DATE</b>	MARCH 2024
<b>SCALE</b>	1 : 2,500
<b>FILE No.</b>	121-60018-16
<b>FIG. No.</b>	<b>MAP 2</b>

1450 1st Ave W, Suite 101, Owen Sound ON, N4K 6W2  
Telephone: (519) 376-7612 / Fax: (519) 376-8008  
Toll Free: 1-888-376-7612





**LEGEND**


- OW 6-85**  
OBSERVATION WELL LOCATION AND GROUNDWATER LEVEL
- OW 11-85**  
INACTIVE OR DECOMMISSIONED WELL LOCATION
- SW1**  
APPROXIMATE LOCATION OF SURFACE WATER SAMPLE
- GP 2**  
LOCATION OF GAS PROBE
- APPROXIMATE TOTAL SITE BOUNDARY
- 3 ha AREA PURCHASED DECEMBER, 1989
- 80.5**  
ESTIMATED GROUNDWATER CONTOUR (METRES) (Non Geodetic Benchmark)
- GROUNDWATER FLOW DIRECTION
- OW5\***  
WATERLEVEL EXCLUDED FROM INTERPRETATION

- NOTES:
1. INFORMATION ON THIS DRAWING DERIVED FROM DRAWINGS CONTAINED IN THE TOWNSHIP OF HURON-KINLOSS 2006 ANNUAL OPERATIONS AND MONITORING REPORT, KINLOSS LANDFILL SITE PREPARED BY R.J. BURNSIDE & ASSOCIATES LIMITED.
  2. LANDS DESCRIBED AS PART OF LOT 17, CONCESSION 6, FORMER TOWNSHIP OF KINLOSS, COUNTY OF BRUCE (PART 3, PLAN 3R-4858), LEASED BY THE TOWNSHIP OF KINLOSS (NOVEMBER 30, 1989) TOTALING 12.26 ha (30.3 Acres)
  3. WASTE NO LONGER ACCEPTED AT KINLOSS LANDFILL SITE. ONLY RECYCLABLES AND BURNABLE MATERIALS ACCEPTED. CURRENT FILLING AREA USED FOR DISPOSAL OF BURN PIT ASHES.
  4. CORRECTED SITE BOUNDARIES PROVIDED BY THE TOWNSHIP OF HURON-KINLOSS.
  5. GROUNDWATER ELEVATIONS AS OF MAY 15, 2023.

<b>GROUNDWATER FLOW - MAY 15, 2023</b>	
<b>KINLOSS LANDFILL SITE</b>	
<b>TOWNSHIP OF HURON-KINLOSS</b>	
DESIGN	T C G
DRAWN	J L M
APPROVED	J L M
DATE	MARCH 2024
SCALE	1 : 2,500
FILE No.	121-60018-16
FIG. No.	MAP 3

**wsp**

1450 1st Ave W, Suite 101, Owen Sound ON, N4K 6W2  
 Telephone: (519) 376-7612 / Fax: (519) 376-8008  
 Toll Free: 1-888-376-7612



SCALE HORZ 1: 1000, VERT 1:200

NOTES:

- CROSS-SECTION CONSTRUCTED FROM AVAILABLE LOCAL SURVEY DATE FOR MONITORING WELLS AND INFERRED GROUND ELEVATIONS (GEODETIC). INFERRED STRATIGRAPHY MAY CHANGE SLIGHTLY IF WELL SURVEY INFORMATION BECOMES AVAILABLE.
- WATER ELEVATIONS REFLECT FIELD MEASUREMENTS IN MAY 2018 RELATIVE TO GROUND SURFACE. WATER ELEVATIONS ARE TYPICALLY LOWER IN NOVEMBER.

SECTION A-A  
KINLOSS LANDFILL SITE  
TOWNSHIP OF HURON-KINLOSS



1450 1st Ave W, Suite 101, Owen Sound ON, N4K 6W2  
Telephone: (519) 376-7612 / Fax: (519) 376-8008  
Toll Free: 1-888-376-7612

DESIGN	
DRAWN	J L K
APPROVED	J L M
DATE	MARCH 2024
SCALE	HL H
FILE No.	121-60018-16
FIG. No.	4

**APPENDIX A**

**Environmental Compliance  
Approval**



Ontario

Ministry  
of the  
Environment

Provisional Certificate No. A 272801

## PROVISIONAL CERTIFICATE OF APPROVAL WASTE DISPOSAL SITE

Under The Environmental Protection Act, 1971 and the regulations and subject to the limitations thereof, this Provisional Certificate of Approval is issued to:

Township of Kinloss  
Holyrood, Ontario  
NOG 2B0

for the use and operation of a 6 hectares (15 acre) landfilling site

all in accordance with the following plans and specifications: 1. Plan of operation submitted to the Owen Sound District Office of MDE under cover of a letter dated August 23, 197

2. Site plan entitled "Kinloss Township Waste Disposal Site."

Located: Part Lot 16, Concession 6  
Township of Kinloss  
County of Bruce

which includes the use of the site only for the disposal of the following categories of waste (NOTE: Use of the site for additional categories of wastes requires a new application and amendments to the Provisional Certificate of Approval) Domestic, commercial and 10% non-hazardous solid industrial (limited to miscellaneous debris from agriculture such as wire, stumps and scrap metal) wastes.

and subject to the following conditions:

1. No operation shall be carried out at the site after sixty days from this condition becoming enforceable unless this Certificate including the reasons for this condition has been registered by the applicant as an instrument in the appropriate Land Registry Office against title to the site and a duplicate registered copy thereof has been returned by the applicant to the Director.

Dated this 1st day of October 19 80

Director, Section 39.



NOTICE

TO: Township of Kinloss  
Holyrood, Ontario  
NOG 2B0

You are hereby notified that Provisional Certificate of Approval No. A 272801 has been issued to you subject to the conditions outlined therein.

The reasons for the imposition of these conditions are as follows:  
The reason for the condition requiring registration of the Certificate is that Section 46 of The Environmental Protection Act, 1971 prohibits any use being made of the lands after they cease to be used for waste disposal purposes within a period of twenty-five years from the year in which such land ceased to be used unless the approval of the Minister for the proposed use has been given. The purpose of this prohibition is to protect future occupants of the site and the environment from any hazards which might occur as a result of waste being disposed of on the site. This prohibition and potential hazard should be drawn to the attention of future owners and occupants by the Certificate being registered on title.

You may by written notice served upon me and the Environmental Appeal Board within 15 days after receipt of this notice, require a hearing by the Board.

This Notice should be served upon:

The Secretary,  
Environmental Appeal Board,  
1 St. Clair Ave. West,  
5th Floor,  
Toronto, Ontario.  
M-1V 1K7

AND The Director,  
Section 39  
Ministry of the Environment,

DATED this 1st day of October . 1980 .

*[Handwritten Signature]*



NOTICE OF AMENDMENT

TO: Township of Kinloss  
Holyrood, Ontario  
NOG 2B0

You are hereby notified that the approval issued to you under Certificate of Approval No. A2728 dated October 1, 1980 is hereby amended as follows:

The following Condition and corresponding reason is added to the Provisional Certificate of Approval:

2. the Municipality shall submit an annual report prepared by their consultant to the Owen Sound District Officer, Ministry of the Environment addressing the following requirements:
  - 1) volumes of waste received; remaining capacity and site life expectancy;
  - 2) review of operating procedures, and any deficiencies therein
  - 3) the results of any surface water or ground water monitoring programs which may be initiated; and
  - 4) the extent and success of the recycling program established by the Township.

This report is to be submitted each year by March 31<sup>st</sup>, commencing March 31, 1993.

The reason for this addition is to ensure that the necessary studies are completed in order to ensure the protection of the natural environment.



You may by written notice served upon me and the Environmental Appeal Board within 15 days after receipt of this Notice, require a hearing by the Board. Section 142 of the Environmental Protection Act, S.O. 1990 c. E-19, as amended, provides that the Notice requiring the hearing shall state:

- The portions of the approval or each term or condition in the approval in respect of which the hearing is required, and;
- The grounds on which you intend to rely at the hearing in relation to each portion appealed.

In addition to these legal requirements, the Notice should also include:

- The name of the appellant;
- The address of the appellant;
- The Certificate of Approval number;
- The date of the Certificate of Approval;
- The name of the Director;
- The municipality within which the sewage works are located;

And the Notice should be signed and dated by the appellant.

This Notice must be served upon:

Secretary,  
Environmental Appeal Board,  
100 St. Clair Avenue West,  
Suite 502,  
Toronto, Ontario.  
M5V 1N3

AND

The Director,  
Section 39  
Environmental Protection Act,  
Ministry of the Environment,  
985 Adelaide St. South  
London, Ontario  
N6E 1V3

SERVED AT LONDON this 12<sup>th</sup> day of February, 1993



Director  
Section 39,  
Environmental Protection Act

W. Page  
Director, Approvals Branch  
Director, Waste Management Branch  
File



Ministry of  
Environment  
and Energy

Ministère de  
l'Environnement  
et de l'Énergie

AMENDED PROVISIONAL CERTIFICATE OF APPROVAL  
FOR A WASTE DISPOSAL SITE (PROCESSING) NO. A27280  
Page 1 of 2

### NOTICE OF AMENDMENT

TO: Township of Kinloss  
Holyrood, Ontario  
NOG 2B0

You are hereby notified that the approval issued under Certificate of Approval No. A272801 dated October 1, 1980, including all revisions, is hereby amended to the following:

The following conditions are added:

3. Monitoring of groundwater and surface water at the waste disposal site shall be carried out each year to the satisfaction of the Director of the Southwestern Region of the Ministry of the Environment and Energy.
4. Any changes to the monitoring programs for groundwater or surface water must be approved by the Director of the Southwestern Region of the Ministry of the Environment and Energy in writing.

The reasons for the addition of these conditions are:

3. The reason for Condition 3 is to ensure that the appropriate monitoring takes place so that the environmental impact of the waste disposal site can be assessed.
4. The reason for Condition 4 is to ensure that any changes made to the monitoring programs accurately reflect the impact of the waste disposal site on the natural environment.

The following document is added as supporting information to this Certificate of Approval:

"Township of Kinloss Waste Disposal Site Plan of Operation & Development and Hydrogeologic Assessment" dated December 1991 and prepared by Paragon Engineering Ltd.

This Notice shall constitute part of the approval issued under Certificate of Approval No. A272801 dated October 1, 1980, including all revisions.

AMENDED PROVISIONAL CERTIFICATE OF APPROVAL  
FOR A WASTE DISPOSAL SITE (PROCESSING) NO. A:  
Page

You may by written notice served upon me and the Environmental Appeal Board within 10 days after receipt of this Notice, require a hearing by the Board. Section 142, of the Environmental Protection Act, R.S.O., 1990, c. E-19, as amended, provides that the Notice requiring the hearing shall state:

1. The portions of the approval or each term or condition in the approval in respect of which the hearing is required, and;
2. The grounds on which you intend to rely at the hearing in relation to each portion appealed.

In addition to these legal requirements, the Notice should also include:

3. The name of the appellant;
4. The address of the appellant;
5. The Certificate of Approval number;
6. The date of the Certificate of Approval;
7. The name of the Director;
8. The municipality within which the works are located;

And the Notice should be signed and dated by the appellants.


This Notice must be served upon:

The Secretary,  
Environmental Appeal Board,  
112 St. Clair Avenue West,  
Suite 502,  
Toronto, Ontario,  
M4V 1N3

AND

The Director,  
Section 39, Environmental Protection Act,  
Ministry of the Environment and Energy,  
985 Adelaide Street South  
London, Ontario,  
N6E 1V3

DATED AT LONDON this 27<sup>th</sup> day of February, 1996

  
Director,  
Section 39,  
Environmental Protection Act


Ministry of the Environment  
Environmental Assessment and  
Approvals Branch  
Floor 12A  
2 St Clair Ave W  
Toronto ON M4V 1L5  
Fax (416)314-8452  
Telephone:

Ministère de l'Environnement  
Direction des évaluations et des  
autorisations environnementales  
Étage 12A  
2 av St Clair O  
Toronto ON M4V 1L5  
Télécopieur: (416)314-8452  
Téléphone :



April 30, 2003

Mary Rose Walden, Administrator  
PO Box 130  
Ripley, Ontario  
N0G 2R0



Dear Sir/Madam:

**Re: Notification of Change of Name/Address  
MOE Reference Number 1923-SM4HNL**

The Ministry of the Environment (the "Ministry") acknowledges receipt of your letter dated April 10, 2003 requesting a change in company name/address:

**FROM: The Township of Kinloss  
Holyrood, Ontario  
N0G 2B0**

**TO: The Corporation of the Township of Huron-Kinloss  
PO Box 130  
Ripley, Ontario  
N0G 2R0**

By this letter, the Ministry advises you that your notification of change in company name/address has been registered in our records for the following Certificate(s) of Approval:..

Certificate(s) of Approval for Waste Disposal Sites, Section 27, EPA:  
A272801

The Ministry will not be providing you with an amended certificate(s) to reflect the change in company name/address. Therefore, this letter must be appended to its corresponding Certificate(s) of Approval. The name/address change will be included in any future amended Certificate(s) of Approval.

If you have any questions regarding the above, please contact me at the above phone number.

Yours truly,



**Michael Durst**  
**Application Processor**

**cc: District Manager, Owen Sound**

**File Storage Number: 0899**

**APPENDIX B**

**BASWR Recycling Data**

## Municipality of HURON-KINLOSS


December 2023 BASWR Tons Diverted from Landfill

	TOTAL TONS	TOTAL TONS TO DATE	TOTAL MT TO DATE
<i>Newspaper</i>	6.33	87.85	79.68
<i>Steel Cans</i>	2.02	27.99	25.39
<i>Aluminum</i>	1.37	18.98	17.22
<i>Mixed Glass</i>	6.43	89.25	80.95
<i>HDPE Plastic</i>	2.84	39.33	35.67
<i>PET Plastic</i>	4.20	58.28	52.86
<i>Boxboard</i>	4.95	68.70	62.31
<i>Cardboard</i>	9.52	113.55	102.99
<b>TOTAL</b>	37.67	503.93	457.07
<b>TOTAL TO DATE</b>	503.93		

**APPENDIX C**

**Cross Section and Borehole Logs**





SCALE HORZ 1: 1000, VERT 1:200

NOTES:

- CROSS-SECTION CONSTRUCTED FROM AVAILABLE LOCAL SURVEY DATE FOR MONITORING WELLS AND INFERRED GROUND ELEVATIONS (GEODETIC). INFERRED STRATIGRAPHY MAY CHANGE SLIGHTLY IF WELL SURVEY INFORMATION BECOMES AVAILABLE.
- WATER ELEVATIONS REFLECT FIELD MEASUREMENTS IN MAY 2018 RELATIVE TO GROUND SURFACE. WATER ELEVATIONS ARE TYPICALLY LOWER IN NOVEMBER.

SECTION A-A  
KINLOSS LANDFILL SITE  
TOWNSHIP OF HURON-KINLOSS



1450 1st Ave W, Suite 101, Owen Sound ON, N4K 6W2  
Telephone: (519) 376-7612 / Fax: (519) 376-8008  
Toll Free: 1-888-376-7612

DESIGN	
DRAWN	J L K
APPROVED	J L M
DATE	MARCH 2024
SCALE	HL H
FILE No.	121-60018-16
FIG. No.	4

Project No.: LNE08508  
 Location: North Half Part Lot 16, Concession 6, Kinloss Township  
 Drilling Company: Noll Drilling Inc.  
 Drilling Method: Geoprobe  
 Sampling Interval: Continuous  
 Supervised by: J. Rutherford  
 Construction: 25 mm diameter threaded-joint PVC pipe with 10 slot PVC screen capped with slip-on labcock valve lockable steel protective casing

GP1	Depth	Soil Description	Concrete	Bentonite	Sand	Screen
	0.0 - 0.45	Medium brown fine sandy SILT, trace clay; compact; moist				
	0.45 - 3.65	Medium brown fine sandy SILT with 3 to 20 cm thick layers of light brown very fine SAND some silt, and light brown fine to medium sand; compact; moist	0 - 0.5	0.5 - 0.9	0.9 - 3.7	1.2 - 2.7
Borehole Location: North of OW1 Date Started: Jun 14, 2006 Date Completed: Jun 14, 2006						

GP2	Depth	Soil Description	Concrete	Bentonite	Sand	Screen
	0.0 - 0.40	Medium brown fine sandy SILT, trace clay; very stiff; moist				
	0.40 - 1.00	Medium brown silty fine SAND; compact; moist	0 - 0.5	0.5 - 1.2	1.2 - 3.7	1.5 - 3
	1.00 - 1.20	Medium brown fine sandy SILT, trace gravel; firm; moist				
	1.20 - 1.50	Medium brown fine sandy SILT, some gravel; non-plastic; firm; moist (appears disturbed - fill?)				
	1.50 - 2.25	Medium brown sandy SILT, some gravel; non-plastic; firm; moist				
	2.25 - 2.45	Light brown fine SAND, trace silt; loose; moist				
	2.45 - 3.60	Light brown fine SAND, some silt; layered with thin layers of medium sand nad sandy silt; loose; moist				
	3.60 - 3.65	Medium brown fine sandy SILT; non-plastic; firm; moist				
Borehole Location: West side of access road, between page wire fence and tire pile Date Started: Jun 14, 2006 Date Completed: Jun 14, 2006						

GP3	Depth	Soil Description	Concrete	Bentonite	Sand	Screen
	0.0 - 0.10	Light brown gravelly SAND, some silt; trace organic matter; loose; dry	0 - 0.5	0.5 - 0.6	0.6 - 2.3	0.8 - 2.3
	0.10 - 0.55	Medium red-brown fine SAND, trace silt; loose; moist				
	0.55 - 1.20	Light brown fine SAND, trace silt; loose; moist				
	1.20 - 2.15	Light brown fine SAND, trace silt; layered with thin seams of fine sand some silt, and silty fine sand; loose; moist				
	2.15 - 2.45	Medium brown fine sand SILT; non-plastic; compact; moist				
Borehole Location:		Between fill area and lower access road				
Date Started:		Jun 14, 2006				
Date Completed:		Jun 14, 2006				

CLIENT Township of Kinloss

PROJECT Kinloss Township Landfill

LOCATION Part Lot 16, Concession VI, Kinloss Township

DATE November 20, 1985

PROJECT No. 5-937

DEPTH METRES	ELEV.	DESCRIPTION	SAMPLE			WELL DETAIL	REMARKS
			No.	TYPE	"N"		
0	82.316	GROUND LEVEL					
0.20	82.313	TOPSOIL					
0.610	81.906	LIGHT BROWN SILTY SAND GRAVEL AND SOME COBBLE					
1.118	81.398		2		G.S.		
1.524	80.992	FINE TO MEDIUM SAND					
2.032	80.484		3		G.S.		
		END OF TEST PIT					

NO GROUND WATER

INCLUST TUBE, 15 - CRAB SAMPLE, 12 - SPLIT SPOON, "N" - BLOW



Paragon Engineering Limited

WELL No. Tf

CLIENT Township of Kinloss

PROJECT Kinloss Township Landfill

DATE November 20, 198

LOCATION Part Lot 16, Concession VI, Kinloss Township

PROJECT No. 5-937

DEPTH METRES - ELEV.		DESCRIPTION	SAMPLE No. TYPE "N"		WELL DETAIL	REMARK
	3:24	GROUND LEVEL				
0.203	3:03	TOPSOIL	5-5	4-4		
1.295	2:03	MEDIUM BROWN SAND	1	G.S.		
1.778	1:55					
2.210	1:12	END OF TEST PIT				

▽ Nov. 20

ST - INLET TUBE, GS - GAS SAMPLE, IS - SPLIT SPONGE, "N" - BLOW



Paragon Engineering Limited

WELL No. TP3

CLIENT Township of Kinloss

PROJECT Kinloss Township Landfill

DATE November 20, 1985

LOCATION Part lot 16, Concession VI, Kinloss Township

PROJECT No. 5-937

DEPTH METRES	ELEV	DESCRIPTION	SAMPLE		WELL DETAIL	REMARKS
			No.	TYPE		
0	35.39	GROUND LEVEL				
		TOPSOIL				
0.20	35.19	BROWN SILTY SAND, SOME GRAVEL				
0.61	35.02	GREY SANDY GRAVEL, SOME COBBLE				
0.91	34.72		4	G.S.		
1.93	33.58	FINE TO MEDIUM SAND				
2.43	33.21		5	G.S.		
2.74	32.95	END OF TEST PIT				NO GROUND WATER

CLIENT Township of Kinloss  
 PROJECT Kinloss Township Landfill DATE November 20, 1985  
 LOCATION Part lot 16, Concession VI, Kinloss Township PROJECT No. 5-937

DEPTH		DESCRIPTION	SAMPLE		WELL DETAIL	REMARKS
METRES	FEET		No.	TYPE "N"		
0.479	81.280					OW4-85
0	80.501	GROUND LEVEL				
		PEAT				
0.406	80.372					
0.664	80.177	YELLOW TO GREY SILTY SAND WITH GRAVEL				0.038 (1 1/2) $\phi$ $\Delta$ PIPE NOV. 20/85
0.762	80.039					
1.219	79.282	SANDY GRAVEL SOME COBBLE				NATIVE BACKFILL
				.6 GS.		
1.430	78.571					SLOTTED PIPES WRAPPED WITH FABRIC FILTER 10.6M LENGTH



Paragon Engineering Limited

WELL No. TP5-

CLIENT Township of Kinloss

PROJECT Kinloss Township Landfill

LOCATION Part Lot 16, Concession VI, Kinloss Township

DATE November 20, 1985

PROJECT No. 5-937

DEPTH METRES ELEV		DESCRIPTION	SAMPLE No. TYPE "N"	WELL DETAIL	REMARKS
0	80.286	GROUND LEVEL			TW5-85  NOV. 20/85  0.038 (1/2") Ø ΔE PIPE  NATIVE BACKFI  SLOTTED PIPE WRAPPED WITH FABRIC FILTER (3.6M LENGTH)
		PEAT			
0.203	80.157	LIGHT BROWN FINE TO MEDIUM SAND, SOME GRAVEL			
0.305	79.951				
0.410	79.746	STILTY SAND SOME GRAVEL			
0.714	79.312		7 G.S.		
1.524	78.752	GREY SANDY SILT			
2.38	77.918		8 G.S.		
2.40	77.916	END OF TEST PIT			

1 - SHOT TUBE, 25 - GRAB SAMPLE, 33 - SPLIT SPON, "N" - BLOW



CLIENT Township of Kinloss

DATE November 20, 1985

PROJECT Kinloss Township Landfill

PROJECT No. 5-937

LOCATION Part Lot 16, Concession VI, Kinloss Township

DEPTH METRES	DESCRIPTION	SAMPLE NO. TYPE "X"	WELL DETAIL	REMARKS
0	GROUND LEVEL			0W6-81
0-203	BLACK TOPSOIL			NOV. 20/85
0-610	LTGHT BROWN SILTY SAND	9 G.S.	0.038 (1/2") $\phi$ PIPE	
0-914				
1-219	GREY SILTY SAND, SOME GRAVEL	10 G.S.	NATIVE BACKFILL	
1-340	END OF TEST PIT		SLOTTED PIT WRAPPED W/ FABRIC FILTE (0.6M LENGT)	

7 - SHOT PIPE 15 - GRAB SAMPLE 15 - SPLIT SPOON "X" - BLOW

CLIENT: Township of Kinloss  
 PROJECT: Kinloss Township Landfill  
 LOCATION: Part Lot 16, Concession VI, Kinloss Township

DATE: November 20, 1985  
 PROJECT No: 9-937

DEPTH METRES		DESCRIPTION	SAMPLE		WELL DETAIL	REMARKS
NO.	FEET		NO.	TYPE		
0-131	83.173					
0	33.42	GROUND LEVEL				OW7-8
		TOPSOIL				
0-203	82.217	BROWN SILTY SAND				0-038 (1 1/2") Ø Δ PIPE
0-670	82.412	GREYISH BROWN FINE TO MEDIUM SAND				NATIVE BACKFILL
1-219	81.403	DENSE LIGHT BROWN SILTY SAND				NOV. 20/83
3-29	81.143					SLOTTED PIPE WRAPPED WITH FABRIC FILTER (0.6M LENGTH)
4-38	85.584	SILT				
5-63	80.457	END OF TEST PIT				



Paragon Engineering Limited

WELL No. TP8

CLIENT Township of Kinloss

PROJECT Kinloss Township Landfill

DATE November 20, 1985

LOCATION Part Lot 16, Concession VI, Kinloss Township

PROJECT No. 5-937

DEPTH METRES - ELEV.		DESCRIPTION	SAMPLE			WELL DETAIL	REMARKS
			No.	Type	"X"		
0	87.344	GROUND LEVEL					
		TOPSOIL					
0.508	87.236						
		BROWN SILTY SAND					
0.916	86.730						
		LIGHT BROWN FINE SAND					
1.219	86.348						
			12	G.S.			
2.236	85.378						
		DENSE SILTY SAND SOME GRAVEL					
2.591	84.773						
			13	G.S.			
2.672	84.672	END OF TEST PIT					

NO GROUND WATER

17 - INCH TUBE, 02 - GRAV SAMPLE, 12 - SPLIT SPOON, "X" - BLOW



Paragon Engineering Limited

WELL No. 1P2

CLIENT Township of Kinloss

PROJECT Kinloss Township Landfill

DATE November 20, 1985

LOCATION Part Lot 16, Concession VI, Kinloss Township

PROJECT No. 5-937

DEPTH METRES	DEPTH FEET	DESCRIPTION	SAMPLE		WELL DETAIL	REMARKS
			No.	Type "N"		
0.000	0.000	GROUND LEVEL				OW 9-85  0.038 (1 1/2") $\phi$ Δ PIPE  NATIVE BACKFI  SLOTTED PIPE WRAPPED W/ FILTER FABR (0.6M LENGTH)  NO GROUND WATER BU MOIST
0.305	0.971	TOPSOIL				
1.219	3.998	BROWN SANDY SILT COBBLES AT 1.219M LEVEL (COMPACT AND WET)	12	GS		
2.458	8.063	SILTY SAND AND GRAVEL (DRY)				
3.12	10.240	END OF TEST PIT				

11 - SHOULDER TUBE, 12 - GRAB SAMPLE, 13 - SPLIT SPoon, "N" - BLOW



Paragon Engineering Limited

WELL NO. TRIC

CLIENT Township of Kinloss

DATE November 20, 1985

PROJECT Kinloss Township Landfill

PROJECT No. 5-937

LOCATION Part Lot 16, Concession VI, Kinloss Township

DEPTH METRES ELEV.		DESCRIPTION	SAMPLE No. TYPE "X"	WELL DETAIL	REMARKS
0	101.152	GROUND LEVEL			
		TOPSOIL			
0.205	101.244	BROWN SANDY SILT, GRAVEL, COMPACT COBBLE AT 1829 LEVEL			NO GROUND WATER
1.324	99.128				
			15 G.S.		
1.418	98.104	END OF TEST PIT			

17 - SHALLOW TUBE, 18 - WASH SAMPLE, 19 - SPLIT SPIN, "X" - BLOW



Paragon Engineering Limited

WELL No. TP11-

CLIENT Township of Kinloss

DATE November 20, 1985

PROJECT Kinloss Township Landfill

PROJECT No. 5-937


LOCATION Part Lot 16, Concession VI, Kinloss Township

DEPTH METRES <u>22.316</u>	DESCRIPTION	SAMPLE			WELL DETAIL	REMARKS
		No.	TYPE	"X"		
0.000	GROUND LEVEL					<p>OW.TI-85</p> <p>0.038 (1/2") <math>\phi</math> AB PIPE</p> <p>NATIVE BACKFILL</p> <p>SLOTTED PIPE WRAPPED WITH FILTER FABRIC (0.6M LENGTH)</p> <p>NO GROUND WATER</p>
0.000 - 0.203	TOPSOIL					
0.203 - 0.610	DARK BROWN SILTY SAND					
0.610 - 1.524	LIGHT BROWN SILTY SAND SOME GRAVEL COBBLE AT BOTTOM			16 G.S.		
1.524 - 1.716	END OF TEST PIT					

17 - 1/2" DIAM. 18 - 3/8" DIAM. 19 - 3/4" DIAM. 20 - 1" DIAM. 21 - 1 1/2" DIAM. 22 - 2" DIAM. 23 - 2 1/2" DIAM. 24 - 3" DIAM. 25 - 3 1/2" DIAM. 26 - 4" DIAM. 27 - 4 1/2" DIAM. 28 - 5" DIAM. 29 - 5 1/2" DIAM. 30 - 6" DIAM. 31 - 6 1/2" DIAM. 32 - 7" DIAM. 33 - 7 1/2" DIAM. 34 - 8" DIAM. 35 - 8 1/2" DIAM. 36 - 9" DIAM. 37 - 9 1/2" DIAM. 38 - 10" DIAM. 39 - 10 1/2" DIAM. 40 - 11" DIAM. 41 - 11 1/2" DIAM. 42 - 12" DIAM. 43 - 12 1/2" DIAM. 44 - 13" DIAM. 45 - 13 1/2" DIAM. 46 - 14" DIAM. 47 - 14 1/2" DIAM. 48 - 15" DIAM. 49 - 15 1/2" DIAM. 50 - 16" DIAM. 51 - 16 1/2" DIAM. 52 - 17" DIAM. 53 - 17 1/2" DIAM. 54 - 18" DIAM. 55 - 18 1/2" DIAM. 56 - 19" DIAM. 57 - 19 1/2" DIAM. 58 - 20" DIAM. 59 - 20 1/2" DIAM. 60 - 21" DIAM. 61 - 21 1/2" DIAM. 62 - 22" DIAM. 63 - 22 1/2" DIAM. 64 - 23" DIAM. 65 - 23 1/2" DIAM. 66 - 24" DIAM. 67 - 24 1/2" DIAM. 68 - 25" DIAM. 69 - 25 1/2" DIAM. 70 - 26" DIAM. 71 - 26 1/2" DIAM. 72 - 27" DIAM. 73 - 27 1/2" DIAM. 74 - 28" DIAM. 75 - 28 1/2" DIAM. 76 - 29" DIAM. 77 - 29 1/2" DIAM. 78 - 30" DIAM. 79 - 30 1/2" DIAM. 80 - 31" DIAM. 81 - 31 1/2" DIAM. 82 - 32" DIAM. 83 - 32 1/2" DIAM. 84 - 33" DIAM. 85 - 33 1/2" DIAM. 86 - 34" DIAM. 87 - 34 1/2" DIAM. 88 - 35" DIAM. 89 - 35 1/2" DIAM. 90 - 36" DIAM. 91 - 36 1/2" DIAM. 92 - 37" DIAM. 93 - 37 1/2" DIAM. 94 - 38" DIAM. 95 - 38 1/2" DIAM. 96 - 39" DIAM. 97 - 39 1/2" DIAM. 98 - 40" DIAM. 99 - 40 1/2" DIAM. 100 - 41" DIAM.

DEPTH METRES	BORING METHOD	SOIL PROFILE		SAMPLES			ADDITIONAL LAB. TESTING
		DESCRIPTION	STRATA PLOT	ELEV.	NUMBER	TYPE	
				DEPTH			
		GROUND SURFACE		37.89			
0.00		Compact to very dense brown fine SAND, trace silt	[Strata Plot: Dotted pattern]	0.00	1	SS	
0.50				0.50	2	SS	
1.00				1.00	3	SS	
1.50				1.50	4	SS	
2.00				2.00	5	SS	
2.50				2.50	6	SS	
3.00				3.00	7	SS	
3.50				3.50	8	SS	
4.00				4.00	9	SS	
4.50				4.50	10	SS	
5.00				5.00	11	SS	
5.50				5.50	12	SS	
6.00				6.00	13	SS	
6.50				6.50	14	SS	
7.00				7.00	15	SS	
7.50				7.50	16	SS	
8.00		Dense gray-brown medium SAND trace silt, trace gravel	[Strata Plot: Dotted pattern]	7.18	17	SS	
8.50		Very dense brown fine SAND trace silt	[Strata Plot: Dotted pattern]	8.08	18	SS	
9.00		Dense to very dense gray-brown medium SAND, trace gravel, trace silt	[Strata Plot: Dotted pattern]	8.84	19	SS	
9.50			[Strata Plot: Dotted pattern]	9.50	20	SS	
10.00			[Strata Plot: Dotted pattern]	10.00	21	SS	
10.50			[Strata Plot: Dotted pattern]	10.50	22	SS	
11.00			[Strata Plot: Dotted pattern]	11.00	23	SS	
11.50			[Strata Plot: Dotted pattern]	11.50	24	SS	
12.00			[Strata Plot: Dotted pattern]	12.00	25	SS	

MONITORING INSTALLATIONS  
GROUNDWATER AND  
ENVIRONMENTAL OBSERVATIONS  
OW12-97



POWER AUGER  
(MOLLOW SOIL)

CONTINUED ON NEXT PAGE

SCALE


Golder Associates

LOGGED: T.P.  
CHECKED: *RW*

DRILLING DATE: AUG 21, 1997  
 SAMPLER: SAMMER, 53.5kg; DROP, 760mm

DATUM: LOCAL

NO. 12119.1

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES			ADDITIONAL LAB. TESTING	MONITORING INSTALLATIONS GROUNDWATER AND ENVIRONMENTAL OBSERVATIONS
		DESCRIPTION	STRATA PLOT	ELEV. #	NUMBER	TYPE		
14		CONTINUED FROM PREVIOUS PAGE						 <p>Sand Filter</p>
15		Dense to very dense gray-brown medium SAND, trace gravel, trace silt	[Pattern]	11	08	77		
17	POWER AUGER (MOLLOW BIT)	Very dense brown SILT trace gravel	[Pattern]	12	08	38		
18		Very dense grey SILT with gravel (TILL)	[Pattern]	13	08	100		
19		END OF BOREHOLE	[Pattern]	14	08			

WATER LEVEL ENCOUNTERED AT ELEV. 01.00 DURING DRILLING ON AUG. 21, 1997

SCALE

Golder Associates

LOGGED: T.P.  
 CHECKED: RWV




BORING DATE: AUG. 14, 1997

SAMPLE .MMER, 63.5kg; DROP, 760mm

DATUM: LOCAL

MONITORING INSTALLATIONS  
GROUNDWATER AND  
ENVIRONMENTAL OBSERVATIONS  
**OW13-97**

DEPTH METRES	BORING METHOD	SOIL PROFILE			SAMPLES		
		DESCRIPTION	STRATA PLOT	ELEV.	NUMBER	TYPE	BLOWS/0.3m
				DEPTH (m)			
0		GROUND SURFACE		80.33 0.00	1	50 DO	8
0.5	POWER AUGER (HOLLOW STEM)	Firm brown fibrous PEAT		78.98 1.37	2	50 DO	3
1.5		Soft grey CLAYEY SILT, trace gravel (TILL)		75.20 2.13	3	50 DO	54
2.5		Very dense grey SANDY SILT, trace gravel, trace clay and cobbles (TILL)		77.28 3.05			
3.0		END OF BOREHOLE					



WATER LEVEL ENCOUNTERED AT ELEV. 80.23 DURING DRILLING ON AUG. 21, 1997.

DEPTH SCALE


75

Golder Associates

LOGGED: T.P.  
CHECKED: *BW*

R. J. Burnside & Associates Limited  
 232 Speedvale Avenue West, Guelph, Ontario N1H 1C4  
 telephone (519) 823-4895 fax (519) 836-5477

Client: <b>Township of Huron-Kinloss</b>	Project Name: <b>Monitoring Well Installation</b>	Logged by: <b>S Quinlan</b>
Project No.: <b>W99613</b>	Location: <b>Kinloss Landfill</b>	Ground (m amsl):
Drilling Co.: <b>Lantech Drilling Services Inc.</b>	Date Started: <b>24/07/2003</b>	Static Water Level (m amsl):
Drilling Method: <b>Hollow Stem Auger</b>	Date Completed: <b>24/07/2003</b>	Sand Pack (m amsl):




Prepared By: **S. Quinlan** Checked By: **D. Hopkins** Date Prepared: **July 25, 03**

This borehole log was prepared for hydrogeological and/or environmental purposes and does not necessarily contain information suitable for a geotechnical assessment of the subsurface conditions. Borehole data requires interpretation by R. J. Burnside & Associates Limited personnel before use by others.

LEGEND		MONITORING WELL DATA		SAMPLE TYPE					
Water found @ time of drilling	Static Water Level -	Pipe: <b>51 mm dia. PVC</b>	Screen: <b>51 mm dia. PVC #10 slot</b>	AC	CS	RC	SS	AR	WC

Client: Township of Huron-Kinloss	Project Name: Kinloss Landfill	Logged by: J. Rutherford
Project No.: W99613.4	Location: PL 16, C 6, former Twp of Kinloss	Ground (m amsl): 80.36
Drilling Co.: Lantech Drilling Services Inc.	Date Started: 6/7/2004	Static Water Level (m amsl): 80.42
Drilling Method: Hollow Stem Auger	Date Completed: 6/7/2004	Sand Pack (m amsl): 71.52 - 73.68




Prepared By: **C. Paterson** Checked By: **G. Takata** Date Prepared: **8/18/2004**

This borehole log was prepared for hydrogeological and/or environmental purposes and does not necessarily contain information suitable for a geotechnical assessment of the subsurface conditions. Borehole data requires interpretation by R. J. Burnside & Associates Limited personnel before use by others.

<b>LEGEND</b> Water found @ time of drilling Static Water Level - 6/7/2004	<b>MONITORING WELL DATA</b> Pipe: 51 mm dia. PVC Screen: 51 mm dia. PVC #10 slot	<b>SAMPLE TYPE</b> AC  Auger Cutting CS  Continuous RC  Rock Core SS  Split Spoon AR  Air Rotary WC  Wash Cuttings
----------------------------------------------------------------------------------	----------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------









B:\LOG GUEP\PH\PROJECT\SW\996134.GPJ TEMPLATE GDT 26/08/04

Client: Township of Huron-Kinloss	Project Name: Kinloss Landfill	Logged by: J. Rutherford
Project No.: W99613.4	Location: PL 16, C 6, former Twp of Kinloss	Ground (m amsl): 80.42
Drilling Co.: Lantech Drilling Services Inc.	Date Started: 6/7/2004	Static Water Level (m amsl): 80.96
Drilling Method: Hollow Stem Auger	Date Completed: 6/7/2004	Sand Pack (m amsl): 74.50 - 76.31



Prepared By: **C. Paterson** Checked By: **G. Takata** Date Prepared: **8/18/2004**

This borehole log was prepared for hydrogeological and/or environmental purposes and does not necessarily contain information suitable for a geotechnical assessment of the subsurface conditions. Borehole data requires interpretation by R. J. Burnside & Associates Limited personnel before use by others.

<b>LEGEND</b>	<b>MONITORING WELL DATA</b>	<b>SAMPLE TYPE</b>	<b>AC</b>  Auger Cutting	<b>SS</b>  Split Spoon
 Water found @ time of drilling	Pipe: 51 mm dia. PVC	<b>CS</b>  Continuous	<b>AR</b>  Air Rotary	
 Static Water Level - 6/7/2004	Screen: 51 mm dia. PVC #10 slot	<b>RC</b>  Rock Core	<b>WC</b>  Wash Cuttings	


B:\LOG\3\DELPHI\GIN\PROJECTS\W996134\CPU TEMPLATE.GDT 260804

**BOREHOLE LOG**

Project: **Kinloss Landfill**  
 Client: **Township of Huron - Kinloss**  
 Method: **HSA / Direct Push sampling**  
 Elev: **masl**      TOC: **masl**

Dia: **197 mm**  
 Depth: **12.52 m**  
 Supervisor: **E.VanDenKleboom**

Project#: **101-16945-00**  
 Date: **Oct 28, 14**  
 Driller: **Strata Soil**



**BOREHOLE LOG**

Project: **Kinloss Landfill**  
 Client: **Township of Huron - Kinloss**  
 Method: **HSA / Direct Push sampling**  
 Elev: **masl**      TOC: **masl**

Dia: **197 mm**  
 Depth: **12.52 m**  
 Supervisor: **E.VanDenKieboom**

Project#: **101-16945-00**  
 Date: **Oct 28, 14**  
 Driller: **Strata Soil**

METRES	Depth	Stratigraphic Description	Samples					Well Instrumentation
			Strata Plot	Sample Interval	Sample No.	Sample Type	SPT - N Value	
8		<i>SAND - Medium grey grading to brown in colour with depth, very fine to fine grained SAND, moist. Soil has a distinct chemical odour.</i>						Bentonite Seal ( Holeplug )
8.2								
9								Graded Sandpack
9.5								
10								PVC threaded 2" dia. 10 slot screen
11		<i>Sands are becoming saturated, with some silt.</i>			2	DP		Encountered water @ 10.66 mbgl - Oct 28, 2014
12		<i>SILTY very fine SAND - brown, saturated.</i>						Static Water Level @ 11.75 mbgl - Oct 29, 2014
12.5		<i>E.O.H. - End of Hole @ 12.52 mbgl</i>						Bottom of Well @ 12.52 mbgl
13								

PROJECT: Landfill Monitoring CLIENT: Township of Huron-Kinloss PROJECT LOCATION: Huron County, Kinloss Landfill DATUM: Geodetic BH LOCATION:	<b>DRILLING DATA</b> Method: Direct Push Continuous Sampler Diameter: 150 Date: Aug/16/2016 REF. NO.: 101-16945-00 ENCL NO.: 2
----------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------

SOIL PROFILE		SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT				POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m <sup>3</sup> )	REMARKS AND GRAIN SIZE DISTRIBUTION (%)
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE			"N" BLOWS 0.3 m	SHEAR STRENGTH (kPa)					
96.2	0.0	TOPSOIL: 600mm, silty sand, trace organics, wet											GR SA SI CL
95.6	0.6	SAND AND GRAVEL: coarse, some silt, brown, wet	1	UNDIST									TOC elevation = 96.98 masl
94.6	1.6	SILTY CLAY: some gravel, occasional sand pockets, light brown, moist to wet	2	UNDIST									Drilling supervised by Elaine VanDenKieboom
93.0	3.2	SILTY SAND AND GRAVEL: medium, light brown, moist											
92.6	3.6	SAND AND GRAVEL: coarse, greyish brown, moist to wet	3	UNDIST									
92.3	3.9	SILTY CLAY TILL: some sand, some gravel, light brown, moist											
90.9	5.3	SAND AND GRAVEL: coarse, light brown, moist	4	UNDIST									
90.6	5.6	SILTY CLAY TILL: some gravel, some medium sand pockets, brown, moist											
90.1	6.1	SILTY CLAY: alternating layers of some gravel and medium sand layers	5	UNDIST									
89.0	7.2	SILTY SAND AND GRAVEL: medium, light brown, dry to moist											
88.5	7.7	SILTY CLAY: some gravel, medium sand pockets, brown, moist											
87.9	8.3	SILTY SAND AND GRAVEL: medium, brown, dry to moist	6	UNDIST									
87.0	9.1	SANDY SILT AND GRAVEL: some clay, brown, moist											
86.7	9.5	SAND: fine to medium, some gravel, some silt, brown, dry to moist	7	UNDIST									
86.0	10.2	SILTY SAND AND GRAVEL: medium, some clay, brown, moist											
85.2													

WSP SOIL LOG 101-16945-00 BH LOGS.GPJ SPL.GDT 3/22/17

Continued Next Page

GROUNDWATER ELEVATIONS

Measurement  $\nabla$  1st  $\nabla$  2nd  $\nabla$  3rd  $\nabla$  4th

GRAPH NOTES

+ 3, × 3: Numbers refer to Sensitivity      ○ ε=3% Strain at Failure

<p>PROJECT: Landfill Monitoring          CLIENT: Township of Huron-Kinloss          PROJECT LOCATION: Huron County, Kinloss Landfill          DATUM: Geodetic          BH LOCATION:</p>	<p><b>DRILLING DATA</b>          Method: Direct Push Continuous Sampler          Diameter: 150          Date: Aug/16/2016</p> <p style="text-align: right;">REF. NO.: 101-16945-00          ENCL NO.: 2</p>
---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

SOIL PROFILE		SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT				PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m <sup>3</sup> )	REMARKS AND GRAIN SIZE DISTRIBUTION (%)		
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE			"N" BLOWS 0.3 m	SHEAR STRENGTH (kPa)									WATER CONTENT (%)	
11.0  12  13  14  15  16  17  78.5 17.7  18  19  76.4 19.8	<p><b>SAND:</b> very fine, trace to some silt, light brown, dry to moist</p> <p style="text-align: center;">saturated</p>		8 9 10 11 12 13	UNDIST AUGER AUGER AUGER AUGER AUGER	<p style="text-align: center;">W. L. 81.0 m Upon Completion</p>	85 84 83 82 81 80 79 78 77												
<p><b>END OF BOREHOLE:</b>          Notes:          1. At 12.2 mbg, had to switch to augers due to refusal of the direct push continuous sampler.          2. Borehole caved to 14.3 mbg upon completion. Drillers were able to push well pipe through saturated sand to 19.8 mbg.          3. Installed monitoring well upon completion.</p>																		

WSP SOIL LOG 101-16945-00 BH LOGS.GPJ SPL.GDT 3/22/17

GROUNDWATER ELEVATIONS  
 Measurement

GRAPH NOTES + 3, × 3: Numbers refer to Sensitivity ○ ε=3% Strain at Failure



PROJECT: Landfill Monitoring CLIENT: Township of Huron-Kinloss PROJECT LOCATION: Huron County, Kinloss Landfill DATUM: Geodetic BH LOCATION:	<b>DRILLING DATA</b> Method: Sonic Vibration Diameter: 150 Date: Aug/15/2016 REF. NO.: 101-16945-00 ENCL NO.: 3
----------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------

SOIL PROFILE		SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT				POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m <sup>3</sup> )	REMARKS AND GRAIN SIZE DISTRIBUTION (%)
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE			"N" BLOWS 0.3 m	SHEAR STRENGTH (kPa)					
						20 40 60 80 100 ○ UNCONFINED + FIELD VANE & Sensitivity ● QUICK TRIAXIAL × LAB VANE	PLASTIC LIMIT W <sub>p</sub>	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W <sub>L</sub>	W <sub>p</sub> — W — W <sub>L</sub>			
80.0	TOPSOIL: 300mm, trace organics, wet to saturated												GR SA SI CL
79.7	SILTY CLAY: grey, some brown weathering, wet, dense		1	SS									TOC elevation = 81.01 masl
79.2	dark grey, some gravel, mosit to wet, some root channels		2	SS									Drilling supervised by Elaine VanDenKieboom
78.7	SAND AND GRAVEL: some silt, some clay, grey, saturated												
78.3	SILTY CLAY: some sand, some gravel, brown, wet, dense		3	SS									
77.7	SAND AND GRAVEL: coarse, brown, saturated		4	SS									
77.4	END OF BOREHOLE: Notes: 1. Borehole caved to approximately 2.3 mbg upon completion. 2. Installed monitoring well upon completion.												


WSP SOIL LOG 101-16945-00 BH LOGS.GPJ SPL.GDT 3/22/17

GROUNDWATER ELEVATIONS  
 Measurement

GRAPH NOTES + 3 × 3: Numbers refer to Sensitivity ○ ε=3% Strain at Failure

PROJECT: Landfill Monitoring CLIENT: Township of Huron-Kinloss PROJECT LOCATION: Huron County, Kinloss Landfill DATUM: Geodetic BH LOCATION:	<b>DRILLING DATA</b> Method: Sonic Vibration Diameter: 150 Date: Aug/15/2016 REF. NO.: 101-16945-00 ENCL NO.: 4
----------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------

SOIL PROFILE		SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT				POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m <sup>3</sup> )	REMARKS AND GRAIN SIZE DISTRIBUTION (%)	
(m) ELEV DEPTH	DESCRIPTION	NUMBER	TYPE	"N" BLOWS 0.3 m			20	40	60	80				100
80.0	<b>TOPSOIL:</b> 360mm, trace organics, saturated													TOC elevation = 80.83 masl
79.6	<b>SILT:</b> layered with silty clay, rust staining in silt lenses, light grey, moist, dense <b>SILTY CLAY:</b> some gravel, some coarse sand, greenish grey, moist, dense dark grey and light grey mottled, smooth	1	SS											Drilling supervised by Elaine VanDenKieboom
79.4														
79.2		2	SS											
78.0	<b>SAND AND GRAVEL:</b> some silt, coarse, brown, saturated													
77.6	<b>SILTY CLAY:</b> dark grey	4	SS											
77.5	<b>SAND AND GRAVEL:</b> coarse, saturated													
2.6	<b>END OF BOREHOLE:</b> Notes: 1. Borehole caved to approximately 2.4 mbg upon completion. 2. Installed monitoring well upon completion.													



WSP SOIL LOG - 101-16945-00 BH LOGS.GPJ SPL.GDT 3/22/17

GROUNDWATER ELEVATIONS: Measurement 1st 2nd 3rd 4th

GRAPH NOTES: + 3, x 3: Numbers refer to Sensitivity; ○ ε=3% Strain at Failure

**APPENDIX D**

**Certificate of Analysis and Lab  
Results**

C.O.C.: G115009/115010/

REPORT No. B23-03431

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1  
 Tel: 613-526-0123  
 Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 20-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Groundwater

WATERWORKS NO.

Parameter	Units	R.L.	Reference Method	Date/Site Analyzed	Client I.D.	OW4	OW5	OW6	OW17	
					Sample I.D.	Date Collected				
Hardness (as CaCO3)	mg/L	1	SM 3120	18-May-23/O	B23-03431-1	15-May-23	575	252	294	156
Alkalinity(CaCO3) to pH4.5	mg/L	5	SM 2320B	19-May-23/O	B23-03431-2	15-May-23	690	257	285	280
Conductivity @25°C	µmho/cm	1	SM 2510B	19-May-23/O	B23-03431-3	15-May-23	1270	503	539	496
pH @25°C	pH Units		SM 4500H	19-May-23/O	B23-03431-4	15-May-23	7.47	7.86	7.99	7.90
Chloride	mg/L	0.5	SM4110C	23-May-23/O			7.9	2.2	3.3	1.7
Nitrite (N)	mg/L	0.05	SM4110C	23-May-23/O			< 0.05	< 0.05	< 0.05	< 0.05
Nitrate (N)	mg/L	0.05	SM4110C	23-May-23/O			< 0.05	< 0.05	0.05	0.15
Sulphate	mg/L	1	SM4110C	23-May-23/O			25	20	13	2
Calcium	mg/L	0.02	SM 3120	18-May-23/O			175	56.4	72.4	72.7
Magnesium	mg/L	0.02	SM 3120	18-May-23/O			33.2	26.9	27.5	21.5
Potassium	mg/L	0.1	SM 3120	18-May-23/O			15.6	0.8	0.8	0.5
Sodium	mg/L	0.2	SM 3120	18-May-23/O			16.7	5.3	9.0	2.7
Aluminum	mg/L	0.01	SM 3120	18-May-23/O			0.05	< 0.01	0.20	0.02
Barium	mg/L	0.001	SM 3120	18-May-23/O			0.148	0.080	0.066	0.009
Boron	mg/L	0.005	SM 3120	18-May-23/O			0.382	0.014	0.024	< 0.005
Cadmium	mg/L	0.00015	EPA 200.8	30-May-23/O			< 0.000028	0.000025	0.000017	< 0.000015
Chromium	mg/L	0.001	EPA 200.8	30-May-23/O			< 0.001	< 0.001	< 0.001	< 0.001
Copper	mg/L	0.0001	EPA 200.8	30-May-23/O			< 0.0002	0.0004	0.0031	0.0071
Iron	mg/L	0.005	SM 3120	18-May-23/O			16.7	< 0.005	1.15	< 0.005
Lead	mg/L	0.00002	EPA 200.8	30-May-23/O			< 0.00004	< 0.00002	0.00042	0.00002
Manganese	mg/L	0.001	SM 3120	18-May-23/O			0.606	0.047	0.082	< 0.001
Zinc	mg/L	0.005	SM 3120	18-May-23/O			< 0.005	0.016	0.037	< 0.005
Ammonia (N)-Total	mg/L	0.01	SM4500-NH3-H	05-Jun-23/K			22.8	0.16	0.30	< 0.01
Total Kjeldahl Nitrogen	mg/L	0.1	E3516.2	07-Jun-23/K			21.5	0.3	0.7	0.6
Organic Nitrogen (Calculation)	mg/L	0.1	E3516.2	13-Jun-23/K			< 0.1	0.1	0.4	0.6
Phenolics	mg/L	0.001	MOEE 3179	06-Jun-23/K			< 0.001	< 0.001	< 0.001	< 0.001



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston,W-Windsor,O-Ottawa,R-Richmond Hill,B-Barrie

Steve Garrett  
 Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from

C.O.C.: G115009/115010/

REPORT No. B23-03431

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1

Tel: 613-526-0123

Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 20-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Groundwater

WATERWORKS NO.

Parameter	Units	R.L.	Client I.D.		OW4	OW5	OW6	OW17
			Reference Method	Date/Site Analyzed	B23-03431-1	B23-03431-2	B23-03431-3	B23-03431-4
Dissolved Organic Carbon	mg/L	0.2	EPA 415.2	18-May-23/O	9.9	1.9	1.0	1.0
Anion Sum	meq/L		Calc.	19-May-23/O	14.5	5.69	6.12	5.70
Cation Sum	meq/L		Calc.	19-May-23/O	13.5	5.28	6.36	5.53
% Difference	%		Calc.	19-May-23/O	3.60	3.67	1.92	1.52
Ion Ratio	AS/CS		Calc.	19-May-23/O	1.07	1.08	0.962	1.03
Sodium Adsorption Ratio	-		Calc.	19-May-23/O	0.304	0.146	0.229	0.0716
TDS(ion sum calc.)	mg/L	1	Calc.	19-May-23/O	705	267	299	269
Conductivity (calc.)	µmho/cm		Calc.	19-May-23/O	1126	492	554	504
TDS(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.557	0.532	0.555	0.543
EC(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.889	0.978	1.03	1.02
Langelier Index(25°C)	S.I.		Calc.	19-May-23/O	1.07	0.468	0.863	0.766



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston,W-Windsor,O-Ottawa,R-Richmond Hill,B-Barrie

Steve Garrett

Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from

C.O.C.: G115009/115010/

REPORT No. B23-03431

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1

Tel: 613-526-0123

Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 20-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Groundwater

WATERWORKS NO.

Parameter	Units	R.L.	Client I.D.		OW11-16	OW12	OW13S	OW13I
			Reference Method	Date/Site Analyzed	B23-03431-5	B23-03431-6	B23-03431-7	B23-03431-8
Hardness (as CaCO3)	mg/L	1	SM 3120	18-May-23/O	355	376	463	601
Alkalinity(CaCO3) to pH4.5	mg/L	5	SM 2320B	19-May-23/O	357	346	445	593
Conductivity @25°C	µmho/cm	1	SM 2510B	19-May-23/O	646	707	937	1220
pH @25°C	pH Units		SM 4500H	19-May-23/O	7.92	7.98	7.77	7.70
Chloride	mg/L	0.5	SM4110C	23-May-23/O	2.3	3.4	7.0	15.7
Nitrite (N)	mg/L	0.05	SM4110C	23-May-23/O	< 0.05	< 0.05	0.06	< 0.05
Nitrate (N)	mg/L	0.05	SM4110C	23-May-23/O	2.05	0.47	0.95	0.11
Sulphate	mg/L	1	SM4110C	23-May-23/O	5	59	90	101
Calcium	mg/L	0.02	SM 3120	18-May-23/O	93.3	65.9	106	133
Magnesium	mg/L	0.02	SM 3120	18-May-23/O	29.6	51.5	48.1	65.3
Potassium	mg/L	0.1	SM 3120	18-May-23/O	0.5	9.5	19.4	22.6
Sodium	mg/L	0.2	SM 3120	18-May-23/O	1.8	5.6	10.1	23.1
Aluminum	mg/L	0.01	SM 3120	18-May-23/O	0.02	0.02	0.03	0.04
Barium	mg/L	0.001	SM 3120	18-May-23/O	0.025	0.065	0.059	0.080
Boron	mg/L	0.005	SM 3120	18-May-23/O	0.005	0.394	0.449	0.550
Cadmium	mg/L	0.00015	EPA 200.8	30-May-23/O	< 0.00015	< 0.00015	< 0.00015	< 0.00028
Chromium	mg/L	0.001	EPA 200.8	30-May-23/O	< 0.001	0.001	< 0.001	< 0.001
Copper	mg/L	0.0001	EPA 200.8	30-May-23/O	0.0008	0.0014	0.0032	0.0024
Iron	mg/L	0.005	SM 3120	18-May-23/O	< 0.005	0.007	< 0.005	< 0.005
Lead	mg/L	0.00002	EPA 200.8	30-May-23/O	< 0.00002	0.00003	0.00003	< 0.00004
Manganese	mg/L	0.001	SM 3120	18-May-23/O	< 0.001	< 0.001	0.127	0.305
Zinc	mg/L	0.005	SM 3120	18-May-23/O	< 0.005	< 0.005	< 0.005	< 0.005
Ammonia (N)-Total	mg/L	0.01	SM4500-NH3-H	05-Jun-23/K	< 0.01	< 0.01	2.86	5.17
Total Kjeldahl Nitrogen	mg/L	0.1	E3516.2	07-Jun-23/K	0.1	0.2	4.3	5.0
Organic Nitrogen (Calculation)	mg/L	0.1	E3516.2	13-Jun-23/K	0.1	0.2	< 0.1	< 0.1
Phenolics	mg/L	0.001	MOEE 3179	06-Jun-23/K	< 0.001	< 0.001	< 0.001	< 0.001



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston,W-Windsor,O-Ottawa,R-Richmond Hill,B-Barrie

Steve Garrett  
 Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from

**C.O.C.: G115009/115010/**

**REPORT No. B23-03431**

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1

Tel: 613-526-0123

Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 20-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Groundwater

WATERWORKS NO.

Parameter	Units	R.L.	Reference Method	Date/Site Analyzed	Client I.D.	OW11-16	OW12	OW13S	OW13I
					Sample I.D.	B23-03431-5	B23-03431-6	B23-03431-7	B23-03431-8
Date Collected					15-May-23	15-May-23	15-May-23	15-May-23	15-May-23
Dissolved Organic Carbon	mg/L	0.2	EPA 415.2	18-May-23/O	1.0	2.5	4.4	5.8	
Anion Sum	meq/L		Calc.	19-May-23/O	7.48	8.31	11.0	14.4	
Cation Sum	meq/L		Calc.	19-May-23/O	7.18	8.01	10.2	13.6	
% Difference	%		Calc.	19-May-23/O	1.99	1.83	3.99	2.88	
Ion Ratio	AS/CS		Calc.	19-May-23/O	1.04	1.04	1.08	1.06	
Sodium Adsorption Ratio	-		Calc.	19-May-23/O	0.0416	0.126	0.205	0.410	
TDS(ion sum calc.)	mg/L	1	Calc.	19-May-23/O	347	403	548	718	
Conductivity (calc.)	µmho/cm		Calc.	19-May-23/O	638	718	924	1181	
TDS(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.538	0.570	0.585	0.591	
EC(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.987	1.02	0.986	0.972	
Langelier Index(25°C)	S.I.		Calc.	19-May-23/O	0.991	0.875	0.972	1.12	



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston,W-Windsor,O-Ottawa,R-Richmond Hill,B-Barrie

Steve Garrett

Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from

C.O.C.: G115009/115010/

REPORT No. B23-03431

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1

Tel: 613-526-0123

Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 20-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Groundwater

WATERWORKS NO.

Parameter	Units	R.L.	Reference Method	Date/Site Analyzed	Client I.D.	OW13D	OW14/14	OW15	OW16
					Sample I.D.	B23-03431-9	B23-03431-10	B23-03431-11	B23-03431-12
Date Collected					15-May-23	15-May-23	15-May-23	15-May-23	15-May-23
Hardness (as CaCO3)	mg/L	1	SM 3120	18-May-23/O	221	607	680	300	
Alkalinity(CaCO3) to pH4.5	mg/L	5	SM 2320B	19-May-23/O	243	573	493	295	
Conductivity @25°C	µmho/cm	1	SM 2510B	19-May-23/O	542	1270	1360	575	
pH @25°C	pH Units		SM 4500H	19-May-23/O	7.92	7.35	7.88	8.09	
Chloride	mg/L	0.5	SM4110C	23-May-23/O	7.1	51.6	55.0	7.7	
Nitrite (N)	mg/L	0.05	SM4110C	23-May-23/O	< 0.05	< 0.05	< 0.05	< 0.05	
Nitrate (N)	mg/L	0.05	SM4110C	23-May-23/O	0.08	0.09	< 0.05	0.59	
Sulphate	mg/L	1	SM4110C	23-May-23/O	48	83	256	15	
Calcium	mg/L	0.02	SM 3120	18-May-23/O	51.9	197	152	79.0	
Magnesium	mg/L	0.02	SM 3120	18-May-23/O	22.3	28.2	73.2	25.0	
Potassium	mg/L	0.1	SM 3120	18-May-23/O	1.0	8.3	2.4	1.0	
Sodium	mg/L	0.2	SM 3120	18-May-23/O	13.1	19.9	38.4	2.9	
Aluminum	mg/L	0.01	SM 3120	18-May-23/O	0.01	0.06	0.04	0.02	
Barium	mg/L	0.001	SM 3120	18-May-23/O	0.079	0.061	0.146	0.080	
Boron	mg/L	0.005	SM 3120	18-May-23/O	0.043	0.163	0.313	0.008	
Cadmium	mg/L	0.00015	EPA 200.8	30-May-23/O	< 0.00015	< 0.000028	< 0.000028	< 0.000015	
Chromium	mg/L	0.001	EPA 200.8	30-May-23/O	< 0.001	< 0.001	< 0.001	< 0.001	
Copper	mg/L	0.0001	EPA 200.8	30-May-23/O	0.0002	0.0006	0.0005	0.0003	
Iron	mg/L	0.005	SM 3120	18-May-23/O	0.066	35.0	0.427	0.052	
Lead	mg/L	0.00002	EPA 200.8	30-May-23/O	< 0.00002	< 0.00004	0.00012	0.00002	
Manganese	mg/L	0.001	SM 3120	18-May-23/O	0.016	0.225	0.374	0.108	
Zinc	mg/L	0.005	SM 3120	18-May-23/O	< 0.005	< 0.005	< 0.005	< 0.005	
Ammonia (N)-Total	mg/L	0.01	SM4500-NH3-H	05-Jun-23/K	0.15	5.75	0.20	0.01	
Total Kjeldahl Nitrogen	mg/L	0.1	E3516.2	07-Jun-23/K	0.2	6.0	3.2	8.5	
Organic Nitrogen (Calculation)	mg/L	0.1	E3516.2	13-Jun-23/K	< 0.1	0.3	0.2	0.3	



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston,W-Windsor,O-Ottawa,R-Richmond Hill,B-Barrie

Steve Garrett

Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from



**C.O.C.: G115009/115010/**

**REPORT No. B23-03431**

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1

Tel: 613-526-0123

Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 20-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Groundwater

WATERWORKS NO.

			Client I.D.	OW13D	OW14/14	OW15	OW16	
			Sample I.D.	B23-03431-9	B23-03431-10	B23-03431-11	B23-03431-12	
			Date Collected	15-May-23	15-May-23	15-May-23	15-May-23	
Parameter	Units	R.L.	Reference Method	Date/Site Analyzed				
Phenolics	mg/L	0.001	MOEE 3179	06-Jun-23/K	< 0.001	< 0.001	< 0.001	< 0.001
Dissolved Organic Carbon	mg/L	0.2	EPA 415.2	18-May-23/O	2.0	9.1	4.4	3.9
Anion Sum	meq/L		Calc.	19-May-23/O	6.14	14.7	16.8	6.50
Cation Sum	meq/L		Calc.	19-May-23/O	5.02	15.1	15.4	6.15
% Difference	%		Calc.	19-May-23/O	9.98	1.48	4.34	2.77
Ion Ratio	AS/CS		Calc.	19-May-23/O	1.22	0.971	1.09	1.06
Sodium Adsorption Ratio	-		Calc.	19-May-23/O	0.385	0.351	0.641	0.0722
TDS(ion sum calc.)	mg/L	1	Calc.	19-May-23/O	291	767	873	309
Conductivity (calc.)	µmho/cm		Calc.	19-May-23/O	510	1188	1371	568
TDS(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.536	0.606	0.641	0.537
EC(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.941	0.939	1.01	0.987
Langelier Index(25°C)	S.I.		Calc.	19-May-23/O	0.577	0.919	1.26	1.02



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston,W-Windsor,O-Ottawa,R-Richmond Hill,B-Barrie

Steve Garrett

Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from

C.O.C.: G115009/115010/

REPORT No. B23-03431

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1

Tel: 613-526-0123

Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 20-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Groundwater

WATERWORKS NO.

<b>Client I.D.</b>	GW Duplicate #1			
<b>Sample I.D.</b>	B23-03431-13			
<b>Date Collected</b>	15-May-23			

Parameter	Units	R.L.	Reference Method	Date/Site Analyzed			
Hardness (as CaCO3)	mg/L	1	SM 3120	18-May-23/O	610		
Alkalinity(CaCO3) to pH4.5	mg/L	5	SM 2320B	19-May-23/O	571		
Conductivity @25°C	µmho/cm	1	SM 2510B	19-May-23/O	1260		
pH @25°C	pH Units		SM 4500H	19-May-23/O	7.40		
Chloride	mg/L	0.5	SM4110C	23-May-23/O	52.7		
Nitrite (N)	mg/L	0.05	SM4110C	23-May-23/O	< 0.05		
Nitrate (N)	mg/L	0.05	SM4110C	23-May-23/O	< 0.05		
Sulphate	mg/L	1	SM4110C	23-May-23/O	85		
Calcium	mg/L	0.02	SM 3120	18-May-23/O	197		
Magnesium	mg/L	0.02	SM 3120	18-May-23/O	28.5		
Potassium	mg/L	0.1	SM 3120	18-May-23/O	8.4		
Sodium	mg/L	0.2	SM 3120	18-May-23/O	20.1		
Aluminum	mg/L	0.01	SM 3120	18-May-23/O	0.06		
Barium	mg/L	0.001	SM 3120	18-May-23/O	0.061		
Boron	mg/L	0.005	SM 3120	18-May-23/O	0.184		
Cadmium	mg/L	0.00015	EPA 200.8	30-May-23/O	< 0.00028		
Chromium	mg/L	0.001	EPA 200.8	30-May-23/O	< 0.001		
Copper	mg/L	0.0001	EPA 200.8	30-May-23/O	0.0007		
Iron	mg/L	0.005	SM 3120	18-May-23/O	35.3		
Lead	mg/L	0.00002	EPA 200.8	30-May-23/O	0.00030		
Manganese	mg/L	0.001	SM 3120	18-May-23/O	0.224		
Zinc	mg/L	0.005	SM 3120	18-May-23/O	< 0.005		
Ammonia (N)-Total	mg/L	0.01	SM4500-NH3-H	05-Jun-23/K	5.85		
Total Kjeldahl Nitrogen	mg/L	0.1	E3516.2	07-Jun-23/K	5.8		



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston,W-Windsor,O-Ottawa,R-Richmond Hill,B-Barrie

Steve Garrett

Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from

C.O.C.: G115009/115010/

REPORT No. B23-03431

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1

Tel: 613-526-0123

Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 20-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Groundwater

WATERWORKS NO.

<b>Client I.D.</b>	GW Duplicate #1			
<b>Sample I.D.</b>	B23-03431-13			
<b>Date Collected</b>	15-May-23			

Parameter	Units	R.L.	Reference Method	Date/Site Analyzed			
Organic Nitrogen (Calculation)	mg/L	0.1	E3516.2	13-Jun-23/K	< 0.1		
Phenolics	mg/L	0.001	MOEE 3179	06-Jun-23/K	< 0.001		
Dissolved Organic Carbon	mg/L	0.2	EPA 415.2	18-May-23/O	5.8		
Anion Sum	meq/L		Calc.	19-May-23/O	14.7		
Cation Sum	meq/L		Calc.	19-May-23/O	15.2		
% Difference	%		Calc.	19-May-23/O	1.74		
Ion Ratio	AS/CS		Calc.	19-May-23/O	0.966		
Sodium Adsorption Ratio	-		Calc.	19-May-23/O	0.355		
TDS(ion sum calc.)	mg/L	1	Calc.	19-May-23/O	770		
Conductivity (calc.)	µmho/cm		Calc.	19-May-23/O	1192		
TDS(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.611		
EC(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.946		
Langelier Index(25°C)	S.I.		Calc.	19-May-23/O	0.969		



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston, W-Windsor, O-Ottawa, R-Richmond Hill, B-Barrie

Steve Garrett

Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from

C.O.C.: G115011

REPORT No. B23-03432

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1  
 Tel: 613-526-0123  
 Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 07-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Surface Water

WATERWORKS NO.

Parameter	Units	R.L.	Reference Method	Date/Site Analyzed	Client I.D.	SW1	SW2	SW Duplicate #1	
					Sample I.D.	Date Collected			
Hardness (as CaCO3)	mg/L	1	SM 3120	23-May-23/O	B23-03432-1	15-May-23	233	269	245
Alkalinity(CaCO3) to pH4.5	mg/L	5	SM 2320B	19-May-23/O	B23-03432-2	15-May-23	252	276	251
pH @25°C	pH Units		SM 4500H	19-May-23/O	B23-03432-3	15-May-23	7.92	8.17	8.09
Conductivity @25°C	µmho/cm	1	SM 2510B	19-May-23/O			447	498	447
TDS(ion sum calc.)	mg/L	1	Calc.	19-May-23/O			239	272	243
Turbidity	NTU	0.1	SM 2130	17-May-23/O			5.5	0.4	4.7
Chloride	mg/L	0.5	SM4110C	19-May-23/O			2.4	4.8	2.4
Nitrate (N)	mg/L	0.05	SM4110C	19-May-23/O			0.08	0.09	< 0.05
Nitrite (N)	mg/L	0.05	SM4110C	19-May-23/O			< 0.05	< 0.05	< 0.05
Nitrate + Nitrite (N)	mg/L	0.05	SM4110C	19-May-23/O			0.10	0.10	< 0.05
Sulphate	mg/L	1	SM4110C	19-May-23/O			1	4	1
Calcium	mg/L	0.02	SM 3120	23-May-23/O			63.9	72.3	67.1
Magnesium	mg/L	0.02	SM 3120	23-May-23/O			17.7	21.5	18.8
Sodium	mg/L	0.2	SM 3120	23-May-23/O			1.6	2.6	1.8
Potassium	mg/L	0.1	SM 3120	23-May-23/O			0.3	0.8	0.3
Aluminum	mg/L	0.01	SM 3120	23-May-23/O			0.02	0.03	0.02
Barium	mg/L	0.001	SM 3120	23-May-23/O			0.020	0.026	0.021
Boron	mg/L	0.005	SM 3120	23-May-23/O			0.007	0.010	0.006
Cadmium	mg/L	0.00015	EPA 200.8	26-May-23/O			< 0.000015	< 0.000015	< 0.000015
Chromium	mg/L	0.001	EPA 200.8	26-May-23/O			< 0.001	< 0.001	< 0.001
Copper	mg/L	0.0001	EPA 200.8	26-May-23/O			0.0002	0.0003	0.0002
Iron	mg/L	0.005	SM 3120	23-May-23/O			0.116	0.039	0.125
Lead	mg/L	0.00002	EPA 200.8	26-May-23/O			0.00005	0.00002	0.00005
Manganese	mg/L	0.001	SM 3120	23-May-23/O			0.062	0.033	0.069
Zinc	mg/L	0.005	SM 3120	23-May-23/O			0.005	0.009	0.009
Ammonia (N)-Total	mg/L	0.01	SM4500-NH3-H	06-Jun-23/K			< 0.01	< 0.01	< 0.01



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston,W-Windsor,O-Ottawa,R-Richmond Hill,B-Barrie

Steve Garrett

Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from

C.O.C.: G115011

REPORT No. B23-03432

**Report To:**

**WSP Canada Inc.**

1450 1st Ave. West, Suite 101  
 Owen Sound ON N4K 6W2 Canada

**Attention:** Kaurel Tamasauskas

**Caduceon Environmental Laboratories**

2378 Holly Lane  
 Ottawa Ontario K1V 7P1  
 Tel: 613-526-0123  
 Fax: 613-526-1244

DATE RECEIVED: 16-May-23

JOB/PROJECT NO.: Kinloss Landfill -#101-16945-00

DATE REPORTED: 07-Jun-23

P.O. NUMBER: 121.60018-15-200

SAMPLE MATRIX: Surface Water

WATERWORKS NO.

<b>Client I.D.</b>	SW1	SW2	SW Duplicate #1
<b>Sample I.D.</b>	B23-03432-1	B23-03432-2	B23-03432-3
<b>Date Collected</b>	15-May-23	15-May-23	15-May-23

Parameter	Units	R.L.	Reference Method	Date/Site Analyzed				
Phosphorus-Total	mg/L	0.01	E3516.2	05-Jun-23/K	0.01	0.03	0.01	
Phenolics	mg/L	0.001	MOEE 3179	05-Jun-23/K	< 0.001	< 0.001	< 0.001	
Dissolved Organic Carbon	mg/L	0.2	EPA 415.2	18-May-23/O	7.6	5.3	8.0	
Anion Sum	meq/L		Calc.	19-May-23/O	5.14	5.74	5.12	
Cation Sum	meq/L		Calc.	19-May-23/O	4.73	5.51	4.99	
% Difference	%		Calc.	19-May-23/O	4.14	2.07	1.26	
Ion Ratio	AS/CS		Calc.	19-May-23/O	1.09	1.04	1.03	
Sodium Adsorption Ratio	-		Calc.	19-May-23/O	0.0465	0.0699	0.0499	
Conductivity (calc.)	µmho/cm		Calc.	19-May-23/O	446	508	457	
TDS(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.534	0.546	0.543	
EC(calc.)/EC(actual)	-		Calc.	19-May-23/O	0.997	1.02	1.02	
Langelier Index(25°C)	S.I.		Calc.	19-May-23/O	0.695	1.03	0.885	



R.L. = Reporting Limit

Test methods may be modified from specified reference method unless indicated by an \*

Site Analyzed=K-Kingston,W-Windsor,O-Ottawa,R-Richmond Hill,B-Barrie

Steve Garrett  
 Director of Laboratory Services

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from

**C.O.C.:** -

**REPORT No:** 23-025661 - Rev. 0

**Report To:**

WSP Canada Inc. - Owen Sound  
 1450 1st Ave. West  
 Suite 101  
 Owen Sound, ON N4K 6W2

**CADUCEON Environmental Laboratories**

112 Commerce Park Dr Unit L  
 Barrie, ON L4N 8W8

**Attention: Kaurel Tamasauskas**

DATE RECEIVED: 2023-Sep-22  
 DATE REPORTED: 2023-Oct-05  
 SAMPLE MATRIX: Ground Water

CUSTOMER PROJECT: Kinloss WDS/101-16945-00  
 P.O. NUMBER: CA0004834.9449-100

Analyses	Qty	Site Analyzed	Authorized	Date Analyzed	Lab Method	Reference Method
Anions (Liquid)	12	OTTAWA	PCURIEL	2023-Sep-25	A-IC-01	SM 4110B
Cond/pH/Alk Auto (Liquid)	12	OTTAWA	SBOUDREAU	2023-Sep-26	COND-02/PH-02/A LK-02	SM 2510B/4500H/ 2320B
DOC/DIC (Liquid)	12	OTTAWA	VKASYAN	2023-Sep-26	C-OC-01	EPA 415.2
ICP/MS (Liquid)	12	OTTAWA	AOZKAYMAK	2023-Sep-27	D-ICPMS-01	EPA 200.8
ICP/OES (Liquid)	12	OTTAWA	NHOGAN	2023-Sep-27	D-ICP-01	SM 3120B
Ammonia & o-Phosphate (Liquid)	12	KINGSTON	KDIBBITS	2023-Sep-26	NH3-001	SM 4500NH3
Organic Nitrogen (Liquid)	12	KINGSTON	KDIBBITS	2023-Oct-02	TPTKN-001	MECP E3516.2
Phenols (Liquid)	12	KINGSTON	JMACINNES	2023-Sep-26	PHEN-01	MECP E3179
TP & TKN (Liquid)	12	KINGSTON	KDIBBITS	2023-Oct-04	TPTKN-001	MECP E3516.2

R.L. = Reporting Limit

NC = Not Calculated

Test methods may be modified from specified reference method unless indicated by an \*



**Michelle Dubien**  
**Data Specialist**

**CADUCEON Environmental Laboratories Certificate of Analysis**

Final Report

REPORT No: 23-025661 - Rev. 0

Parameter	Units	R.L.	Client I.D.	OW4	OW5	OW6	OW7	OW11-16
			Sample I.D.	23-025661-1	23-025661-2	23-025661-3	23-025661-4	23-025661-5
			Date Collected	2023-09-21	2023-09-21	2023-09-21	2023-09-21	2023-09-21
				-	-	-	-	-
Alkalinity(CaCO3) to pH4.5	mg/L	5		732	262	295	355	338
pH @25°C	pH units	-		7.32	7.55	7.55	7.54	7.81
Conductivity @25°C	uS/cm	1		1410	516	569	648	627
Chloride	mg/L	0.5		12.7	2.7	3.4	2.3	2.5
Nitrate (N)	mg/L	0.05		0.25	0.11	<0.05	0.13	1.66
Nitrite (N)	mg/L	0.05		<0.05	<0.05	<0.05	<0.05	<0.05
Sulphate	mg/L	1		14	18	11	2	4
Total Kjeldahl Nitrogen	mg/L	0.1		146	0.3	1.2	0.4	0.2
Ammonia (N)-Total (NH3+NH4)	mg/L	0.05		25.1	0.15	0.44	<0.05	<0.05
Organic Nitrogen	mg/L	0.1		<0.1	0.2	0.8	0.4	0.2
Dissolved Organic Carbon	mg/L	0.2		15.2	3.2	2.8	3.4	4.0
Phenolics	mg/L	0.001		<0.001	<0.001	<0.001	<0.001	<0.001
Hardness (as CaCO3)	mg/L	0.02		597	250	266	333	325
Aluminum	mg/L	0.01		0.10	0.02	0.04	0.07	0.05
Barium	mg/L	0.001		0.192	0.092	0.075	0.013	0.025
Boron	mg/L	0.005		0.468	0.017	0.029	0.008	0.024
Calcium	mg/L	0.02		184	57.6	67.9	91.1	87.1
Iron	mg/L	0.005		16.2	0.053	1.01	0.255	0.006
Magnesium	mg/L	0.02		33.3	25.9	23.5	25.5	26.0
Manganese	mg/L	0.001		0.616	0.140	0.062	0.155	<0.001
Potassium	mg/L	0.1		19.9	0.8	0.9	0.5	0.5



**Michelle Dubien  
Data Specialist**

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.

**CADUCEON Environmental Laboratories Certificate of Analysis**

Final Report

REPORT No: 23-025661 - Rev. 0

Parameter	Client I.D.		OW4	OW5	OW6	OW7	OW11-16
	Sample I.D.		23-025661-1	23-025661-2	23-025661-3	23-025661-4	23-025661-5
	Date Collected		2023-09-21	2023-09-21	2023-09-21	2023-09-21	2023-09-21
	Units	R.L.	-	-	-	-	-
Sodium	mg/L	0.2	30.2	3.7	8.3	11.8	2.8
Zinc	mg/L	0.005	0.007	0.005	0.010	0.021	<0.005
Cadmium	mg/L	0.000015	<0.000015	<0.000015	0.000016	<0.000015	<0.000015
Chromium	mg/L	0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Copper	mg/L	0.0001	0.0006	0.0009	0.0002	0.0010	0.0006
Lead	mg/L	0.00002	<0.00004	<0.00002	<0.00002	0.00011	<0.00002
pH (Client Data)	pH units	-	6.84	7.93	7.74	7.5	7.63
Temperature (Client Data)	°C	-	14.6	14.4	13.7	14.7	10.4



**Michelle Dubien**  
Data Specialist

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.



**CADUCEON Environmental Laboratories Certificate of Analysis**

Final Report  
REPORT No: 23-025661 - Rev. 0

Parameter	Units	R.L.	Client I.D.	OW12	OW13S	OW13I	OW13D	OW14/14
			Sample I.D.	23-025661-6	23-025661-7	23-025661-8	23-025661-9	23-025661-10
			Date Collected	2023-09-21	2023-09-21	2023-09-21	2023-09-21	2023-09-21
				-	-	-	-	-
Alkalinity(CaCO3) to pH4.5	mg/L	5		339	526	545	265	619
pH @25°C	pH units	-		7.81	7.58	7.51	7.65	7.23
Conductivity @25°C	uS/cm	1		722	1110	1160	606	1400
Chloride	mg/L	0.5		3.8	10.2	12.4	7.8	42.8
Nitrate (N)	mg/L	0.05		0.42	0.28	0.14	0.15	0.08
Nitrite (N)	mg/L	0.05		<0.05	<0.05	<0.05	<0.05	<0.05
Sulphate	mg/L	1		61	76	90	51	97
Total Kjeldahl Nitrogen	mg/L	0.1		0.2	8.1	4.2	1.7	3.4
Ammonia (N)-Total (NH3+NH4)	mg/L	0.05		0.09	6.54	4.63	0.22	2.29
Organic Nitrogen	mg/L	0.1		0.1	<0.1	<0.1	1.4	1.1
Dissolved Organic Carbon	mg/L	0.2		4.6	8.7	9.3	3.6	18.0
Phenolics	mg/L	0.001		<0.001	<0.001	<0.001	<0.001	<0.001
Hardness (as CaCO3)	mg/L	0.02		378	508	538	243	705
Aluminum	mg/L	0.01		0.04	0.08	0.07	0.04	0.12
Barium	mg/L	0.001		0.075	0.088	0.078	0.092	0.055
Boron	mg/L	0.005		0.438	0.515	0.534	0.070	0.176
Calcium	mg/L	0.02		67.8	119	121	58.0	223
Iron	mg/L	0.005		<0.005	0.006	<0.005	0.458	22.0
Magnesium	mg/L	0.02		50.8	51.2	57.3	23.8	35.9
Manganese	mg/L	0.001		<0.001	0.218	0.241	0.015	0.096
Potassium	mg/L	0.1		10.5	25.1	23.7	1.0	6.6



**Michelle Dubien  
Data Specialist**

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.

**CADUCEON Environmental Laboratories Certificate of Analysis**

Final Report  
REPORT No: 23-025661 - Rev. 0

Parameter	Units	R.L.	Client I.D.	OW12	OW13S	OW13I	OW13D	OW14/14
			Sample I.D.	23-025661-6	23-025661-7	23-025661-8	23-025661-9	23-025661-10
			Date Collected	2023-09-21	2023-09-21	2023-09-21	2023-09-21	2023-09-21
Sodium	mg/L	0.2	-	5.9	16.1	19.7	14.7	32.0
Zinc	mg/L	0.005	-	<0.005	0.005	0.006	<0.005	0.008
Cadmium	mg/L	0.000015	-	0.000018	<0.000015	<0.000015	<0.000015	<0.000015
Chromium	mg/L	0.001	-	0.001	<0.001	<0.001	<0.001	<0.001
Copper	mg/L	0.0001	-	0.0010	0.0025	0.0023	0.0004	0.0009
Lead	mg/L	0.00002	-	0.00002	<0.00004	<0.00004	0.00002	<0.00004
pH (Client Data)	pH units	-	-	7.82	7.22	7.27	7.83	6.9
Temperature (Client Data)	°C	-	-	10.7	12.3	11.2	10.1	12.2



**Michelle Dubien**  
**Data Specialist**

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.

**CADUCEON Environmental Laboratories Certificate of Analysis**

Final Report  
REPORT No: 23-025661 - Rev. 0

Parameter	Units	R.L.	Client I.D.	OW15	OW16
			Sample I.D.	23-025661-11	23-025661-12
			Date Collected	2023-09-21	2023-09-21
				-	-
Alkalinity(CaCO3) to pH4.5	mg/L	5		450	311
pH @25°C	pH units	-		7.68	7.56
Conductivity @25°C	uS/cm	1		816	607
Chloride	mg/L	0.5		6.6	6.9
Nitrate (N)	mg/L	0.05		0.06	0.28
Nitrite (N)	mg/L	0.05		<0.05	<0.05
Sulphate	mg/L	1		3	16
Total Kjeldahl Nitrogen	mg/L	0.1		3.6	<0.1
Ammonia (N)-Total (NH3+NH4)	mg/L	0.05		0.16	0.12
Organic Nitrogen	mg/L	0.1		0.2	<0.1
Dissolved Organic Carbon	mg/L	0.2		22.0	8.3
Phenolics	mg/L	0.001		<0.001	<0.001
Hardness (as CaCO3)	mg/L	0.02		439	327
Aluminum	mg/L	0.01		0.07	0.06
Barium	mg/L	0.001		0.077	0.092
Boron	mg/L	0.005		0.075	0.018
Calcium	mg/L	0.02		114	87.1
Iron	mg/L	0.005		2.49	0.177
Magnesium	mg/L	0.02		37.4	26.5
Manganese	mg/L	0.001		0.404	0.193
Potassium	mg/L	0.1		3.1	0.8



**Michelle Dubien**  
**Data Specialist**

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.

Parameter	Client I.D.		OW15	OW16
	Sample I.D.		23-025661-11	23-025661-12
	Date Collected		2023-09-21	2023-09-21
	Units	R.L.	-	-
Sodium	mg/L	0.2	7.9	3.6
Zinc	mg/L	0.005	0.005	<0.005
Cadmium	mg/L	0.000015	<0.000015	<0.000015
Chromium	mg/L	0.001	<0.001	<0.001
Copper	mg/L	0.0001	0.0008	0.0007
Lead	mg/L	0.00002	0.00027	0.00005
pH (Client Data)	pH units	-	7.39	7.58
Temperature (Client Data)	°C	-	14.7	14.3



**Michelle Dubien**  
**Data Specialist**

C.O.C.: -

REPORT No: 23-025654 - Rev. 0

**Report To:**

WSP Canada Inc. - Owen Sound  
 1450 1st Ave. West  
 Suite 101  
 Owen Sound, ON N4K 6W2

**CADUCEON Environmental Laboratories**

112 Commerce Park Dr Unit L  
 Barrie, ON L4N 8W8

**Attention: Kaurel Tamasauskas**

DATE RECEIVED: 2023-Sep-22  
 DATE REPORTED: 2023-Oct-05  
 SAMPLE MATRIX: Ground Water

CUSTOMER PROJECT: Kinloss WDS/101-16945-00  
 P.O. NUMBER: CA0004834.9449-100

Analyses	Qty	Site Analyzed	Authorized	Date Analyzed	Lab Method	Reference Method
Anions (Liquid)	1	OTTAWA	PCURIEL	2023-Sep-25	A-IC-01	SM 4110B
Cond/pH/Alk Auto (Liquid)	1	OTTAWA	SBOUDREAU	2023-Sep-25	COND-02/PH-02/A LK-02	SM 2510B/4500H/ 2320B
DOC/DIC (Liquid)	1	OTTAWA	VKASYAN	2023-Sep-26	C-OC-01	EPA 415.2
ICP/MS (Liquid)	1	OTTAWA	AOZKAYMAK	2023-Sep-27	D-ICPMS-01	EPA 200.8
ICP/OES (Liquid)	1	OTTAWA	NHOGAN	2023-Sep-27	D-ICP-01	SM 3120B
Ammonia & o-Phosphate (Liquid)	1	KINGSTON	KDIBBITS	2023-Sep-26	NH3-001	SM 4500NH3
Organic Nitrogen (Liquid)	1	KINGSTON	KDIBBITS	2023-Oct-02	TPTKN-001	MECP E3516.2
Phenols (Liquid)	1	KINGSTON	JMACINNES	2023-Sep-26	PHEN-01	MECP E3179
TP & TKN (Liquid)	1	KINGSTON	KDIBBITS	2023-Sep-29	TPTKN-001	MECP E3516.2

R.L. = Reporting Limit

NC = Not Calculated

Test methods may be modified from specified reference method unless indicated by an \*



**Michelle Dubien**  
**Data Specialist**

**CADUCEON Environmental Laboratories Certificate of Analysis**

Final Report  
REPORT No: 23-025654 - Rev. 0

Parameter	Units	R.L.	Client I.D.
			GW DUP 1
			Sample I.D.
			23-025654-1
			Date Collected
			2023-09-21
Parameter	Units	R.L.	
Alkalinity(CaCO3) to pH4.5	mg/L	5	334
pH @25°C	pH units	-	7.67
Conductivity @25°C	uS/cm	1	606
Chloride	mg/L	0.5	2.3
Nitrate (N)	mg/L	0.05	1.31
Nitrite (N)	mg/L	0.05	<0.05
Sulphate	mg/L	1	4
Total Kjeldahl Nitrogen	mg/L	0.1	0.3
Ammonia (N)-Total (NH3+NH4)	mg/L	0.05	<0.05
Organic Nitrogen	mg/L	0.1	0.2
Dissolved Organic Carbon	mg/L	0.2	3.4
Phenolics	mg/L	0.001	<0.001
Hardness (as CaCO3)	mg/L	0.02	324
Aluminum	mg/L	0.01	0.06
Barium	mg/L	0.001	0.025
Boron	mg/L	0.005	0.023
Calcium	mg/L	0.02	87.3
Iron	mg/L	0.005	<0.005
Magnesium	mg/L	0.02	25.8
Manganese	mg/L	0.001	0.001
Potassium	mg/L	0.1	0.5



**Michelle Dubien**  
**Data Specialist**

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.

Parameter	Units	R.L.	Client I.D.
			GW DUP 1
			Sample I.D.
			23-025654-1
			Date Collected
			2023-09-21
			-
Sodium	mg/L	0.2	2.7
Zinc	mg/L	0.005	<0.005
Cadmium	mg/L	0.000015	<0.000015
Chromium	mg/L	0.001	<0.001
Copper	mg/L	0.0001	0.0003
Lead	mg/L	0.00002	<0.00002
pH (Client Data)	pH units	-	6.84
Temperature (Client Data)	°C	-	14.6



**Michelle Dubien**  
**Data Specialist**

C.O.C.: -

REPORT No: 23-025659 - Rev. 0

**Report To:**

WSP Canada Inc. - Owen Sound  
 1450 1st Ave. West  
 Suite 101  
 Owen Sound, ON N4K 6W2

**CADUCEON Environmental Laboratories**

112 Commerce Park Dr Unit L  
 Barrie, ON L4N 8W8

**Attention: Kaurel Tamasauskas**

DATE RECEIVED: 2023-Sep-22  
 DATE REPORTED: 2023-Oct-05  
 SAMPLE MATRIX: Surface Water

CUSTOMER PROJECT: Kinloss WDS/101-16945-00  
 P.O. NUMBER: CA0004834.9449-100

Analyses	Qty	Site Analyzed	Authorized	Date Analyzed	Lab Method	Reference Method
Anions (Liquid)	3	OTTAWA	VKASYAN	2023-Sep-26	A-IC-01	SM 4110B
Cond/pH/Alk Auto (Liquid)	3	OTTAWA	SBOUDREAU	2023-Sep-25	COND-02/PH-02/A LK-02	SM 2510B/4500H/ 2320B
DOC/DIC (Liquid)	3	OTTAWA	VKASYAN	2023-Sep-26	C-OC-01	EPA 415.2
ICP/MS Total (Liquid)	3	OTTAWA	AOZKAYMAK	2023-Sep-26	D-ICPMS-01	EPA 6020
ICP/OES Total (Liquid)	3	OTTAWA	NHOGAN	2023-Sep-26	D-ICP-01	SM 3120B
Ammonia & o-Phosphate (Liquid)	3	KINGSTON	KDIBBITS	2023-Sep-26	NH3-001	SM 4500NH3
Phenols (Liquid)	3	KINGSTON	JMACINNES	2023-Sep-26	PHEN-01	MECP E3179
TP & TKN (Liquid)	3	KINGSTON	KDIBBITS	2023-Sep-29	TPTKN-001	MECP E3516.2
Turbidity (Liquid)	3	OTTAWA	MDON	2023-Sep-26	A-TURB-01	SM 2130B

R.L. = Reporting Limit

NC = Not Calculated

Test methods may be modified from specified reference method unless indicated by an \*



**Michelle Dubien**  
**Data Specialist**



**CADUCEON Environmental Laboratories Certificate of Analysis**

Final Report  
REPORT No: 23-025659 - Rev. 0

Parameter	Units	R.L.	Client I.D.	SW1	SW2	SW DUP 1
			Sample I.D.	23-025659-1	23-025659-2	23-025659-3
			Date Collected	2023-09-21	2023-09-21	2023-09-21
				-	-	-
Alkalinity(CaCO3) to pH4.5	mg/L	5		273	301	303
pH @25°C	pH units	-		7.46	8.10	8.11
Conductivity @25°C	uS/cm	1		495	554	553
TDS (Calc. from Cond.)	mg/L	3		256	287	287
Turbidity	NTU	0.1		1.1	0.9	0.8
Chloride	mg/L	0.5		4.5	6.2	5.9
Nitrate (N)	mg/L	0.05		<0.05	0.15	0.12
Nitrite (N)	mg/L	0.05		<0.05	<0.05	<0.05
Nitrate (N) + Nitrite (N)	mg/L	0.1		<0.10	0.15	0.12
Sulphate	mg/L	1		<1	5	5
Phosphorus (Total)	mg/L	0.01		0.01	0.02	0.01
Ammonia (N)-Total (NH3+NH4)	mg/L	0.05		<0.05	<0.05	<0.05
Dissolved Organic Carbon	mg/L	0.2		12.7	7.4	7.8
Phenolics	mg/L	0.001		<0.001	<0.001	<0.001
Hardness (as CaCO3)	mg/L	-		279	294	302
Aluminum (Total)	mg/L	0.01		0.07	0.07	0.07
Barium (Total)	mg/L	0.001		0.031	0.034	0.035
Boron (Total)	mg/L	0.005		<0.005	0.009	0.010
Calcium (Total)	mg/L	0.02		77.3	78.8	80.6
Iron (Total)	mg/L	0.005		0.507	0.048	0.047
Magnesium (Total)	mg/L	0.02		20.8	23.7	24.5



**Michelle Dubien**  
Data Specialist

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.

**CADUCEON Environmental Laboratories Certificate of Analysis**

Final Report  
REPORT No: 23-025659 - Rev. 0

Parameter	Client I.D.		SW1	SW2	SW DUP 1
	Sample I.D.		23-025659-1	23-025659-2	23-025659-3
	Date Collected		2023-09-21	2023-09-21	2023-09-21
	Units	R.L.	-	-	-
Manganese (Total)	mg/L	0.001	0.293	0.060	0.059
Potassium (Total)	mg/L	0.1	0.2	1.0	1.0
Sodium (Total)	mg/L	0.2	2.3	2.9	3.0
Zinc (Total)	mg/L	0.005	0.048	0.029	0.023
Cadmium (Total)	mg/L	0.000015	<0.000015	<0.000015	0.000050
Chromium (Total)	mg/L	0.001	<0.001	<0.001	<0.001
Copper (Total)	mg/L	0.0001	0.0005	0.0006	0.0005
Lead (Total)	mg/L	0.00002	0.00002	0.00004	0.00008
pH (Client Data)	pH units	-	7.37	7.93	
Temperature (Client Data)	°C	-	17.8	13.7	



**Michelle Dubien**  
**Data Specialist**

The analytical results reported herein refer to the samples as received. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.

**APPENDIX E**

# Summary of Groundwater Results

E-1 Summary of Groundwater Results (2007 – R.J. Burnside)

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #4

	SEP 00					
pH	7.97					
conductivity	1190					
chloride	64					
hardness	488					
D.O.C.	8.4					
phenols	-					
colour	6					
alkalinity	582					
iron	9.60					
potassium	20.9					
magnesium	46.4					
calcium	119					
sodium	69.2					
sulphate	46					
nitrite	<0.02					
ammonia	3.01					
TKN (nitrogen)	3.36					
nitrate	<0.1					
Nickel	-					
Arsenic	-					
Cadmium	<0.002					
Chromium	<0.01					
Copper	<0.01					
Mercury	-					
Manganese	0.45					
Boron	0.27					
Lead	<0.001					
Selenium	-					
Zinc	0.42					
Cyanide	-					

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #5

	MAY 97	SEP 97	MAY 98	OCT 98	MAY 99	OCT 99
pH	7.78	7.81	8.53	7.43	8.24	7.86
conductivity	431	436	544	456.	442.	438
chloride	<1	4	4	2.	1.	1
hardness	221	241	174	233.	244.	266
D.O.C.	0.6	0.6	4.2	<0.5	0.9	1.0
phenols			-	-	-	-
colour	<5	9	<5	<5	<5	<5
alkalinity	208	217	410	248.	204.	230
iron	0.18	0.04	0.25	0.07	0.03	0.07
potassium	0.7	1.14	1.63	0.89	0.79	-.98
magnesium	24.5	26.9	11.3	22.9	23.3	25.8
calcium	48.2	52.1	51.0	55.4	59.3	63.8
sodium	8.0	3.87	93.5	9.02	4.26	4.61
sulphate	17	11	19	13.	21.	19
nitrite	<0.01	0.01	0.97	<0.02	<0.02	<0.02
ammonia	0.40	0.15	0.19	0.12	0.11	0.14
TKN (nitrogen)	0.70	0.49	2.21	1.28	0.94	0.49
nitrate	<0.05	0.05	-	<0.1	0.20	<0.1
Nickel			-	-	-	-
Arsenic			-	-	-	-
Cadmium	<.0003	<0.005	<0.002	<0.002	<0.002	<0.002
Chromium	<0.002	<0.02	<0.02	<0.02	<0.02	<0.01
Copper	0.002	<0.02	<0.01	<0.01	<0.01	<0.01
Mercury			-	-	-	-
Manganese	0.22	0.20	0.07	0.16	0.25	0.10
Boron	0.019	<0.02	0.04	0.11	0.10	0.02
Lead	0.0005	<0.04	<0.03	0.04	<0.03	<0.03
Selenium			-	-	-	-
Zinc	0.017	<0.01	1.01	0.41	0.07	0.02
Cyanide			-	-	-	-

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #5

	MAY 00	SEP 00				
pH	7.70	8.18				
conductivity	443	441				
chloride	1	2				
hardness	282	248				
D.O.C.	1.3	0.7				
phenols	-	-				
colour	<5	<5				
alkalinity	236	226				
iron	0.04	0.03				
potassium	0.34	1.10				
magnesium	28.4	26.3				
calcium	65.9	55.8				
sodium	5.82	3.95				
sulphate	15	12				
nitrite	<0.02	<0.02				
ammonia	0.08	0.11				
TKN (nitrogen)	4.01	0.20				
nitrate	0.85	<0.1				
Nickel	-	-				
Arsenic	-	-				
Cadmium	<0.002	<0.002				
Chromium	<0.01	<0.01				
Copper	0.01	0.01				
Mercury	-	-				
Manganese	0.40	0.27				
Boron	0.05	0.15				
Lead	<0.0005	<0.001				
Selenium	-	-				
Zinc	0.14	0.19				
Cyanide	-	-				

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #6

	MAY 97	SEP 97	MAY 98	OCT 98	MAY 99	OCT 99
pH	7.4	7.5	8.05	8.14	8.07	7.76
conductivity	509	528	467	485.	489.	489
chloride	2.40	6	4	5.	4.	5
hardness	270	175	257	252.	262.	275
D.O.C.	0.9	0.7	0.6	0.6	0.7	0.7
phenols			-	-	-	-
colour	<5	7	<5	<5	<5	<5
alkalinity	248	256	254	264.	246.	260
iron	0.99	1.21	1.07	0.74	0.75	0.17
potassium	0.9	1.3	1.20	1.03	1.33	1.18
magnesium	26.0	26.3	24.2	23.0	24.3	23.3
calcium	65.3	26.7	63.2	63.0	65.0	71.8
sodium	10	9.06	8.38	10.5	10.2	12.5
sulphate	19	13	17	21.	20.	29
nitrite	<0.01	0.01	0.02	<0.02	<0.02	<0.02
ammonia	1.77	0.36	0.26	0.39	0.38	0.28
TKN (nitrogen)	1.84	19.3	0.83	0.74	0.73	1.02
nitrate	<0.05	<0.05	<0.1	<0.1	0.15	<0.1
Nickel			-	-	-	-
Arsenic			-	-	-	-
Cadmium	<.0003	<0.005	<0.002	<0.002	<0.002	<0.002
Chromium	<0.002	<0.02	<0.02	<0.02	<0.02	<0.01
Copper	<0.002	<0.02	<0.01	<0.01	<0.01	0.01
Mercury			-	-	-	-
Manganese	0.13	0.13	0.16	0.13	0.14	0.02
Boron	0.028	<0.02	0.05	0.10	0.08	0.04
Lead	0.0002	<0.04	<0.03	<0.03	<0.03	<0.03
Selenium			-	-	-	-
Zinc	0.005	0.02	1.18	0.01	1.87	0.04
Cyanide			-	-	-	-



GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #6

	MAY 00	SEP 00				
pH	7.62	7.98				
conductivity	480	488				
chloride	4	2				
hardness	282	260				
D.O.C.	0.9	0.7				
phenols	-	-				
colour	<5	<5				
alkalinity	248	262				
iron	1.20	1.53				
potassium	0.96	1.16				
magnesium	25.9	24.6				
calcium	70.2	63.5				
sodium	12.5	10.5				
sulphate	24	19				
nitrite	<0.02	<0.02				
ammonia	0.06	0.08				
TKN (nitrogen)	0.58	0.08				
nitrate	0.94	<0.1				
Nickel	-	-				
Arsenic	-	-				
Cadmium	<0.002	<0.002				
Chromium	<0.01	<0.01				
Copper	<0.01	<0.01				
Mercury	-	-				
Manganese	0.08	0.08				
Boron	0.05	0.08				
Lead	<0.0005	<0.001				
Selenium	-	-				
Zinc	0.07	0.21				
Cyanide	-	-				

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #7

	SEP 97	MAY 98	MAY 99	MAY 00	SEP 00	
pH	7.97	7.97	7.56	7.53	8.01	
conductivity	400	407	478.	468	481	
chloride	2	2	<1	1	1	
hardness	166	270	296.	303	298	
D.O.C.	0.9	0.6	0.9	1.1	1.1	
phenols		-	-	-	-	
colour	11	<5	<5	<5	<5	
alkalinity	212	250	270.	251	277	
iron	0.42	0.84	<0.02	0.27	0.49	
potassium	0.68	0.82	0.54	<0.2	0.84	
magnesium	20.0	22.1	19.5	21.9	22.5	
calcium	33.4	71.6	86.2	85.2	82.1	
sodium	0.72	0.94	1.63	2.99	1.16	
sulphate	<2	2	17.	8	9	
nitrite	0.01	<0.02	<0.02	<0.02	<0.02	
ammonia	0.10	<0.05	<0.05	<0.05	<0.05	
TKN (nitrogen)	0.18	0.40	2.31	0.51	<0.05	
nitrate	0.14	0.12	0.17	1.03	<0.1	
Nickel		-	-	-	-	
Arsenic		-	-	-	-	
Cadmium	<0.005	<0.002	<0.002	<0.002	<0.002	
Chromium	<0.02	<0.02	<0.02	<0.01	<0.01	
Copper	0.02	<0.01	<0.01	0.01	<0.01	
Mercury		-	-	-	-	
Manganese	<0.02	0.06	<0.02	0.03	0.93	
Boron	<0.02	0.03	0.03	0.06	0.11	
Lead	0.04	<0.03	<0.03	<0.0005	<0.001	
Selenium		-	-	-	-	
Zinc	0.87	0.86	0.02	0.19	0.24	
Cyanide		-	-	-	-	

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #12

	SEP 97	MAY 98	OCT 98	MAY 99	OCT 99	MAY 00
pH	7.59	7.89	8.01	7.59	7.73	7.63
conductivity	1030	842	879.	855.	943	907
chloride	13	8	8.	9.	8	8
hardness	659	550	581.	565.	616	562
D.O.C.	2.0	1.4	2.1	1.8	1.9	1.3
phenols		-	-	-	-	-
colour	7	<5	<5	<5	<5	<5
alkalinity	339	334	382.	320.	350	332
iron	<0.04	0.29	0.02	<0.02	0.07	3.74
potassium	2.89	4.20	2.62	2.82	2.73	2.74
magnesium	81.1	66.8	67.1	62.0	70.1	78.2
calcium	130	110	122.	124.	131	96.0
sodium	11.9	11.0	11.1	12.1	13.0	12.2
sulphate	220	162	176.	184.	180	142
nitrite	0.02	0.05	<0.02	0.03	0.03	0.02
ammonia	0.11	<0.05	<0.05	<0.05	<0.05	<0.05
TKN (nitrogen)	0.28	0.44	0.60	0.67	0.48	0.44
nitrate	8.56	8.07	7.01	6.64	9.65	4.32
Nickel		-	-	-	-	-
Arsenic		-	-	-	-	-
Cadmium	<0.005	<0.002	<0.002	<0.002	<0.002	<0.002
Chromium	<0.02	<0.02	<0.02	<0.02	<0.01	0.01
Copper	<0.02	<0.01	0.01	<0.01	<0.01	0.01
Mercury		-	-	-	-	-
Manganese	0.07	0.02	<0.02	<0.02	<0.02	0.08
Boron	0.61	0.75	0.60	0.50	0.50	0.51
Lead	<0.04	<0.03	<0.03	<0.03	<0.03	0.0011
Selenium		-	-	-	-	-
Zinc	0.01	0.08	<0.01	0.02	0.03	0.09
Cyanide		-	-	-	-	-

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #12

	SEP 00					
pH	7.85					
conductivity	900					
chloride	7					
hardness	308					
D.O.C.	1.4					
phenols	-					
colour	<5					
alkalinity	373					
iron	1.84					
potassium	14.1					
magnesium	20.8					
calcium	88.9					
sodium	181					
sulphate	177					
nitrite	<0.02					
ammonia	<0.05					
TKN (nitrogen)	<0.05					
nitrate	3.97					
Nickel	-					
Arsenic	-					
Cadmium	<0.002					
Chromium	<0.01					
Copper	0.01					
Mercury	-					
Manganese	0.06					
Boron	0.58					
Lead	<0.001					
Selenium	-					
Zinc	0.13					
Cyanide	-					

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #13

	SEP 97	MAY 98	OCT 98	MAY 99	OCT 99	MAY 00
pH	7.24	7.64	7.69	7.06	7.46	7.40
conductivity	1570	1430	1410.	1450	1300	1270
chloride	72	63	60.	47.	34	36
hardness	871	903	879.	855.	831	823
D.O.C.	2.9	1.9	2.0	2.1	2.0	1.5
phenols		-	-	-	-	-
colour	9	<5	<5	<5	<5	<5
alkalinity	363	400	470.	338.	386	289
iron	<0.04	0.19	0.07	<0.02	<0.02	3.98
potassium	6.92	12.3	12.1	14.4	16.5	16.3
magnesium	115	92.5	89.8	82.8	83.6	97.5
calcium	159	209	204.	206.	195	169
sodium	42.0	34.9	36.9	34.6	29.4	31.0
sulphate	510	121	397.	462.	372	433
nitrite	0.05	<0.02	<0.02	<0.02	0.03	<0.02
ammonia	0.09	<0.05	0.08	<0.05	0.05	<0.05
TKN (nitrogen)	0.17	0.51	0.55	1.19	0.42	0.42
nitrate	1.60	3.59	2.40	3.95	1.96	2.71
Nickel		-	-	-	-	-
Arsenic		-	-	-	-	-
Cadmium	<0.005	0.004	<0.002	<0.002	<0.002	<0.002
Chromium	<0.02	<0.02	<0.02	<0.02	<0.01	<0.01
Copper	<0.02	0.01	<0.01	<0.01	<0.01	0.01
Mercury		-	-	-	-	-
Manganese	0.48	0.21	0.21	0.15	0.18	0.33
Boron	0.53	0.57	0.56	0.63	0.59	0.64
Lead	<0.04	<0.03	<0.03	<0.03	<0.03	<0.0011
Selenium		-	-	-	-	
Zinc	<0.01	0.70	<0.01	0.17	0.09	0.14
Cyanide		-	-	-	-	-

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

OBSERVATION WELL #13

	SEP 00					
pH	7.79					
conductivity	1240					
chloride	31					
hardness	701					
D.O.C.	1.6					
phenols	-					
colour	<5					
alkalinity	382					
iron	0.23					
potassium	14.4					
magnesium	81.2					
calcium	147					
sodium	27.7					
sulphate	358					
nitrite	<0.02					
ammonia	<0.05					
TKN (nitrogen)	<0.05					
nitrate	1.69					
Nickel	-					
Arsenic	-					
Cadmium	<0.002					
Chromium	<0.01					
Copper	<0.01					
Mercury	-					
Manganese	0.09					
Boron	0.54					
Lead	0.009					
Selenium	-					
Zinc	0.06					
Cyanide	-					

Appendix D  
 Groundwater Chemistry - Observation Wells  
 Kinross Landfill Site

Parameter	Units	RUC			OW4 May-00	OW5 May-00	OW6 May-00	OW7 May-00	OW12 May-00	OW13 May-00	OW4 Sep-00	OW5 Sep-00	OW6 Sep-00	OW7 Sep-00	OW12 Sep-00	OW13 Sep-00	OW4 May-01
		OW7	OW12	Ave.													
<i>Vadose Zone Monitoring</i>																	
Methane	%LEL				NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
Oxygen	% Vol/Vol				NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
<i>General Chemistry</i>																	
pH Value	pH units				7.18	7.7	7.62	7.53	7.63	7.4	7.97	8.18	7.98	8.01	7.85	7.79	7.53
pH Value (Field)	pH units				NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
Temperature (Field)	°C				NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
Ammonia as N	mg/L				3.22	0.08	0.06	< 0.05	< 0.05	< 0.05	3.01	0.11	0.08	< 0.05	< 0.05	< 0.05	4.5
Ammonia (un-ionized)	mg/L				NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
Total Kjeldahl Nitrogen (as N)	mg/L				3.66	4.01	0.58	0.51	0.44	0.42	3.36	0.2	0.08	< 0.05	< 0.05	< 0.05	4.5
Nitrate (as N)	mg/L	2.59	6.55	4.57	1.01	0.85	0.94	1.03	0.42	3.36	0.2	0.08	< 0.05	< 0.05	< 0.05	< 0.05	4.5
Nitrite + Nitrite (as N)	mg/L				< 0.02	< 0.02	< 0.02	< 0.02	4.32	2.71	NA	NA	NA	< 0.05	< 0.05	< 0.05	5.3
Dissolved Organic Carbon (as C)	mg/L				1.01	0.85	0.94	1.03	0.02	< 0.02	< 0.1	< 0.1	< 0.1	< 0.1	< 0.05	< 0.05	5.3
Conductivity	µs/cm	3.1	3.6	3.3	11.7	1.3	0.9	1.1	4.34	2.71	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.1	
Conductivity (Field)	µs/cm				1160	443	480	468	907	1.5	8.4	0.7	0.7	< 0.10	< 0.10	< 0.10	
Sulphate (as SO4)	mg/L				NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	
Alkalinity (as CaCO3)	mg/L	253	316	284	34	15	24	8	142	433	46	12	19	9	1.4	1.8	16.4
Chloride (as Cl)	mg/L				585	238	248	251	332	289	582	226	262	277	373	382	709
Colour	TCU	126	129	127	48	1	4	1	8	36	64	2	2	1	7	31	162
Calculated Hardness (as CaCO3)	mg/L				10	< 5	< 5	< 5	< 5	8	64	2	2	1	7	31	162
Total Cations	meq/L				513	282	282	303	582	823	488	248	290	298	308	701	710
Total Anions	meq/L				13.54	5.89	6.21	6.18	11.83	18.22	13.52	5.16	5.69	6.02	14.38	15.59	20.53
Ion Balance	% diff.				12.58	5.12	5.84	5.29	10.13	16.00	14.40	4.83	5.89	5.78	11.62	18.08	19.31
Calculated T.D.S.	mg/L				3.88	7.01	4.80	7.81	7.73	6.51	3.17	3.31	0.05	2.25	10.60	1.55	3.06
					877	276	303	280	568	977	734	253	282	291	741	906	1033
<i>Trace Metals</i>																	
Aluminum, Al	mg/L				0.04	< 0.03	0.77	0.29	1.83	2.17	< 0.03	< 0.03	0.89	0.39	1.24	0.17	< 0.03
Barium, Ba	mg/L				1.07	0.54	0.55	0.83	0.49	0.64	1.01	1.05	0.79	1.13	0.5	0.32	0.18
Boron, B	mg/L	0.50	0.54	0.52	0.25	0.05	0.05	0.08	0.51	0.84	0.27	0.16	0.08	0.11	0.58	0.54	0.22
Cadmium, Cd	mg/L	0.002	0.002	0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002
Calcium, Ca	mg/L				120.0	85.9	70.2	85.2	96.0	169.0	119.0	55.8	83.5	82.1	88.9	147.0	200.0
Chromium, Cr	mg/L				< 0.01	< 0.01	< 0.01	< 0.01	0.01	0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01
Copper, Cu	mg/L	0.01	0.01	0.01	< 0.01	< 0.01	< 0.01	< 0.01	0.01	0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01
Iron, Fe	mg/L	0.50	0.50	0.50	< 0.01	0.01	< 0.01	< 0.01	0.01	0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01
Lead, Pb	mg/L	0.16	0.16	0.16	5.85	0.04	1.2	0.27	3.74	3.98	9.8	0.03	1.53	0.49	1.84	0.23	12.7
Magnesium, Mg	mg/L	0.003	0.003	0.003	< 0.0005	< 0.0005	< 0.0005	< 0.0005	0.0011	< 0.0011	< 0.0011	< 0.0011	< 0.0011	< 0.0011	< 0.0011	< 0.0011	< 0.0011
Manganese, Mn	mg/L				51.7	28.4	25.9	21.9	78.2	97.5	46.4	26.3	24.8	22.5	20.8	81.2	51.2
Potassium, K	mg/L	0.10	0.03	0.08	0.73	0.4	0.08	0.03	0.08	0.33	0.45	0.27	0.08	0.93	0.06	0.09	0.76
Silica, Reactive (as SiO2)	mg/L				21.70	0.34	0.96	< 0.20	2.74	16.30	0.45	0.27	0.08	0.93	0.06	0.09	0.76
Sodium, Na	mg/L	100.5	104.2	102.3	12.5	13.8	12.0	5.6	10.2	8.9	20.90	1.10	1.16	0.84	14.10	14.40	20.90
Zinc, Zn	mg/L	2.50	2.51	2.50	57.7	5.82	12.5	2.99	12.2	31	69.2	3.95	10.5	7.2	10.3	8.0	14.5
					0.43	0.14	0.07	0.19	0.09	0.14	0.42	0.19	0.21	0.24	0.13	0.06	0.01

Note: While concentrations of parameters exceeding the Reasonable Use Criteria have been highlighted at all wells regardless of location, the Reasonable Use Guideline applies only to the boundary wells.

F:\Cienca\2004\WV9613 Annual Data\2003\W9613 - 2004 Database.xls\GW

Appendix D  
Groundwater Chemistry - Observation Wells  
Kinloss Landfill Site

Parameter	Units	QW7	RUC OW12	Ave.	OW5 May-01	OW6 May-01	OW7 May-01	OW12 May-01	OW13 May-01	OW4 Sep-01	OW5 Sep-01	OW6 Sep-01	OW7 Sep-01	OW12 Sep-01	OW13 Sep-01	OW4 May-02	OW6 May-02
<b>Vadose Zone Monitoring</b>																	
Methane	%LEL				NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0
Oxygen	% Vol/Vol				NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	21	21
<b>General Chemistry</b>																	
pH Value	pH units				8.09	8	8.08	7.91	7.67	7.31	7.95	7.8	DRY	7.89	7.55	7.86	9.01
pH Value (Field)	pH units				NA	NA	NA	NA	NA	NA	NA	NA	DRY	NA	NA	NA	NA
Temperature (Field)	°C				NA	NA	NA	NA	NA	NA	NA	NA	DRY	NA	NA	NA	NA
Ammonia as N	mg/L				0.08	0.06	0.14	< 0.05	< 0.05	5.48	0.08	0.09	DRY	< 0.05	0.19	9.21	0.06
Ammonia (un-ionized)	mg/L				NA	NA	NA	NA	NA	NA	NA	NA	DRY	NA	NA	NA	NA
Total Kjeldahl Nitrogen (as N)	mg/L				0.19	0.11	0.43	0.27	0.54	7.19	0.33	0.3	DRY	0.43	0.66	10.1	0.8
Nitrate (as N)	mg/L	2.59	6.55	4.57	< 0.1	< 0.1	< 0.1	6.58	2.64	< 0.1	< 0.1	< 0.1	DRY	< 0.02	< 0.02	< 0.02	< 0.20
Nitrite (as N)	mg/L				< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	0.03	< 0.02	< 0.02	DRY	6.58	1.82	0.44	3.09
Nitrate + Nitrite (as N)	mg/L				< 0.10	< 0.10	< 0.10	6.58	2.64	0.13	< 0.10	< 0.10	DRY	< 0.02	< 0.02	< 0.02	< 0.20
Dissolved Organic Carbon (as C)	mg/L	3.1	3.6	3.3	0.9	0.8	1.4	1.3	2.2	16.2	0.8	1	DRY	6.58	1.92	0.44	3.09
Conductivity	µs/cm				441	482	418	890	1410	1770	477	524	DRY	1.5	3.8	18.9	7.4
Conductivity (Field)	µs/cm				NA	NA	NA	NA	NA	NA	NA	NA	DRY	978	1530	1680	724
Sulphate (as SO4)	mg/L	253	316	284	18	18	3	95	372	37	14	20	DRY	NA	NA	NA	NA
Alkalinity (CaCO3)	mg/L				234	262	239	405	402	681	227	250	DRY	141	290	73	31
Chloride (as Cl)	mg/L	126	129	127	2	2	1	4	42	126	2	1	DRY	350	484	858	539
Colour	TCU				7	6	< 5	< 5	< 5	7	< 5	< 5	DRY	5	50	117	10
Calculated Hardness (as CaCO3)	mg/L				264	271	264	562	855	646	252	274	DRY	569	850	785	189
Total Cations	meq/L				5.51	5.88	5.37	11.80	18.92	19.93	5.20	5.99	DRY	11.93	19.13	21.91	12.78
Total Anions	meq/L				3.80	2.14	4.84	10.66	17.15	17.95	4.89	5.44	DRY	10.54	17.45	22.01	11.93
Ion Balance	% dif.				269	282	249	576	1008	974	248	284	DRY	585	988	1248	847
Calculated T.D.S.	mg/L				< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.01	< 0.01	< 0.01	DRY	< 0.01	< 0.01	< 0.01	0.058
<b>Trace Metals</b>																	
Aluminum, Al	mg/L				0.06	0.07	< 0.04	0.08	0.11	0.144	0.065	0.098	DRY	0.069	0.12	0.185	0.007
Barium, Ba	mg/L				0.02	0.03	< 0.02	0.41	0.7	0.26	0.02	0.04	DRY	0.62	0.71	0.25	0.02
Boron, B	mg/L	0.50	0.54	0.52	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.0001	< 0.0001	< 0.0001	DRY	< 0.0001	< 0.0001	< 0.0001	0.0004
Cadmium, Cd	mg/L				62.5	69.2	74.8	103.0	191.0	178.0	58.0	68.7	DRY	108.0	182.0	220.0	24.9
Calcium, Ca	mg/L	0.01	0.01	0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.005	< 0.005	< 0.005	DRY	< 0.005	< 0.005	< 0.005	< 0.005
Chromium, Cr	mg/L	0.50	0.50	0.50	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.002	< 0.002	< 0.002	DRY	0.002	0.003	< 0.002	< 0.002
Copper, Cu	mg/L	0.003	0.003	0.003	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	6.01	0.03	0.47	DRY	0.04	< 0.03	0.33	< 0.03
Iron, Fe	mg/L	0.10	0.03	0.06	28.1	23.9	18.8	73.9	91.7	< 0.0005	< 0.0005	< 0.0005	DRY	< 0.0005	< 0.0005	< 0.0005	0.0021
Lead, Pb	mg/L				0.81	0.83	0.67	< 0.02	0.07	5.535	0.221	24.8	DRY	72.8	96.1	57.2	30.8
Magnesium, Mg	mg/L	100.5	104.2	102.3	14.0	12.6	5.7	11.20	18.60	22.60	0.082	0.082	DRY	< 0.005	0.112	0.897	0.008
Manganese, Mn	mg/L	2.50	2.51	2.50	5.08	9.89	1.35	6.65	8.4	7.3	6.9	6.5	DRY	4.4	20.50	20.30	3.06
Potassium, K	mg/L				0.03	0.04	0.01	0.01	0.05	139	3.6	11.2	DRY	10	36.9	116	205
Silica, Reactive (as SiO2)	mg/L				< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	DRY	< 0.005	< 0.005	0.115	0.049
Sodium, Na	mg/L												DRY				
Zinc, Zn	mg/L												DRY				

Note: While concentrations of parameters exceeding the Reasonable Use Criteria



Appendix D  
Groundwater Chemistry - Observation Wells  
Kinross Landfill Site

Parameter	Units	RUC			OW6 May-02	OW7 May-02	OW12 May-02	OW13 May-02	OW4 Sep-02	OW5 Sep-02	OW6 Sep-02	OW7 Sep-02	OW12 Sep-02	OW13 Sep-02	OW4 May-03	OW6 May-03	OW6 May-03
		OW7	OW12	Ave.													
<b>Vadose Zone Monitoring</b>																	
Methane	%LEL				0	0	0	0	0	1	0	DRY	1	0	0	0	
Oxygen	% Vol/Vol				21	21	21	21	20.8	20.7	20.8	DRY	20.5	20.8	20.9	21.1	21.2
<b>General Chemistry</b>																	
pH Value	pH units				8.07	8.12	8	7.88	7.32	7.86	7.86	DRY	7.88	7.42	7.39	8	7.86
pH Value (Field)	pH units				NA	NA	NA	NA	6.7	7.6	7.3	DRY	7.3	7.1	8.25	7.2	7.1
Temperature (Field)	°C				NA	NA	NA	NA	14.3	16	15.6	DRY	11	11.2	11.7	12.2	12.6
Ammonia as N	mg/L				0.08	< 0.05	< 0.05	0.05	9.28	0.1	0.13	DRY	< 0.05	0.82	9.4	0.12	0.12
Ammonia (un-ionized)	mg/L				NA	NA	NA	NA	0.01389	0.00132	0.000845	DRY	< 0.00023	0.002378	0.3416	0.0004	0.0003
Total Kjeldahl Nitrogen (as N)	mg/L				0.22	0.15	0.31	0.39	11	0.43	0.51	DRY	< 0.00023	0.002378	0.3416	0.0004	0.0003
Nitrate (as N)	mg/L	2.59	6.55	4.57	0.25	0.3	7.3	3.45	< 0.1	< 0.1	< 0.1	DRY	0.41	1.49	10.3	0.3	0.29
Nitrite (as N)	mg/L				< 0.02	< 0.02	< 0.02	0.02	< 0.02	< 0.02	< 0.1	DRY	8.37	2.2	0.12	< 0.1	< 0.1
Nitrate + Nitrite (as N)	mg/L				0.25	0.30	7.30	3.47	< 0.02	< 0.02	< 0.10	DRY	6.37	2.20	0.14	< 0.10	< 0.10
Dissolved Organic Carbon (as C)	mg/L	3.1	3.6	3.3	1.2	1.1	1.9	2.7	17.9	1.1	0.7	DRY	6.37	2.20	0.14	< 0.10	< 0.10
Conductivity	us/cm				485	404	859	1440	1700	448	486	DRY	1.8	4	12.9	1	0.8
Conductivity (Field)	us/cm				NA	NA	NA	NA	2040	550	590	DRY	863	1480	2030	525	537
Sulphate (as SO4)	mg/L	253	316	284	18	6	122	411	82	18	21	DRY	1050	1820	1751	486	491
Alkalinity (as CaCO3)	mg/L				259	239	387	411	830	243	253	DRY	135	381	108	17	20
Chloride (as Cl)	mg/L	128	129	127	2	1	5	55	104	2	5	DRY	378	497	867	268	272
Colour	TCU				< 5	< 5	< 5	< 5	10	< 5	< 5	DRY	7	67	138	3	4
Calculated Hardness (as CaCO3)	mg/L				259	236	495	797	745	258	260	DRY	< 5	< 5	< 5	< 5	< 5
Total Cations	meq/L				5.55	4.76	10.45	17.83	21.06	5.45	5.71	DRY	557	889	905	287	286
Total Anions	meq/L				5.83	4.96	10.94	18.57	21.45	5.29	5.64	DRY	11.69	20.24	23.82	5.89	6.14
Ion Balance	% diff.				0.74	1.98	2.31	2.03	0.91	1.50	0.80	DRY	11.02	19.50	23.45	5.80	5.97
Calculated T.D.S.	mg/L				284	238	572	1074	1217	266	291	DRY	598	1136	1331	285	306
<b>Trace Metals</b>																	
Aluminum, Al	mg/L				< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	0.03	< 0.01	DRY	< 0.01	< 0.01	< 0.005	< 0.005	0.015
Barium, Ba	mg/L	0.50	0.54	0.52	0.068	0.006	0.065	0.11	0.174	0.072	0.084	DRY	0.075	< 0.01	< 0.005	< 0.005	0.015
Boron, B	mg/L	2.50	2.75	2.63	0.02	< 0.01	0.47	0.69	0.3	0.02	0.03	DRY	0.58	0.75	0.282	0.016	0.024
Cadmium, Cd	mg/L	0.002	0.002	0.002	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	0.0028	< 0.0001	DRY	0.0002	< 0.0001	< 0.0001	0.0009	< 0.0001
Calcium, Ca	mg/L				68.1	65.0	91.8	173.0	205.0	61.1	67.2	DRY	104.0	191.0	259.0	69.3	76.8
Chromium, Cr	mg/L	0.01	0.01	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	DRY	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
Copper, Cu	mg/L	0.50	0.50	0.50	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	DRY	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
Iron, Fe	mg/L	0.16	0.16	0.16	0.53	< 0.03	< 0.03	< 0.03	0.48	< 0.03	0.15	DRY	0.002	0.002	< 0.0005	< 0.0005	< 0.0005
Lead, Pb	mg/L	0.003	0.003	0.003	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	0.0008	< 0.0005	DRY	< 0.03	< 0.03	1.38	0.07	0.37
Magnesium, Mg	mg/L	0.10	0.03	0.06	18.0	64.8	88.8	58.8	25.7	22.4	22.4	DRY	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005
Manganese, Mn	mg/L				< 1.00	< 1.00	8.20	19.40	23.20	1.10	1.00	DRY	< 0.005	0.113	62.8	27.6	23.0
Potassium, K	mg/L				5.9	2.9	4.7	4.1	7.2	7.1	6.1	DRY	7.10	25.30	28.20	0.80	0.80
Silica, Reactive (as SiO2)	mg/L	100.5	104.2	102.3	8.6	0.9	8	32.3	113	5.8	10.9	DRY	8.8	4.4	7.2	6.4	5.6
Sodium, Na	mg/L	2.50	2.51	2.50	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	0.501	< 0.005	DRY	< 0.005	< 0.005	0.006	0.158	0.06
Zinc, Zn	mg/L																

Note: While concentrations of parameters exceeding the Reasonable Use Criteria

Appendix D  
Groundwater Chemistry - Observation Wells  
Kinross Landfill Site

Parameter	Units	RUC			OW7 May-03	OW12 May-03	OW13 May-03	OW13 (Rep) May-03	OW4 Oct-03	OW5 Oct-03	OW6 Oct-03	OW7 Oct-03	OW12 Oct-03	OW13 Oct-03	OW14 Oct-03	OW13 (Rep) Oct-03	OW4 May-04	
		OW7	OW12	Ave.														
<b>Vadose Zone Monitoring</b>																		
Methane	%LEL				0	0	0	NA	0	0	0	0	0	0	NA	0		
Oxygen	% Vol/Vol				21	21	20.8	NA	20.9	20.9	20.9	20.9	20.5	20.9	20.8	NA	20.9	
<b>General Chemistry</b>																		
pH Value	pH units				7.83	7.91	7.87	7.69	7.3	7.99	7.84	7.82	7.7	7.55	7.29	7.53	7.28	
pH Value (Field)	pH units				7.63	7.88	7.15	7.69	8.89	8.05	7.87	7.38	7.42	7.17	8.82	NA	6.78	
Temperature (Field)	°C				14	14.4	12.3	NA	12.7	13	11.9	13	11.4	11.1	12.5	NA	6.78	
Ammonia as N	mg/L				< 0.05	< 0.05	0.07	0.1	8.82	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	NA	11.2	
Ammonia (un-ionized)	mg/L				< 0.0005	< 0.0006	0.0002	NA	< 0.0157	< 0.0013	< 0.0005	< 0.0003	< 0.0003	< 0.0001	17.3	< 0.05	14.8	
Total Kjeldahl Nitrogen (as N)	mg/L				0.38	0.32	0.55	0.5	11.2	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	0.06	22.8	0.1	16.3
Nitrate (as N)	mg/L	2.59	6.55	4.57	< 0.1	3.53	2.45	2.41	< 0.1	< 0.05	< 0.05	< 0.05	< 0.05	0.06	22.8	0.1	16.3	
Nitrite (as N)	mg/L				< 0.02	< 0.02	0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02
Nitrate + Nitrite (as N)	mg/L				< 0.10	3.53	2.50	2.41	< 0.10	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02
Dissolved Organic Carbon (as C)	mg/L	3.1	3.6	3.3	1.1	1.6	3.1	2.9	16.5	0.5	< 0.5	0.8	4.57	2.18	< 0.1	1.97	< 0.1	
Conductivity	us/cm				504	894	1880	1890	2120	468	511	609	965	1570	1620	1550	2300	
Conductivity (Field)	us/cm				453	834	1554	NA	1882	479	461	545	817	1372	1341	NA	2224	
Sulphate (as SO4)	mg/L	253	316	284	8	138	572	590	60	19	22	6	137	471	29	482	61	
Alkalinity (as CaCO3)	mg/L	126	129	127	2	8	400	397	902	245	268	352	385	392	916	382	953	
Chloride (as Cl)	TCU				< 5	< 5	< 5	< 5	10	6	4	1	7	57	27	57	204	
Colour	TCU				291	549	1060	1040	800	256	< 5	< 5	< 5	< 5	8	< 5	71.2	
Calculated Hardness (as CaCO3)	meq/L				5.87	11.49	23.73	23.42	23.55	5.28	5.90	6.71	5.42	8.09	7.83	8.31	8.20	
Total Cations	meq/L				5.96	11.09	21.99	22.33	24.36	5.44	5.93	6.71	5.42	8.09	7.83	8.31	8.20	
Total Anions	meq/L				1.83	1.80	3.80	2.38	1.69	1.43	0.26	3.55	1.28	2.65	1.00	1.88	3.24	
Ion Balance	% diff.				280	595	1358	1367	1391	267	303	340	592	1137	997	1157	1461	
Calculated T.D.S.	mg/L																	
<b>Trace Metals</b>																		
Aluminum, Al	mg/L				< 0.005	0.008	< 0.005	0.01	< 0.005	0.006	0.026	< 0.005	0.016	< 0.005	< 0.005	0.025	< 0.005	
Barium, Ba	mg/L	0.50	0.54	0.52	0.007	0.071	0.118	0.118	0.227	0.068	0.078	0.01	0.068	< 0.005	< 0.005	0.025	< 0.005	
Boron, B	mg/L	2.50	2.75	2.63	0.006	0.49	1.06	1.06	0.249	0.02	0.028	0.006	0.527	0.889	0.867	0.857	0.307	
Cadmium, Cd	mg/L	0.002	0.002	0.002	0.0002	0.004	0.0002	< 0.0001	< 0.0001	0.0003	< 0.0001	0.0007	0.0004	< 0.0001	0.0002	< 0.0001	< 0.0001	
Calcium, Ca	mg/L				83.4	114.0	237.0	233.0	227.0	62.3	73.9	95.5	107.0	178.0	182.0	183.0	225	
Chromium, Cr	mg/L	0.01	0.01	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	
Copper, Cu	mg/L	0.50	0.50	0.50	< 0.0005	0.0012	0.0015	0.0015	< 0.0005	< 0.0009	< 0.0005	< 0.0007	0.0025	0.0012	0.0025	0.0012	< 0.0005	
Iron, Fe	mg/L	0.16	0.16	0.16	< 0.03	< 0.03	< 0.03	< 0.03	0.38	< 0.03	< 0.03	0.49	0.03	< 0.03	< 0.03	< 0.03	0.07	
Lead, Pb	mg/L	0.003	0.003	0.003	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	
Magnesium, Mg	mg/L	0.10	0.03	0.06	20.2	64.3	113.0	112.0	56.8	24.4	21.8	22.9	66.7	88.8	73.7	90.8	62.8	
Manganese, Mn	mg/L				0.032	0.006	0.137	0.131	0.598	0.047	0.06	0.198	0.008	0.053	0.645	0.053	0.663	
Potassium, K	mg/L				0.40	4.10	24.00	23.80	26.30	0.90	1.00	0.50	4.80	25.30	45.80	25.70	25.8	
Silica, Reactive (as SiO2)	mg/L	100.5	104.2	102.3	0.9	9.4	45.6	45.1	144	3.3	9.4	1	9.3	8.1	10.7	8.3	6.05	
Sodium, Na	mg/L	2.50	2.51	2.50	< 0.005	0.025	< 0.005	0.011	< 0.005	0.083	0.049	0.009	0.037	< 0.005	0.007	0.04	0.016	
Zinc, Zn	mg/L																	

Note: While concentrations of parameters exceeding the Reasonable Use Criteria

Appendix D  
Groundwater Chemistry - Observation Wells  
Kinloss Landfill Site

Parameter	Units	RUC			OW6 May-04	OW6 May-04	OW7 May-04	OW12 May-04	OW13 May-04	OW13I Jun-04	OW13D Jun-04	OW14 May-04	OW13SO4 May-04	OW4 Sep-04	OW6 Sep-04	OW6 Sep-04	OW7 Sep-04
		OW7	OW12	Ave.													
<b>Vadose Zone Monitoring</b>																	
Methane	%LEL				0	0	0	0	0	NA	NA	0	NA	2	0	0	
Oxygen	% Vol/Vol				20.9	20.9	21.1	20.8	20.8	NA	NA	20.9	NA	20.9	20.9	20.8	20.9
<b>General Chemistry</b>																	
pH Value	pH units				7.85	7.73	7.76	7.71	7.49	7.63	7.88	7.28	7.56	7.47	8.12	8.02	DRY
pH Value (Field)	pH units				7.83	7.38	7.38	7.14	7.03	7.88	7.88	7.28	7.56	7.47	8.12	8.02	DRY
Temperature (Field)	°C				12.8	10.6	10.3	13.4	10.8	NA	NA	6.72	NA	6.87	7.83	7.31	DRY
Ammonia as N	mg/L				0.05	0.21	< 0.05	< 0.05	< 0.05	0.27	0.17	21.8	< 0.05	22.2	0.14	0.4	DRY
Ammonia (un-ionized)	mg/L				0.0008	0.001	< 0.0002	< 0.0002	< 0.0001	NA	NA	0.0287	< 0.05	0.0284	0.0031	0.0024	DRY
Total Kjeldahl Nitrogen (as N)	mg/L				0.18	0.38	0.17	0.38	0.43	0.7	0.83	24.1	0.38	21.3	< 0.06	0.3	DRY
Nitrate (as N)	mg/L	2.59	6.55	4.57	< 0.1	0.1	0.13	4.81	2.84	0.38	< 0.1	< 0.1	2.94	< 0.1	< 0.1	< 0.1	DRY
Nitrite (as N)	mg/L				< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	0.5	< 0.1	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	DRY
Nitrate + Nitrite (as N)	mg/L				< 0.1	0.1	0.13	4.81	2.84	0.38	< 0.1	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	DRY
Dissolved Organic Carbon (as C)	mg/L	3.1	3.6	3.3	< 0.1	0.1	0.13	4.81	2.84	0.5	< 0.1	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	DRY
Conductivity	µs/cm				1.5	1.8	2	3.1	3.3	2.4	1.8	10.7	4	17.5	0.7	2	DRY
Conductivity (Field)	µs/cm				468	516	439	959	1590	978	582	1870	1580	2080	435	452	DRY
Sulphate (as SO4)	mg/L	253	316	284	468	478	405	851	1379	NA	NA	1646	NA	2080	435	452	DRY
Alkalinity (CaCO3)	mg/L				23	21	8	112	1379	NA	NA	1646	NA	2080	435	452	DRY
Chloride (as Cl)	mg/L				232	260	238	419	458	172	47	32	454	29	23	21	DRY
Colour	TCU	126	129	127	3	5	2	8	393	308	249	852	385	975	244	283	DRY
Calculated Hardness (as CaCO3)	mg/L				< 2.5	9.6	2.8	< 2.5	2.8	60	30	118	59	231	4	4	DRY
Total Cations	meq/L				246	252	234	514	793	545	260	808	821	790	261	259	DRY
Total Anions	meq/L				5.07	5.44	4.73	10.93	17.99	12.32	5.97	21.18	18.64	25.48	5.37	5.67	DRY
Ion Balance	% diff.				5.2	5.78	4.85	11.22	19.28	10.58	6.32	21.03	19.02	28.62	5.47	5.81	DRY
Calculated T.D.S.	mg/L				1.28	3.09	2.32	1.31	3.48	7.61	2.85	0.34	1.01	2.18	0.81	1.19	DRY
					255	287	237	579	1123	637	332	1112	1127	1517	269	294	DRY
<b>Trace Metals</b>																	
Aluminum, Al	mg/L				< 0.005	< 0.005	0.008	< 0.005	< 0.005	< 0.005	0.013	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	DRY
Barium, Ba	mg/L				0.065	0.071	0.008	0.083	0.099	0.123	0.082	0.131	< 0.005	< 0.005	< 0.005	< 0.005	DRY
Boron, B	mg/L	0.50	0.54	0.52	0.012	0.019	< 0.005	0.458	0.814	0.353	0.064	0.729	0.855	0.321	0.068	0.08	DRY
Cadmium, Cd	mg/L	0.002	0.002	0.002	0.0002	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	DRY
Calcium, Ca	mg/L				59.1	65.9	66.5	91	178	134	80.8	188	181	212	62.3	66.9	DRY
Chromium, Cr	mg/L				< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	DRY
Copper, Cu	mg/L	0.01	0.01	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	DRY
Iron, Fe	mg/L	0.50	0.50	0.50	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	DRY
Lead, Pb	mg/L	0.18	0.18	0.18	< 0.03	0.21	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	DRY
Magnesium, Mg	mg/L	0.003	0.003	0.003	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	DRY
Manganese, Mn	mg/L				24	21.3	16.5	69.7	85.8	51.1	26.2	81.7	89.5	63.4	25.5	22.3	DRY
Potassium, K	mg/L	0.10	0.03	0.06	0.347	0.101	0.18	< 0.005	0.025	0.244	0.031	1.56	0.032	0.667	0.293	0.069	DRY
Silica, Reactive (as SiO2)	mg/L				0.7	0.8	0.4	14.5	22	5.5	4.3	49.9	22.2	27.5	0.8	0.9	DRY
Sodium, Na	mg/L	100.5	104.2	102.3	5.82	5.17	2.35	4.5	3.65	4.4	5.63	4.99	22.2	27.5	0.8	0.9	DRY
Zinc, Zn	mg/L	2.50	2.51	2.50	0.11	< 0.005	0.014	< 0.005	0.008	0.005	0.014	< 0.005	0.008	< 0.005	0.008	< 0.005	DRY

Note: While concentrations of parameters exceeding the Reasonable Use Criteria

Appendix D  
Groundwater Chemistry - Observation Wells  
Kinross Landfill Site

Parameter	Units	RUC			OW12 Sep-04	OW13 Sep-04	OW13J Sep-04	OW13D Sep-04	OW14 Sep-04	OW13I-04 Sep-04
		OW7	OW12	Ave.						
<b>Vadose Zone Monitoring</b>										
Methane	%LEL				0	1	1	1	55	NA
Oxygen	% Vol/Vol				20.9	20.9	20.9	20.9	15.2	NA
<b>General Chemistry</b>										
pH Value	pH units				7.89	7.63	7.73	7.85	7.53	8.05
pH Value (Field)	pH units				7.01	6.9	7.01	7.83	7.53	8.05
Temperature (Field)	°C				15.3	12.1	12.3	11.4	15.1	NA
Ammonia as N	mg/L				< 0.05	0.18	< 0.05	< 0.05	24.6	< 0.05
Ammonia (un-ionized)	mg/L				< 0.0001	0.0003	< 0.0001	< 0.0004	0.0186	NA
Total Kjeldahl Nitrogen (as N)	mg/L				< 0.05	0.22	< 0.05	< 0.05	25.2	< 0.05
Nitrate (as N)	mg/L	2.59	6.55	4.57	5.8	2.67	2	2.06	< 0.1	< 0.1
Nitrite (as N)	mg/L				< 0.02	0.02	0.04	0.03	< 0.02	< 0.02
Nitrate + Nitrite (as N)	mg/L				5.8	2.69	2.04	2.09	< 0.1	< 0.1
Dissolved Organic Carbon (as C)	mg/L	3.1	3.6	3.3	3	2.6	2	2	7.7	1.8
Conductivity	us/cm				1020	1610	1570	1570	1720	530
Conductivity (Field)	us/cm				863	1375	1325	478	1454	NA
Sulphate (as SO4)	mg/L	253	316	284	145	447	458	455	7	48
Alkalinity (CaCO3)	mg/L				11	391	384	390	817	236
Chloride (as Cl)	TCU	126	129	127	64	60	60	60	98	7
Colour	mg/L				3.2	< 2.5	4	< 2.5	7.9	< 2.5
Calculated Hardness (as CaCO3)	meq/L				530	800	823	823	574	252
Total Cations	meq/L				11.27	18.26	18.85	18.64	18.61	5.74
Total Anions	meq/L				0.41	2.3	1.05	1.24	19.25	5.92
Ion Balance	% diff.				603	1110	1127	1128	1060	315
Calculated T.D.S.	mg/L									
<b>Trace Metals</b>										
Aluminum, Al	mg/L				< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
Barium, Ba	mg/L				0.071	0.081	0.146	0.146	0.072	0.077
Boron, B	mg/L	0.50	0.54	0.52	0.489	0.734	0.78	0.757	0.606	0.043
Cadmium, Cd	mg/L	0.002	0.002	0.002	0.0003	< 0.0001	0.0001	< 0.0001	< 0.0001	< 0.0001
Calcium, Ca	mg/L				90.4	172	181	182	133	80.7
Chromium, Cr	mg/L	0.01	0.01	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
Copper, Cu	mg/L	0.50	0.50	0.50	0.0014	0.0016	0.0013	0.0012	0.0009	< 0.0005
Iron, Fe	mg/L	0.16	0.16	0.16	< 0.03	< 0.03	< 0.03	< 0.03	0.3	0.41
Lead, Pb	mg/L	0.003	0.003	0.003	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005
Magnesium, Mg	mg/L				74	90	90	< 0.0005	< 0.0005	< 0.0005
Manganese, Mn	mg/L	0.10	0.03	0.06	< 0.005	0.027	0.039	0.038	0.82	0.019
Potassium, K	mg/L				12.1	24.6	17.1	17.3	36.9	2.1
Silica, Reactive (as SiO2)	mg/L				4.24	3.93	4.68	4.67	4.68	6.66
Sodium, Na	mg/L	100.5	104.2	102.3	8.2	37.3	40.7	40.3	102	15.2
Zinc, Zn	mg/L	2.50	2.51	2.50	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005

Note: While concentrations of parameters exceeding the Reasonable Use Criteria

Appendix D  
 Historical Groundwater Quality Data  
 Kinross Landfill Site

Parameter	Units	RUC	TDL	OW4 5/25/2005	OW5 5/25/2005	OW6 5/25/2005	OW7 5/25/2005	OW12 5/25/2005	OW13 5/25/2005	OW13U 5/25/2005	OW13D 5/25/2005	OW14 Leachate 5/25/2005	OW14 Leachate-Rep 5/25/2005	OW4 9/28/2005	OW5 9/28/2005	OW6 9/28/2005	OW7 9/28/2005	OW12 9/28/2005	OW13 9/28/2005	OW13U 9/28/2005	OW13D 9/28/2005	OW14 9/28/2005		
FIELD MONITORING RESULTS																								
Methane	%Vol			N/A	0.15	<0.06	<0.06	<0.06	<0.06	0.05	<0.05	0.06	0.06											
Oxygen	%Vol			N/A	20.9	20.8	20.8	20.9	20.3	20.9	21	20.8	19.8											
Temperature	°C			N/A	20.9	20.8	20.8	20.9	20.3	20.9	21	20.8	19.8											
pH				N/A	10.9	12.5	10.3	12.6	12.8	10.8	10.5	9.8	15.3		<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	<0.25	2.5	
Conductivity	µS/cm			N/A	6.55	7.32	7.15	6.97	6.90	6.68	6.91	7.23	6.35		20.8	20.7	20.7	20.8	20.7	20.9	20.9	<0.25	<0.25	
INORGANICS																								
Unionized Ammonia (Calculated)	mg/L			N/A	2078	464	493	421	936	1458	1495	497	1623		6.83	7.69	7.41	DRY	7.04	7.11	7.32	8.17	DRY	
Total Ammonia-N	mg/L			N/A	0.0131	0.0007	0.0007	0.0036	N/A	0.0003	N/A	N/A	0.0114		2184	496	526	DRY	868	1818	1568	848	DRY	
Conductivity	µS/cm			0.06	18.5	0.140	0.270	1.22	N/A	0.0003	N/A	N/A	0.0114		0.0371	0.0015	0.0010	N/A	N/A	0.0038	N/A	0.0054	N/A	
Total Kjeldahl Nitrogen (TKN)	mg/L			2	2040	466	507	436	948	1819	1820	521	1830		18.1	0.110	0.140	DRY	ND	1.39	ND	0.160	DRY	
Nitrite (N)	mg/L			0.1	0.1										1960	468	521	DRY	ND	ND	1500	523	DRY	
Dissolved Organic Carbon	mg/L	0.27	0.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	1830		21	0.5	8	DRY	1.3	2.8	3.1	4.3	DRY	
pH		4.98	0.1	16.2	1.10	0.900	1.00	3.60	ND	ND	ND	ND	ND		18.8	1.20	1.20	DRY	2.80	ND	ND	ND	DRY	
Alkalinity (Total as CaCO3)	mg/L			0.01	7.85	8.20	8.01	8.03	8.11	8.02	8.05	8.26	7.77		ND	ND	ND	DRY	ND	ND	ND	ND	DRY	
Chloride (Cl)	mg/L			1	884	220	247	227	364	336	337	224	738		7.98	8.12	8.02	DRY	7.98	8.03	7.83	8.19	DRY	
p-Alkalinity	mg/L	130	1	151	3.10	3.80	1.22	8.38	62.1	67.9	61.8	62.7	64.3		942	252	264	DRY	361	456	456	234	DRY	
Dissolved Nitrate + Nitrate	mg/L			0.3	ND	ND	ND	ND	ND	ND	ND	ND	ND		188	3.00	6.00	DRY	11.0	66.0	66.0	8.00	DRY	
Nitrate (N)	mg/L	6.8	0.3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		ND	ND	ND	DRY	ND	ND	ND	ND	DRY	
Phosphate-P	mg/L	7.1	0.2	0.10	ND	0.10	0.10	0.8	3.8	1.9	ND	0.10	ND		ND	ND	ND	DRY	ND	ND	ND	ND	DRY	
Sulphate (SO4)	mg/L	320	1	40.8	20.4	17.8	4.80	146	426	442	43.0	13.8	16.6		ND	ND	ND	DRY	7.1	3.8	2.7	1.5	DRY	
CALCULATED VALUES																								
Anion Sum	meq/L			N/A	22.8	4.92	5.42	4.88	10.8	17.7	18.0	6.83	16.8		24.3	5.87	6.09	DRY	11.8	19.8	19.5	6.80	DRY	
Bicarb. Alkalinity (calc. as CaCO3)	mg/L			1	878	217	245	225	350	335	333	220	732		938	248	281	DRY	387	480	452	231	DRY	
Calculated TDS	mg/L			1	1200	266	271	232	563	1050	1070	287	742		4	3	3	DRY	631	1110	1110	317	DRY	
Carb. Alkalinity (calc. as CaCO3)	mg/L			1	8	3	2	2	4	3	4	4	4		4	3	3	DRY	3	5	3	3	DRY	
Cation Sum	meq/L			N/A	24.4	5.85	5.85	5.03	11.2	19.3	18.6	6.89	18.7		17.8	23.7	5.74	DRY	12.1	20.1	20.4	6.31	DRY	
Hardness (CaCO3)	mg/L			N/A	750	280	280	240	630	840	850	630	630		760	280	280	DRY	570	850	800	270	DRY	
Langelier Index (@ 20C)				N/A	3.35	8.74	2.08	3.91	1.58	4.39	4.17	0.930	0.60		1.35	1.55	0.00	DRY	0.962	0.802	2.18	3.33	DRY	
Langelier Index (@ 4C)				N/A	1.82	0.943	0.826	0.822	1.15	1.28	1.30	0.973	1.33		1.37	0.926	0.884	DRY	1.07	1.42	1.21	0.987	DRY	
Saturation pH (@ 20C)				N/A	1.27	0.963	0.977	0.972	0.904	1.02	1.06	0.724	1.33		1.12	0.877	0.838	DRY	0.828	1.17	0.985	0.738	DRY	
Saturation pH (@ 4C)				N/A	6.33	7.25	7.18	7.21	6.96	6.78	6.76	7.28	6.45		6.44	7.18	7.13	DRY	6.81	6.82	6.81	7.21	DRY	
METALS																								
Dissolved Aluminum (Al)	mg/L			0.005	ND	0.009	0.009	0.010	0.009	0.032	ND	ND	ND		6.54	7.44	7.38	DRY	7.16	8.86	8.86	7.48	DRY	
Dissolved Arsenic (As)	mg/L			0.007	0.001																			
Dissolved Barium (Ba)	mg/L			0.549	0.906	0.787	0.068	0.008	0.072	0.080	0.078	0.080	0.071		0.006	0.001	0.063	DRY	ND	ND	ND	0.040	ND	DRY
Dissolved Boron (B)	mg/L			2.7	0.91	0.28	ND	0.028	0.030	0.49	0.84	0.78	0.040		0.240	0.072	0.077	DRY	0.53	0.77	0.086	0.092	DRY	
Dissolved Cadmium (Cd)	mg/L			0.0018	0.0001	0.0002	ND	ND	0.0008	ND	0.0002	ND	0.0001		0.90	0.33	0.018	DRY	0.0014	0.0003	0.0001	ND	DRY	
Dissolved Calcium (Ca)	mg/L			0.014	0.005	ND	ND	ND	ND	188	192	62.7	188		ND	ND	0.0001	DRY	ND	ND	ND	ND	DRY	
Dissolved Chromium (Cr)	mg/L			0.5	0.001	ND	ND	ND	ND	ND	ND	ND	ND		200	66.0	75.0	DRY	98.0	180	200	71.0	DRY	
Dissolved Copper (Cu)	mg/L			0.18	0.05	ND	ND	ND	0.001	0.002	0.001	0.001	ND		0.007	ND	ND	DRY	ND	ND	ND	ND	DRY	
Dissolved Lead (Pb)	mg/L			0.003	0.0005	ND	ND	ND	ND	ND	ND	ND	ND		ND	ND	ND	DRY	0.004	0.003	0.002	ND	DRY	
Dissolved Magnesium (Mg)	mg/L			0.028	0.002	0.987	0.243	0.0520	0.0280	ND	0.0280	0.0200	0.0170		81.0	27.0	22.0	DRY	78.0	68.0	98.0	23.0	DRY	
Dissolved Manganese (Mn)	mg/L			0.2	27.9	0.800	0.800	0.500	8.70	24.0	19.8	1.00	33.7		34.0	0.910	0.270	DRY	ND	0.0480	0.0360	0.0180	DRY	
Dissolved Silicon (Si)	mg/L			0.05	8.54	7.20	6.03	2.52	4.64	4.22	4.58	7.07	5.48		5.48	31.0	0.820	DRY	4.70	29.0	18.0	1.20	DRY	
Dissolved Sodium (Na)	mg/L			104	0.1	168	3.40	8.80	0.800	8.20	41.8	14.4	91.0		140	3.50	11.9	DRY	9.80	48.0	46.0	18.0	DRY	
Dissolved Zinc (Zn)	mg/L			2.5	0.005	0.056	0.012	ND	0.0080	ND	0.081	ND	0.0070		0.012	0.084	0.082	DRY	0.010	0.0080	0.028	ND	DRY	

N/A = Not Applicable  
 ND = Not Detected  
 TDL = Typical Detection Limit. Actual detection limit varies with concentration of each sample.  
 Reasonable Use Criteria (RUC) were calculated in accordance with MOEE Guidelines B-7 using 2 years of data for OW7 and OW12 and applying the detection limit when a non-detect is reported.  
 Refer to Table 5 for notes relating to landfill gas measurements.

Standard Groundwater Quality Package  
Kinross Landfill Site

Parameter	Short LD.	Unit	RUC Max (OW7&OW12)	OW6 M.O.L.	OW4 Down Town 17-Apr-06	OW5 Down Town 17-Apr-06	OW6 Down Town 17-Apr-06	OW7 Up Town 17-Apr-06	OW8 Up Town 17-Apr-06	OW9 Up Town 17-Apr-06	OW10 Up Town 17-Apr-06	OW11 Up Town 17-Apr-06	OW12 Up Town 17-Apr-06	OW13M Down Town 17-Apr-06	OW13N Down Town 17-Apr-06	OW13O Down Town 17-Apr-06	OW14 leachate Town 17-Apr-06	OW6-Rep Down Town 17-Apr-06	OW4 Down Town 01-Oct-06	OW5 Down Town 03-Oct-06
Temperature		°C			11	8.4	9	8.2	DRY	DRY	DRY	DRY	12.2	10.5	10.5	10	11.6	9	15	18.2
pH		pH			8.18	7.32	7	7.24	DRY	DRY	DRY	DRY	7.08	6.96	6.86	7.38	6.86	7	6.28	7.15
Electrical Conductivity		µS/cm			1988	900	508	415	DRY	DRY	DRY	DRY	863	1682	1338	620	1256	508	2651	805
INORGANICS																				
pH		pH			129	250	0.1	7.58	8.19	6.16	8.11	DRY	DRY	DRY	DRY	DRY	DRY	8.13	7.92	7.94
Chloride		mg/L			93.3	3.14	4.6	0.96	DRY	DRY	DRY	DRY	6.91	70.8	54.6	8.80	7.54	22.8	4.15	122
Electrical Conductivity		µS/cm			1980	504	520	407	DRY	DRY	DRY	DRY	842	1780	1380	538	1310	608	2010	495
Total Hardness (as CaCO3)		mg/L			712	248	274	221	DRY	DRY	DRY	DRY	463	862	688	217	563	241	677	250
Desoxygenated Organic Carbon (DOC)		mg/L			<1	<1	<1	<1	DRY	DRY	DRY	DRY	<1	<1	<1	<1	<1	<1	<1	16
Total Dissolved Solids		mg/L			562	500	29	1878	282	274	96	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Arsenite (un-ionized)		mg/L			0.0043	0.0001	0.0008	<0.0001	DRY	DRY	DRY	DRY	594	1218	1848	322	782	294	1678	284
Arsenite as N		mg/L			0.02	14.3	<0.04	0.47	<0.04	DRY	DRY	DRY	DRY	<0.0001	0.0003	0.0011	0.012	0.0009	0.0116	0.0007
Nitrate + Nitrite as N		mg/L			6.94	10	0.05	<0.05	<0.05	DRY	DRY	DRY	DRY	0.05	0.04	0.18	0.28	11.7	0.52	22.1
Nitrate as N		mg/L			0.29	1	0.05	<0.05	<0.05	DRY	DRY	DRY	DRY	0.05	0.04	0.18	0.28	11.7	0.52	22.1
Nitrite as N		mg/L			6.1	10	0.1	<0.10	<0.10	DRY	DRY	DRY	DRY	0.05	0.04	0.18	0.28	11.7	0.52	22.1
Total Kjeldahl Nitrogen		mg/L			0.1	<0.10	<0.10	<0.10	<0.10	DRY	DRY	DRY	DRY	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Bromide		mg/L			17.1	10	0.1	<0.10	<0.10	DRY	DRY	DRY	DRY	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Fluoride		mg/L			0.1	15.6	0.13	0.43	0.13	DRY	DRY	DRY	DRY	4.79	5.11	1.24	0.08	<0.05	<0.05	<0.05
Sulfate		mg/L			1.1	1.5	0.05	0.25	<0.05	DRY	DRY	DRY	DRY	0.21	5.11	1.24	<0.10	<0.10	<0.10	<0.10
Orthophosphate as P		mg/L			311	500	0.1	75.8	23.6	20.3	4.4	DRY	DRY	DRY	0.8	<0.05	0.08	<0.05	<0.05	<0.05
Saturation pH		pH			NA	NA	0.10	<0.10	<0.10	<0.10	<0.10	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
pH-Sat (as CaCO3)		mg/L			8	6.11	7.06	7.06	7.06	DRY	DRY	DRY	DRY	594	337	337	44.1	20.7	22.9	
Hardness (as CaCO3)		mg/L			9	<5	<5	<5	<5	DRY	DRY	DRY	DRY	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Calcium		mg/L			10	885	240	248	224	DRY	DRY	DRY	DRY	6.89	6.42	6.46	7.14	6.3	7.28	
Magnesium		mg/L			NA	18.3	4.59	4.88	3.79	DRY	DRY	DRY	DRY	<5	<5	<5	<5	<5	<5	
% Difference/Calc Balance		%			NA	20.8	5.06	5.16	4.48	DRY	DRY	DRY	DRY	346	348	383	240	675	283	
Carbonate (as CaCO3)		mg/L			NA	6.5	4.9	4.8	8.3	DRY	DRY	DRY	DRY	8.18	18.3	15.1	5.13	12.5	4.6	
Bicarbonate (as CaCO3)		mg/L			NA	10	<10	<10	<10	DRY	DRY	DRY	DRY	8.63	18.7	18.1	5.07	15	6.27	
Langlier Index		mg/L			10	885	240	248	224	DRY	DRY	DRY	DRY	8.18	17.8	1.2	0.8	9	4.67	
Aggressive Index		mg/L			NA	1.47	1.13	1.1	1.03	DRY	DRY	DRY	DRY	<10	<10	<10	<10	<10	<10	
Ryznar Stability Index		mg/L			NA	13.4	13	12.8	12.8	DRY	DRY	DRY	DRY	1.44	1.5	1.46	1.13	1.31	1.18	
METALS		mg/L			NA	4.6	5.9	6.1	DRY	DRY	DRY	DRY	DRY	5.3	4.8	5	8	5	6.8	
Aluminum		mg/L			0.009	0.025	0.004	0.007	<0.004	<0.004	<0.004	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Arsenic		mg/L			1.8	1	0.01	0.309	0.024	0.019	<0.010	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Boron		mg/L			0.29	1	0.002	0.221	0.051	0.062	0.008	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Calcium		mg/L			0.0028	0.005	0.002	<0.002	<0.002	<0.002	<0.002	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Cadmium		mg/L			0.015	0.05	0.003	<0.003	<0.003	<0.003	<0.003	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Chromium		mg/L			0.5	1	0.003	<0.003	<0.003	<0.003	<0.003	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Copper		mg/L			0.52	0.3	0.005	14.4	8.688	<0.003	<0.003	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Iron		mg/L			0.027	0.05	0.05	24	0.8	1.47	6.636	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Potassium		mg/L			200	200	0.002	8.886	0.389	0.983	0.94	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Magnesium		mg/L			104	0.05	0.002	19	2.84	8.21	0.77	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Manganese		mg/L			0.004	0.01	0.002	<0.002	<0.002	<0.002	<0.002	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Sodium		mg/L			0.006	0.01	0.004	<0.004	<0.004	<0.004	<0.004	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Selenium		mg/L			2.5	5	0.004	0.007	0.007	0.004	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Lead		mg/L			0.001	0.06	<0.001	<0.001	<0.001	<0.001	<0.001	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Mercury		mg/L			0.001	0.06	<0.001	<0.001	<0.001	<0.001	<0.001	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Silver		mg/L			0.001	0.06	<0.001	<0.001	<0.001	<0.001	<0.001	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Silicon		mg/L			0.001	0.06	<0.001	<0.001	<0.001	<0.001	<0.001	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Zinc		mg/L			0.001	0.06	<0.001	<0.001	<0.001	<0.001	<0.001	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Phenols		mg/L			0.001	0.06	<0.001	<0.001	<0.001	<0.001	<0.001	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	
Total Phosphorus		mg/L			0.001	0.06	<0.001	<0.001	<0.001	<0.001	<0.001	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	

This note is to be reviewed with the comments in Appendix D

Short LD.	Unit	RUC Max (OW7&OW12)	OW6		OW7		OW8		OW9		OW10		OW11		OW12		OW13B		OW13C		OW13D		OW14		OW13B-Rep			
			Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06	Down Town 03-Oct-06	Up Town 03-Oct-06
°C	°C		15.5	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
pH	N/A		6.78	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Th. Cond.	us/cm		517	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
pH	N/A		8.28	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
CT	mg/L	129	4.42	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Th. Cond.	us/cm		528	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Hard(Calc)	mg/L		242	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
DOC	mg/L	3.25	1	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Th. TDS	mg/L	552	290	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
NH <sub>4</sub> -N	mg/L		0.0006	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
NH <sub>3</sub> -N	mg/L		0.38	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
NO <sub>2</sub> -N	mg/L	5.94	<0.05	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
NO <sub>3</sub> -N	mg/L	0.28	<0.05	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
NO <sub>2</sub> +NO <sub>3</sub>	mg/L	6.1	<0.10	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
TKN	mg/L		0.43	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Br	mg/L		<0.06	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
F	mg/L	1.1	1.17	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
SO <sub>4</sub> <sup>2-</sup>	mg/L	311	16.3	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
PO <sub>4</sub> <sup>3-</sup>	mg/L		<0.10	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
pH <sub>s</sub>	N/A		7.02	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Alk 8.3	mg/L		7	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Alk 4.2	mg/L		267	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Anion	mg/L		5.14	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Cation	mg/L		6.29	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
CAS	%		1.5	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
CO <sub>3</sub> <sup>2-</sup>	mg/L		14	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
HCO <sub>3</sub> <sup>-</sup>	mg/L		253	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Li	N/A		1.26	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Li	N/A		13.1	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Li	N/A		5.76	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Al	mg/L		<0.004	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
As	mg/L	0.009	<0.003	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
B	mg/L	1.6	0.029	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Ba	mg/L	0.29	0.061	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Cd	mg/L		91.8	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Co	mg/L	0.0028	<0.002	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Cr	mg/L	0.016	<0.003	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Cu	mg/L	0.5	<0.003	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Fe	mg/L	0.52	8.874	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
K	mg/L		1.02	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Mg	mg/L		21.5	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Mn	mg/L	0.027	8.086	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Na	mg/L	104	8.11	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Pb	mg/L	0.004	<0.002	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Se	mg/L	0.008	<0.004	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Si	mg/L		5.4	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Zn	mg/L	2.5	<0.004	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
Phenol	mg/L		<0.001	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY
P (Tot.)	mg/L		<0.001	DRY	DRY																							

Appendix D  
Leachate Indicator Parameters - Historical Results  
Kinloss Landfill Site

Date	Chloride Concentration (mg/L)										
	OW4	OW5	OW6	OW7	OW12	OW13	OW13 I	OW13D	OW14	SW1	SW2
Jun-88	102.8	1.6	6.0	1.5							
Sep-88	84.5	0.9	5.0	0.9							5.3
Jun-89	57.6	1.3	6.1	2.3							4.7
Sep-89	93.4	1.8	4.9	0.6							4.1
Jun-90	107.0	0.9	5.0	1.3							4.5
Sep-90	107.0	1.3	5.0	1.3						4.5	5.9
Jun-91	34.5	1.3	5.5	1.6						2.7	4.8
Sep-91	34.7	1.8	4.5	1.2						3.1	5.4
Jun-92	36.2	2.1	4.8	1.2						2.7	5.3
Sep-92	38.5	0.9	3.9	1.1						6.0	7.8
Jun-93	29.2	0.9	3.7	0.8						3.2	5.2
Sep-93	36.1	1.1	3.6	0.7						5.0	6.2
Jun-94	26.4	1.4	3.8	1.2						1.7	4.2
Sep-94	33.0	1.7	3.4	1.0						5.0	6.9
Jun-95	30.9	1.3	3.0	0.9						1.8	3.7
Sep-95	37.3	1.5	4.2	0.3						3.8	5.3
Jun-96	21.0	1.0	4.0	0.0						1.9	3.6
Sep-96	18.0	4.0	4.0	1.0						7.3	5.9
Jun-97	4.0	1.0	2.4	1.0						1.0	3.0
Sep-97	21.0	4.0	6.0	2.0						2.0	6.0
May-98	31.0	4.0	4.0	2.0						0.5	3.7
Sep-98	33.0	2.0	5.0	2.0	8.0	63.0				4.0	7.0
May-99	33.0	1.0	4.0	1.0	8.0	60.0				2.0	4.0
Sep-99	27.0	1.0	5.0	1.0	9.0	47.0					5.0
Jun-00	46.0	1.0	4.0	1.0	8.0	34.0				2.0	5.0
Sep-00	64.0	2.0	2.0	1.0	8.0	36.0					4.0
May-01	162.0	2.0	2.0	1.0	7.0	31.0				2.0	4.0
Sep-01	128.0	2.0	1.0	1.0	4.0	42.0				3.0	4.0
May-02	117.0	10.0	2.0	1.0	5.0	50.0				4.0	4.0
Sep-02	104.0	2.0	5.0	1.0	5.0	55.0				5.0	5.0
May-03	138.0	3.0	4.0	2.0	7.0	67.0				9.0	8.0
Oct-03	180.0	3.0	4.0	1.0	8.0	68.0					8.0
May-04	204.0	3.0	5.0	2.0	7.0	57.0				4.0	5.0
Sep-04	231.0	4.0	4.0	1.0	6.0	60.0			27.0	7.0	6.0
May-05	151.0	3.1	3.8	1.2	11.0	64.0	30.0	13.0	118.0	5.0	5.0
Sep-05	169.0	3.0	6.0	1.0	9.4	62.1	60.0	60.0	98.0	12.0	7.0
Apr-06	93.3	3.1	4.8	1.0	11.0	69.0	67.9	6.2	62.7	4.3	5.8
Oct-06	122.0	3.7	4.4	1.0	6.9	70.5	69.0	8.0		6.0	7.0
					9.9	64.5	54.6	6.7	22.8	3.9	5.2
							65.0	14.2	15.2	6.9	9.3



Appendix D  
Leachate Indicator Parameters - Historical Results  
Kinloss Landfill Site

Date	Conductivity (uS/cm)										
	OW4	OW5	OW6	OW7	OW12	OW13	OW13 I	OW13D	OW14	SW1	SW2
Jun-88	1800	455	545	457							
Sep-88	1530	478	501	586							505
Jun-89	1590	449	535	460							405
Sep-89	1620	512	538	555							445
Jun-90	1580	455	532	420							409
Sep-90	1580	441	528	420						388	510
Jun-91	1520	447	490	430						492	467
Sep-91	1540	465	538	530						423	485
Jun-92	1590	459	529	434						428	471
Sep-92	1530	466	539	555						407	517
Jun-93	1440	448	523	428						497	510
Sep-93	1490	458	515	531						447	460
Jun-94	1430	445	506	447						411	454
Sep-94	1480	452	516	613						377	468
Jun-95	1570	444	516	438						420	502
Sep-95	1540	456	528	559						426	479
Jun-96	1230	395	449	394						425	523
Sep-96	1400	442	509	456						461	329
Jun-97	1070	431	509	434						273	451
Sep-97	1030	436	528	400						356	437
May-98	775	544	467	407						366	512
Sep-98	720	456	485	842	1430					441	430
May-99	1100	442	489	879	1410					376	509
Sep-99	931	438	489	855	1450						440
Jun-00	1160	443	480	843	1300					360	465
Sep-00	1190	441	488	907	1270						440
May-01	1620	441	482	900	1240					396	462
Sep-01	1770	477	524	890	1410					391	437
May-02	1680	724	465	876	1530					382	526
Sep-02	1700	448	486	404	859	1440				469	510
May-03	2030	525	537	504	863	1480				500	488
Oct-03	2120	468	511	609	994	1880					463
May-04	2300	488	516	439	965	1570				370	495
Sep-04	2360	487	518		959	1590				439	436
May-05	2040	455	507	436	1020	1810	978	582	1620	372	537
Sep-05	1960	489	521		948	1510	1570	1570	1870	1720	476
Apr-06	1980	504	520	407	959	1530	1520	521	1530	557	499
Oct-06	2010	495	528		882	1760	1500	523	1530	415	469
					918	1630	1380	538	1310	425	544
							1590	825	1230	452	

Appendix D  
Leachate Indicator Parameters - Historical Results  
Kinross Landfill Site


Date	Hardness (mg/L)										
	OW4	OW5	OW6	OW7	OW12	OW13	OW13 I	OW13D	OW14	SW1	SW2
Jun-88	668	237	246	264							
Sep-88	585	242	224	321							275
Jun-89	326	238	341	234							212
Sep-89	600	255	234	283							239
Jun-90	636	253	258	228							217
Sep-90	636	251	241	228						207	282
Jun-91	634	222	227	226						298	240
Sep-91	627	243	255	287						225	263
Jun-92	786	247	266	246						238	254
Sep-92	614	200	187	228						218	291
Jun-93	711	239	269	255						288	269
Sep-93	643	248	247	270						259	278
Jun-94	661	257	258	260						243	249
Sep-94	700	252	262	335						209	267
Jun-95	794	232	254	251						235	300
Sep-95	765	248	252	316						256	265
Jun-96	811	234	243	243						237	302
Sep-96	736	226	237	260						263	197
Jun-97	600	221	270	256						161	252
Sep-97	565	241	175	166						186	246
May-98	424	174	257	270						203	232
Sep-98	407	233	252		550	903				229	272
May-99	613	244	262	296	581	879				277	286
Sep-99	515	266	275		565	855					257
Jun-00	513	282	282	303	616	831				227	307
Sep-00	488	248	260	298	562	823					271
May-01	710	264	271	264	308	701				234	278
Sep-01	646	252	274		582	855				236	288
May-02	785	189	259	236	589	850				258	311
Sep-02	745	258	260		495	797				258	292
May-03	905	287	286	291	557	889				274	297
Oct-03	800	256	273	333	549	1060					230
May-04	820	248	252	234	542	809				195	269
Sep-04	790	261	259		514	793			783	235	227
May-05	750	280	260	240	530	800	545	260	806	198	277
Sep-05	760	280	280		530	840	823	823	574	308	290
Apr-06	712	246	236	221	570	860	860	250	630	240	250
Oct-06	677	250	242		453	862	900	270		210	244
					463	844	699	217	563	207	285
							816	251	493	242	

Appendix D  
Leachate Indicator Parameters - Historical Results  
Kinloss Landfill Site


Date	D.O.C. (mg/L)										
	OW4	OW5	OW6	OW7	OW12	OW13	OW13I	OW13D	OW14	SW1	SW2
Jun-88	1.7	2.0	3.0	3.0							
Sep-88	14.5	2.7	2.4	5.2							
Jun-89	11.7	1.3	1.3	3.3							1.6
Sep-89	1.8	1.2	1.0	2.1							6.2
Jun-90	13.0	1.3	1.2	1.2							4.0
Sep-90	13.0	1.2	2.5	1.2						6.5	5.9
Jun-91	12.4	2.4	2.2	9.4						8.0	2.3
Sep-91	26.0	15.2	26.5	13.4						1.0	2.9
Jun-92	11.0	1.8	0.9	1.6						9.3	6.3
Sep-92	8.2	1.3	6.0	1.4						11.7	7.4
Jun-93	7.0	1.0	1.1	1.7						7.3	3.7
Sep-93	7.4	1.8	18.0	1.8						6.2	3.9
Jun-94	7.1	1.5	0.7	1.2						7.6	5.5
Sep-94	7.1	1.6	1.1	1.5						9.3	9.2
Jun-95	5.7	0.7	1.0	0.9						6.8	4.6
Sep-95	6.3	1.5	1.2	16.0						7.2	4.4
Jun-96	4.4	0.6	0.5	0.8						53.0	3.2
Sep-96	8.5	1.1	1.9	4.5						8.3	3.8
Jun-97	5.4	0.6	0.9	0.8						6.8	5.7
Sep-97	6.0	0.6	0.7	0.9						10.0	5.3
May-98	6.2	4.2	0.8	0.6						3.8	2.9
Sep-98	5.3	0.5	0.6	0.6	1.4	1.9				7.1	3.1
May-99	7.2	0.9	0.7	0.9	2.1	2.0				5.4	2.6
Sep-99	6.8	1.0	0.7	0.9	1.8	2.1					3.4
Jun-00	11.7	1.3	0.9	1.1	1.9	2.0				9.3	7.1
Sep-00	8.4	0.7	0.7	1.1	1.3	1.5					1.9
May-01	16.4	0.9	0.6	1.4	1.4	1.6				8.6	5.8
Sep-01	16.2	0.6	1.0	1.4	1.3	2.2				9.8	
May-02	18.9	7.4	1.2	1.1	1.5	3.8				6.2	4.0
Sep-02	17.9	1.1	0.7	1.1	1.9	2.7				7.8	3.5
May-03	12.9	1.0	0.8	1.1	1.8	4.0				3.1	3.2
Oct-03	16.5	0.5	0.5	0.6	1.5	3.1					1.7
May-04	16.6	1.5	1.8	2.0	3.1	3.3				8.7	4.8
Sep-04	17.5	0.7	2.0	3.1	3.0	2.6	2.4	1.8	6.7	7.3	4.6
May-05	16.2	1.1	0.9	1.0	3.9	2.6	2.0	2.0	10.7	6.9	6.0
Sep-05	15.8	1.2	1.2	1.0	2.6	4.4	2.3	0.9	7.7	6.5	2.0
Apr-06	4.0	1.0	1.0	1.0	1.0	1.0	3.6	1.2	9.8	6.0	3.5
Oct-06	15.0	1.0	1.0	1.0	2.0	3.0	3.0	1.0	13.0	15.0**	6.5**
								1.0	10.0	4.0	6.0
								1.0	10.0	9.0	5.3

\*\* Fall 2005 concentrations for SW1 and SW2 are reported as Total Organic Carbon (TOC).


**KINLOSS LANDFILL SITE**  
**Chloride Concentration (mg/L) vs. Time**  
**Downgradient**




**KINLOSS LANDFILL SITE**  
**Conductivity (uS/cm) vs. Time**  
**Downgradient**




**KINLOSS LANDFILL SITE**  
**Hardness (mg/L) vs. Time**  
**Downgradient**



**KINLOSS LANDFILL SITE**  
**D.O.C. (mg/L) vs. Time**  
**Downgradient**



**KINLOSS LANDFILL SITE**  
**Chloride Concentration (mg/L) vs. Time**  
**Upgradient**




F:\Clerical\2006\LNE 08508 (Kinloss LF)\DATA\LNE08508 - 2006 Graphs\Chloride - gw - up


R. J. Burnside & Associates Limited  
 Project Number: LNE08508




**KINLOSS LANDFILL SITE**  
**Conductivity (uS/cm) vs. Time**  
**Upgradient**



**KINLOSS LANDFILL SITE**  
**Hardness (mg/L) vs. Time**  
**Upgradient**



**KINLOSS LANDFILL SITE**  
**D.O.C. (mg/L) vs. Time**  
**Upgradient**



E-2 Summary of groundwater Results (2007 – Present)

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4
		Jan-08	Jul-08	Dec-08	Jul-09	Dec-09	Mar-10	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13	Nov-13
Alkalinity(as CaCO3)	30 - 500 [OG]	925	922	828	853	709	697	590	792	840	836	756	734
Chloride	250 [AO]	120	71	47	54	25	19	30.4	31.5	27.7	20.9	16.1	28.8
Nitrate(as N)	10 (MAC) d	nd	nd	nd	nd	nd	0.4	<0.1	<0.1	<0.1	0.3	11	<0.1
Nitrite(as N)	1 (MAC) d	nd	nd	nd	nd	0.03	0.01	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
Ammonia(as N)		31.8	27	28	40	28	19	28.6	36.1	25.1	20.8	15.6	22.3
Total Kjeldahl Nitrogen(as N)		27	27	29	33	27	20	34.5	31.1	25.5	26.0	18.2	28.6
Organic Nitrogen	0.15	0	0	1	0	0	1	5.9	<0.01	0.40	5.2	2.6	6.3
Phenols		nd	0.003	nd	0.01	nd	<0.001	0.005	0.004	<0.001	<0.001	<0.001	0.002
Dissolved Organic Carbon(DOC)	5 [AO]	15.5	14.8	11	14.7	9.1	6.5	12.6	10.8	11.2	8.6	17.8	23.2
Conductivity (us/cm)		2060	1930	1690	1760	1470	1410	1670	1640	1530	1440	1430	1290
pH		7.7	7.7	7.5	7.4	7.7	7.5	7.19	7.25	7.33	7.26	7.44	7.48
Sulphate (as SO4)	250 (AO)	72	57	85	51	84	79	33	54	32	65	66	56
Hardness(as CaCO3)	80-100 [OG]	710	720	690	650	600	650	699	728	610	688	668	587
Aluminum	0.1 [OG]	0.006	0.005	nd	0.007	nd	<0.005	0.06	0.06	0.05	0.06	0.06	0.07
Barium	1 [MAC]	0.29	0.25	0.22	0.25	0.16	0.18	0.243	0.238	0.211	0.204	0.192	0.192
Boron	5 [IMAC]	0.36	0.35	0.35	0.44	0.34	0.27	0.488	-	0.424	0.381	0.385	0.371
Cadmium	0.005 (MAC)	0.0005	nd	nd	nd	0.0006	<0.0001	<0.00002	<0.00002	<0.00002	0.00010	<0.00002	<0.00002
Calcium	-	188	190	190	180	170	190	191	203	165	201	199	172
Chromium	0.05 (MAC)	nd	nd	nd	nd	nd	<0.005	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	0.001	nd	nd	nd	0.001	0.001	<0.002	<0.002	<0.002	<0.002	<0.002	0.0024
Iron	0.3 [AO]	13	8.8	6.2	17	1.6	16	19.0	17.2	15.6	14.5	13.9	13.1
Lead	0.01 (MAC)c	nd	nd	nd	nd	nd	<0.0005	<0.00002	<0.00002	0.00006	0.00003	<0.00002	0.00006
Magnesium	-	57.1	58	52	51	43	44	52.9	53.5	48.2	45.0	41.7	38.3
Manganese	0.05 [AO]	0.56	0.76	0.93	0.76	0.63	0.840	0.906	0.753	0.868	0.758	0.839	0.683
Potassium	-	30	32	29	29	27	20	29.6	33.0	25.6	24.7	21.4	21.3
Sodium	200 [AO]	160	110	82	87	44	40	61.8	62.3	49.0	46.9	29.2	44.8
Zinc	5 [AO]	0.006	0.01	0.014	nd	0.016	0.026	<0.005	<0.005	0.012	0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
10. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4
		Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19
Alkalinity(as CaCO3)	30 - 500 [OG]	731	718	683	664	973	726	738	658	663	655	663	605
Chloride	250 [AO]	19.3	17.1	14.3	12.7	17.1	14.2	11.6	8.4	12.4	16.2	10.0	11.9
Nitrate(as N)	10 (MAC) d	<0.1	<0.1	<0.25	<0.5	<0.1	<0.1	<0.05	<0.1	<0.05	<0.05	<0.05	0.10
Nitrite(as N)	1 (MAC) d	<0.1	<0.1	<0.25	<0.5	<0.1	<0.1	0.64	<0.1	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		23.8	21.0	21.0	21.2	21.6	18.8	21.8	18.2	25.4	26.0	3.97	23.4
Total Kjeldahl Nitrogen(as N)		27.5	23.2	22.2	22.4	21.9	19.6	22.9	20.1	25.6	28.3	26.4	31.0
Organic Nitrogen	0.15	3.7	2.2	1.2	1.20	0.3	0.8	1.10	1.90	0.20	2.30	22.43	7.60
Phenols		<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.012	<0.002	<0.002
Dissolved Organic Carbon(DOC)	5 [AO]	15	13.7	8.5	5.9	9.3	8.1	<0.2	12.5	8.9	14.0	27.7	10.9
Conductivity (us/cm)		1490	1290	1360	1270	1420	1380	1390	1240	1300	1360	1320	1270
pH		7.44	7.32	7.87	7.80	7.36	7.35	7.31	7.41	7.4	7.14	7.48	7.27
Sulphate (as SO4)	250 (AO)	41	45	29.0	57.4	27	60	29	27	27	29	19	35
Hardness(as CaCO3)	80-100 [OG]	664	587	559	607	630	674	635	592	576	588	637	561
Aluminum	0.1 [OG]	0.07	0.04	0.019	0.006	0.05	0.06	0.05	0.10	0.09	0.09	0.09	0.08
Barium	1 [MAC]	0.209	0.180	0.169	0.177	0.199	0.201	0.200	0.182	0.193	0.212	0.191	0.166
Boron	5 [IMAC]	0.460	0.389	0.395	0.322	0.386	0.401	0.413	0.393	0.434	0.406	0.475	0.362
Cadmium	0.005 (MAC)	<0.00002	<0.00002	<0.001	<0.001	<0.00002	0.00003	<0.000014	<0.000014	<0.000015	<0.000015	<0.000015	<0.000028
Calcium	-	195	175	166	179	188	205	189	177	167	180	191	171
Chromium	0.05 (MAC)	<0.002	<0.002	<0.003	0.004	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.001
Copper	1 [AO]	<0.002	0.0003	<0.003	<0.003	<0.002	0.0005	<0.002	<0.002	<0.002	<0.002	<0.002	0.0028
Iron	0.3 [AO]	18.9	16.1	17.2	13.0	18.7	20.7	17.1	14.3	19.4	19.0	23.5	18.1
Lead	0.01 (MAC)c	<0.00002	<0.00002	<0.002	<0.002	<0.00002	0.00006	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002	0.00006
Magnesium	-	43.1	36.5	35.2	38.8	39.2	39.5	39.6	36.4	38.6	33.5	38.8	32.6
Manganese	0.05 [AO]	0.941	0.848	0.885	0.787	0.818	0.807	0.657	0.658	0.736	0.676	0.778	0.625
Potassium	-	24.3	21.8	19.1	22.4	21.7	22.8	23.1	21.9	23.2	22.7	21.0	20.8
Sodium	200 [AO]	45.7	37.6	27.0	25.9	31.4	36.9	35.0	24.1	30.3	41.8	26.3	24.3
Zinc	5 [AO]	<0.005	<0.005	0.006	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
10. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW4	OW4	OW4	OW4	OW4	OW4	OW4	OW4
		Jul-20	Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	661	608	641	663	633	712	690	732
Chloride	250 [AO]	10.9	9.6	7.9	7.6	7.8	11.9	7.9	12.7
Nitrate(as N)	10 (MAC) d	0.1	<0.05	<0.05	0.29	<0.05	0.10	<0.05	0.25
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		24.8	25.8	20.6	14.0	14.9	26.2	22.8	25.1
Total Kjeldahl Nitrogen(as N)		27.4	37.2	20.6	15.0	19.4	28.2	21.5	146
Organic Nitrogen	0.15	2.60	11.40	<0.1	1.0	4.5	2.0	<0.1	120.9
Phenols		<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	13.1	8.9	12.0	8.1	11.7	8.8	9.9	15.2
Conductivity (us/cm)		1270	1260	1270	1230	1270	1330	1270	1410
pH		7.27	7.19	7.24	7.44	7.25	7.69	7.47	7.32
Sulphate (as SO4)	250 (AO)	21	29	33	29	15	17	25	14
Hardness(as CaCO3)	80-100 [OG]	579	595	667	609	625	581	575	597
Aluminum	0.1 [OG]	0.08	0.08	0.11	0.10	0.06	0.05	0.05	0.1
Barium	1 [MAC]	0.188	0.191	0.185	0.152	0.166	0.188	0.148	0.192
Boron	5 [IMAC]	0.445	0.399	0.402	0.390	0.440	0.465	0.382	0.468
Cadmium	0.005 (MAC)	<0.000028	<0.000028	<0.000015	0.000024	<0.000028	<0.000028	<0.000028	<0.000015
Calcium	-	174	178	206	189	194	178	175	184
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001
Copper	1 [AO]	<0.002	<0.002	0.004	<0.002	0.0027	0.0016	<0.0002	0.0006
Iron	0.3 [AO]	21.8	18.2	10.3	9.60	17.0	15.8	16.7	16.2
Lead	0.01 (MAC)c	0.00006	<0.00004	<0.00002	0.00010	0.00012	0.00006	<0.00004	<0.00004
Magnesium	-	34.9	36.3	37.1	33.3	34.2	33.3	33.2	33.3
Manganese	0.05 [AO]	0.697	0.665	0.638	0.595	0.822	0.659	0.606	0.616
Potassium	-	20.6	21.5	20.1	18.0	15.4	19.6	15.6	19.9
Sodium	200 [AO]	20.4	25.7	21.5	17.2	17.8	3.3	16.7	30.2
Zinc	5 [AO]	<0.005	<0.005	<0.005	<0.005	0.008	<0.005	<0.005	0.007

**NOTES:**

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
10. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5
		Jul-07	Dec-07	Jul-08	Dec-08	Jul-09	Dec-09	Mar-10	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13
Alkalinity(as CaCO3)	30 - 500 [OG]	250	288	237	243	248	242	281	263	263	247	295	244
Chloride	250 [AO]	6	4	4	4	3	3	4	2.8	2.8	2.7	2.6	2.7
Nitrate(as N)	10 (MAC) d	nd	nd	nd	nd	nd	nd	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
Nitrite(as N)	1 (MAC) d	nd	nd	nd	nd	nd	nd	<0.01	<0.1	<0.1	<0.1	<0.1	<0.1
Ammonia(as N)		0.14	nd	0.16	0.13	0.07	nd	<0.05	0.03	0.11	0.11	0.07	0.09
Total Kjeldahl Nitrogen(as N)		0.5	0.2	0.9	0.7	0.9	0.5	0.6	0.90	0.25	0.50	0.38	0.80
Organic Nitrogen	0.15	0.36	0	0.74	0.57	0.83	0.5	<0.55	0.87	0.14	0.39	0.31	0.71
Phenols		nd	nd	nd	nd	nd	nd	<0.001	0.003	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	1.9	0.8	1	0.7	0.8	1.1	0.8	0.8	1.2	1.3	2.3	12.6
Conductivity (us/cm)		498	556	493	504	513	509	560	520	537	497	518	501
pH		8.2	8.2	8.1	8	7.9	8.1	8.2	7.76	7.86	8.01	7.87	7.94
Sulphate (as SO4)	250 (AO)	25	11	28	28	29	28	29	26	19	25	8	23
Hardness(as CaCO3)	80-100 [OG]	270	290	240	250	270	260	250	254	302	258	284	257
Aluminum	0.1 [OG]	nd	nd	nd	nd	nd	nd	<0.005	0.02	0.03	0.02	0.03	0.03
Barium	1 [MAC]	0.077	0.081	0.071	0.072	0.086	0.078	0.066	0.076	0.092	0.084	0.088	0.084
Boron	5 [IMAC]	nd	0.019	0.014	0.011	0.022	0.018	0.012	0.016	-	0.019	0.010	0.016
Cadmium	0.005 (MAC)	nd	0.0011	nd	0.0003	nd	0.0002	0.0001	<0.00002	<0.00002	<0.00002	0.00004	<0.00002
Calcium	-	64	68	54	58	61	60	56	55.0	70.7	58.8	66.3	59.3
Chromium	0.05 (MAC)	nd	nd	nd	nd	nd	nd	<0.005	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	nd	0.002	nd	0.001	nd	0.001	0.004	<0.002	<0.002	<0.002	<0.002	<0.002
Iron	0.3 [AO]	0.13	nd	0.13	nd	nd	nd	<0.1	0.013	0.037	0.047	0.160	0.317
Lead	0.01 (MAC)c	nd	nd	nd	nd	nd	nd	<0.0005	0.00009	0.00004	<0.00002	0.00003	<0.00002
Magnesium	-	28	29	27	26	28	27	27	28.3	30.6	27.0	28.8	26.4
Manganese	0.05 [AO]	0.28	0.006	0.22	0.38	0.56	0.003	0.200	0.215	0.276	0.222	0.196	0.347
Potassium	-	0.87	0.92	2.3	0.93	0.84	0.83	1.1	0.8	1.0	0.8	0.8	0.7
Sodium	200 [AO]	3.4	3.4	6.4	3.3	5.2	3.3	31	15.6	3.7	3.5	3.2	3.3
Zinc	5 [AO]	0.006	nd	0.01	0.068	nd	0.019	0.110	0.261	0.140	0.031	0.016	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
10. Shaded values indicate exceedance of ODWQS.



**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5
		Nov-13	Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19
Alkalinity(as CaCO3)	30 - 500 [OG]	250	236	243	240	265	257	273	239	253	240	235	226
Chloride	250 [AO]	2.4	2.3	2.8	2.60	3.19	2.3	2.0	3.7	2.7	2.3	1.9	2.0
Nitrate(as N)	10 (MAC) d	0.1	<0.1	0.1	<0.05	<0.10	<0.1	0.1	<0.05	<0.1	0.06	<0.05	0.09
Nitrite(as N)	1 (MAC) d	<0.1	<0.1	<0.1	<0.05	<0.10	<0.1	<0.1	<0.05	0.2	<0.05	<0.05	<0.05
Ammonia(as N)		0.07	0.08	0.06	<0.02	0.07	0.07	0.07	0.10	0.08	0.17	0.17	0.23
Total Kjeldahl Nitrogen(as N)		0.22	0.20	0.14	<0.10	0.23	0.12	0.23	0.11	0.3	0.2	0.2	0.2
Organic Nitrogen	0.15	0.15	0.12	0.08	<0.10	0.16	0.05	0.16	0.01	0.22	0.03	0.03	<0.05
Phenols		<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.002	<0.002
Dissolved Organic Carbon(DOC)	5 [AO]	3	2.7	2.3	1.1	0.8	2.5	1.0	1.2	2.4	1.4	2.1	2.3
Conductivity (us/cm)		426	501	470	497	502	491	519	498	490	476	512	489
pH		8.01	7.96	7.90	8.44	7.84	7.95	7.91	7.95	7.98	8.05	7.88	7.90
Sulphate (as SO4)	250 (AO)	23	24	24	24.2	21.9	23	12	19	14	24	17	22
Hardness(as CaCO3)	80-100 [OG]	240	277	260	243	257	262	303	277	269	249	267	272
Aluminum	0.1 [OG]	0.04	0.11	0.02	0.005	0.004	0.03	0.03	0.02	0.04	0.05	0.05	0.04
Barium	1 [MAC]	0.079	0.087	0.082	0.074	0.087	0.087	0.100	0.099	0.098	0.085	0.097	0.080
Boron	5 [IMAC]	0.014	0.016	0.020	0.014	0.018	0.015	0.012	0.008	0.021	0.015	0.015	0.013
Cadmium	0.005 (MAC)	<0.00002	<0.00002	<0.00002	<0.001	<0.001	0.00003	0.00003	0.000028	<0.000014	0.000037	0.000134	<0.000015
Calcium	-	55.4	65.7	60.6	56.4	61.2	60.7	71.9	64.0	62.3	55.7	63.6	62.9
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.003	<0.003	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	<0.0001	<0.002	0.0002	<0.003	<0.003	<0.002	<0.0001	<0.002	<0.002	<0.002	<0.002	<0.002
Iron	0.3 [AO]	0.068	0.214	0.128	0.267	0.140	0.177	0.163	0.139	0.131	0.094	0.074	0.236
Lead	0.01 (MAC)c	<0.00002	<0.00002	<0.00002	<0.002	<0.002	<0.00002	<0.00002	<0.00002	<0.00002	0.00003	<0.00002	0.00010
Magnesium	-	24.6	27.4	26.4	24.7	25.3	26.8	30.0	28.5	27.6	26.8	26.3	28.0
Manganese	0.05 [AO]	0.211	0.328	0.200	0.255	0.245	0.267	0.233	0.379	0.267	0.213	0.076	0.236
Potassium	-	0.7	0.8	0.9	0.71	0.90	0.7	0.9	0.7	0.8	0.6	0.7	0.7
Sodium	200 [AO]	2.9	3.5	3.2	2.96	3.20	3.5	4.0	3.8	3.4	3.6	3.5	3.6
Zinc	5 [AO]	0.015	0.006	0.012	0.005	0.008	<0.005	0.010	0.007	<0.005	<0.005	0.007	<0.005

**NOTES:**

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
10. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5	OW5
		Nov-19	Jul-20	Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	238	238	225	231	293	236	298	257	262
Chloride	250 [AO]	2.0	2.4	2.5	2.3	1.6	1.8	1.7	2.2	2.7
Nitrate(as N)	10 (MAC) d	0.11	0.06	<0.05	<0.05	0.10	<0.05	0.11	<0.05	0.11
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		0.15	0.1	0.1	0.14	0.16	0.18	0.06	0.16	0.15
Total Kjeldahl Nitrogen(as N)		0.1	0.2	0.2	0.1	0.2	0.3	0.4	0.3	0.3
Organic Nitrogen	0.15	<0.05	0.10	0.10	<0.1	0.04	0.12	0.34	0.14	0.15
Phenols		<0.002	<0.002	<0.002	0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	2.7	1.9	1.1	2.2	2.2	2.3	2.9	1.9	3.2
Conductivity (us/cm)		512	483	486	482	545	494	558	503	516
pH		7.95	7.96	8.08	8.05	8.26	7.82	7.86	7.86	7.55
Sulphate (as SO4)	250 (AO)	14	22	18	21	16	20	15	20	18
Hardness(as CaCO3)	80-100 [OG]	263	252	275	277	261	257	200	252	250
Aluminum	0.1 [OG]	0.05	0.02	0.03	0.04	0.03	0.01	0.03	<0.01	0.02
Barium	1 [MAC]	0.091	0.094	0.098	0.093	0.086	0.091	0.088	0.080	0.092
Boron	5 [IMAC]	0.019	0.015	<0.005	0.015	0.025	0.009	0.02	0.014	0.017
Cadmium	0.005 (MAC)	0.000042	<0.000015	0.000022	0.000016	0.000021	<0.000015	0.000038	0.000025	<0.000015
Calcium	-	61.6	57.1	62.3	63.9	58.4	59.0	59.9	56.4	57.6
Chromium	0.05 (MAC)	<0.001	<0.002	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001
Copper	1 [AO]	0.0023	<0.002	<0.002	0.005	<0.002	0.0003	0.0010	0.0004	0.0009
Iron	0.3 [AO]	0.025	0.11	0.024	0.047	<0.005	0.115	<0.005	<0.005	0.053
Lead	0.01 (MAC)c	0.00004	0.00003	0.00003	0.00006	0.00007	<0.00002	0.00012	<0.00002	<0.00002
Magnesium	-	26.6	26.7	29.1	28.5	27.9	26.7	26.2	26.9	25.9
Manganese	0.05 [AO]	0.080	0.173	0.024	0.053	0.042	0.255	0.020	0.047	0.140
Potassium	-	0.8	0.8	1	0.7	1.1	0.8	0.9	0.8	0.8
Sodium	200 [AO]	3.4	3.5	3.5	3.6	26.2	4.3	21.9	5.3	3.7
Zinc	5 [AO]	0.009	<0.005	0.01	<0.005	0.021	<0.005	0.071	0.016	0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
10. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6
		Jul-07	Dec-07	Jul-08	Dec-08	Jul-09	Dec-09	Mar-10	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13
Alkalinity(as CaCO3)	30 - 500 [OG]	254	246	251	255	245	257	259	278	265	270	271	274
Chloride	250 [AO]	8	9	5	5	4	3	6	3.1	3.3	3.3	4.1	3.7
Nitrate(as N)	10 (MAC) d	nd	nd	nd	nd	nd	nd	<0.1	<0.1	<0.1	0.1	<0.1	0.1
Nitrite(as N)	1 (MAC) d	nd	nd	nd	nd	nd	nd	<0.01	<0.1	<0.1	<0.1	<0.1	<0.1
Ammonia(as N)		0.24	0.16	0.38	0.19	0.27	0.3	0.22	0.11	0.29	0.28	0.25	0.30
Total Kjeldahl Nitrogen(as N)		0.4	0.4	5	1.3	4	7	7	1.17	2.06	0.61	5.17	5.61
Organic Nitrogen	0.15	0.16	0.24	4.62	1.11	3.73	6.7	6.78	1.06	1.77	0.33	4.92	5.31
Phenols		nd	nd	nd	nd	nd	nd	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	1.4	0.8	1.8	0.6	0.8	1	0.8	1.1	1.5	0.9	1.6	3.0
Conductivity (us/cm)		507	534	518	508	496	512	513	528	543	522	509	535
pH		8.1	8.1	8	8.1	7.8	7.9	7.9	7.58	7.79	8.06	7.80	7.91
Sulphate (as SO4)	250 (AO)	21	26	24	20	20	20	17	14	16	13	17	13
Hardness(as CaCO3)	80-100 [OG]	270	230	240	250	230	240	240	267	285	257	263	249
Aluminum	0.1 [OG]	0.01	nd	nd	nd	nd	nd	<0.005	0.03	0.04	0.02	0.04	0.03
Barium	1 [MAC]	0.086	0.072	0.079	0.067	0.066	0.062	0.060	0.074	0.081	0.073	0.084	0.077
Boron	5 [IMAC]	0.028	0.027	0.026	0.026	0.027	0.024	0.019	0.023	-	0.027	0.016	0.022
Cadmium	0.005 (MAC)	nd	nd	0.0001	nd	nd	nd	<0.0001	<0.00002	<0.00002	<0.00002	<0.00002	0.00002
Calcium	-	68	57	58	61	58	59	58	67.4	72.8	64.5	67.8	62.6
Chromium	0.05 (MAC)	nd	nd	nd	nd	nd	nd	<0.005	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	nd	nd	nd	0.001	nd	0.001	<0.001	<0.002	<0.002	<0.002	<0.002	<0.002
Iron	0.3 [AO]	0.24	0.63	0.59	0.24	0.95	nd	0.540	0.975	0.567	0.733	0.150	0.909
Lead	0.01 (MAC)c	nd	0.0026	nd	nd	0.0017	nd	0.0005	<0.00002	<0.00002	<0.00002	0.00002	<0.00002
Magnesium	-	25	22	22	23	21	22	23	23.9	25.1	23.2	22.7	22.5
Manganese	0.05 [AO]	0.057	0.073	0.061	0.047	0.041	0.016	0.045	0.093	0.098	0.091	0.094	0.089
Potassium	-	1.1	0.83	2.6	1	0.8	0.82	0.7	0.8	1.1	0.9	0.9	0.8
Sodium	200 [AO]	14	12	14	11	11	10	9.1	8.3	9.8	8.3	8.7	9.2
Zinc	5 [AO]	nd	nd	0.006	nd	nd	nd	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6
		Nov-13	Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19
Alkalinity(as CaCO3)	30 - 500 [OG]	265	271	291	308	306	287	284	259	298	293	279	277
Chloride	250 [AO]	3.2	3.1	2.9	2.79	3.67	3.5	3.1	4.9	2.8	2.7	2.2	2.4
Nitrate(as N)	10 (MAC) d	<0.1	<0.1	<0.1	<0.10	<0.10	<0.1	<0.1	<0.05	<0.1	<0.05	<0.05	0.08
Nitrite(as N)	1 (MAC) d	<0.1	<0.1	<0.1	<0.10	<0.10	<0.1	<0.1	<0.05	0.2	<0.05	<0.05	<0.05
Ammonia(as N)		0.21	0.33	0.23	0.21	0.26	0.18	0.17	0.08	0.24	0.31	0.36	0.40
Total Kjeldahl Nitrogen(as N)		21.8	2.58	1.32	0.43	0.51	0.23	0.36	0.31	0.5	0.8	1.7	2.4
Organic Nitrogen	0.15	21.59	2.25	1.09	0.22	0.25	0.05	0.19	0.23	0.26	0.49	1.34	2.0
Phenols		<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.015	<0.002
Dissolved Organic Carbon(DOC)	5 [AO]	3.4	2.9	3.2	1.9	1.1	1.2	0.7	1.3	3.0	1.9	2.9	4.8
Conductivity (us/cm)		436	547	531	585	571	528	551	527	563	545	578	556
pH		8.03	7.93	7.82	8.40	8.05	7.93	7.89	7.89	7.79	7.94	7.55	8.09
Sulphate (as SO4)	250 (AO)	14	11	10	7.03	15.0	15	13	14	8	9	10	9
Hardness(as CaCO3)	80-100 [OG]	227	280	283	285	280	266	303	269	284	282	322	286
Aluminum	0.1 [OG]	0.04	0.05	0.02	0.005	<0.004	0.02	0.03	0.02	0.05	0.05	0.18	0.05
Barium	1 [MAC]	0.075	0.076	0.070	0.063	0.079	0.072	0.081	0.069	0.077	0.068	0.078	0.062
Boron	5 [IMAC]	0.019	0.022	0.022	0.015	0.020	0.020	0.020	0.016	0.025	0.020	0.018	0.018
Cadmium	0.005 (MAC)	<0.00002	<0.00002	<0.00002	<0.001	<0.001	<0.00002	<0.00002	<0.000014	<0.000014	<0.000015	<0.000015	<0.000015
Calcium	-	57	72.0	72.5	74.8	73.4	68.0	78.6	67.6	72.1	70.5	84.9	73.6
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.003	<0.003	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	0.0001	<0.002	<0.0001	<0.003	<0.003	<0.002	<0.0001	<0.002	<0.002	<0.002	<0.002	0.005
Iron	0.3 [AO]	0.256	0.953	1.10	1.38	0.403	0.436	0.742	1.02	0.899	1.30	1.36	1.16
Lead	0.01 (MAC)c	<0.00002	<0.00002	<0.00002	<0.002	<0.002	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002	0.00023	0.00005
Magnesium	-	20.6	24.4	24.7	23.9	23.6	23.5	26.0	24.3	25.2	25.8	26.7	24.9
Manganese	0.05 [AO]	0.085	0.114	0.125	0.231	0.135	0.101	0.110	0.087	0.119	0.138	0.134	0.113
Potassium	-	0.8	1.0	0.9	0.71	0.93	0.7	0.9	0.7	0.9	0.7	0.8	0.7
Sodium	200 [AO]	8	8.9	6.6	5.32	6.45	8.6	9.8	10.5	8.2	8.2	7.2	7.7
Zinc	5 [AO]	<0.005	<0.005	<0.005	0.007	0.008	<0.005	0.027	0.027	0.023	0.031	0.079	0.056

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6	OW6
		Nov-19	Jul-20	Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	258	265	241	259	292	286	294	285	295
Chloride	250 [AO]	3.1	4.5	4.6	4.4	3.0	3.1	2.3	3.3	3.4
Nitrate(as N)	10 (MAC) d	0.13	0.11	<0.05	0.08	<0.05	<0.05	0.13	0.05	<0.05
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		0.35	0.33	0.26	0.33	0.38	0.38	0.33	0.30	0.44
Total Kjeldahl Nitrogen(as N)		0.5	0.4	0.3	1.4	3.8	3.5	1.0	0.7	1.2
Organic Nitrogen	0.15	0.15	0.07	0.04	1.07	3.42	3.12	0.67	0.4	0.76
Phenols		<0.002	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	4.2	2.3	1.7	2.2	2.3	3.1	0.8	1.0	2.8
Conductivity (us/cm)		544	526	523	525	548	577	551	539	569
pH		7.87	7.83	7.89	7.97	7.91	7.76	7.84	7.99	7.55
Sulphate (as SO4)	250 (AO)	13	17	18	17	12	11	11	13	11
Hardness(as CaCO3)	80-100 [OG]	274	269	274	287	309	285	282	294	266
Aluminum	0.1 [OG]	0.06	0.02	0.12	0.07	0.15	0.02	0.06	0.20	0.04
Barium	1 [MAC]	0.061	0.081	0.078	0.077	0.078	0.071	0.080	0.066	0.075
Boron	5 [IMAC]	0.018	0.026	<0.005	0.024	0.025	0.014	0.025	0.024	0.029
Cadmium	0.005 (MAC)	<0.000015	<0.000015	<0.000015	0.000037	0.000024	<0.000015	<0.000015	0.000017	0.000016
Calcium	-	71.0	67	67.1	72.5	78.9	72.5	71.2	72.4	67.9
Chromium	0.05 (MAC)	<0.001	<0.002	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001
Copper	1 [AO]	0.0003	<0.002	<0.002	0.012	<0.002	<0.0001	0.0006	0.0031	0.0002
Iron	0.3 [AO]	0.983	0.777	0.463	1.06	1.25	1.02	0.416	1.15	1.01
Lead	0.01 (MAC)c	<0.00002	0.00016	0.00013	0.00011	0.00020	0.00003	0.00006	0.00042	<0.00002
Magnesium	-	23.4	24.6	25.9	25.8	27.1	25.4	25.2	27.5	23.5
Manganese	0.05 [AO]	0.111	0.072	0.039	0.065	0.111	0.113	0.086	0.082	0.062
Potassium	-	0.7	1	1	0.8	0.9	0.9	1.0	0.8	0.9
Sodium	200 [AO]	6.3	8.8	10.5	9.6	8.5	7.6	9.0	9.0	8.3
Zinc	5 [AO]	0.134	0.033	0.009	0.027	0.043	0.016	0.015	0.037	0.01

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7
		Jul-07	Jul-08	Dec-08	Jul-09	Dec-09	Mar-10	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13	Nov-13
Alkalinity(as CaCO3)	30 - 500 [OG]	269	248	278	242	349	284	252	Dry	273	Dry	269	288
Chloride	250 [AO]	4	2	2	4	nd	3	0.9		0.9		1.1	0.8
Nitrate(as N)	10 (MAC) d	IS	nd	nd	0.1	nd	<0.1	<0.1		<0.1		0.1	0.1
Nitrite(as N)	1 (MAC) d	IS	nd	nd	nd	nd	<0.01	<0.1		<0.1		<0.1	<0.1
Ammonia(as N)		IS	0.08	0.06	0.08	nd	<0.05	<0.01		0.03		<0.01	<0.01
Total Kjeldahl Nitrogen(as N)		IS	2.1	0.7	4	2	3	0.77		0.12		4.48	30.9
Organic Nitrogen	0.15	IS	2.02	0.64	3.92	2	<2.95	<0.77		0.09		4.48	30.9
Phenols		IS	nd	nd	nd	nd	<0.001	<0.001		<0.001		<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	IS	3.1	0.9	0.8	1.2	0.9	0.8		0.8		3.7	3.4
Conductivity (us/cm)		478	459	502	458	626	526	457		493		497	442
pH		8.2	8.1	7.9	7.8	7.9	7.9	7.62		8.06		7.86	7.86
Sulphate (as SO4)	250 (AO)	4	4	4	4	2	3	3		2		3	3
Hardness(as CaCO3)	80-100 [OG]	250	250	280	220	370	290	259		288		268	264
Aluminum	0.1 [OG]	IS	nd	nd	nd	nd	<0.005	0.02		0.03		0.03	0.03
Barium	1 [MAC]	IS	0.008	0.007	0.006	0.008	0.006	0.008		0.007		0.010	0.007
Boron	5 [IMAC]	IS	nd	nd	nd	nd	<0.01	0.006		0.011		0.006	<0.005
Cadmium	0.005 (MAC)	IS	nd	nd	0.0011	0.0003	0.0002	0.00005		0.00003		0.00008	<0.00002
Calcium	-	IS	69	76	61	100	79	71.1		79.6		74.1	73
Chromium	0.05 (MAC)	IS	nd	nd	nd	nd	<0.005	<0.002		<0.002		<0.002	<0.002
Copper	1 [AO]	IS	0.001	0.001	0.002	nd	0.001	<0.002		<0.002		<0.002	0.0002
Iron	0.3 [AO]	IS	nd	nd	nd	nd	<0.1	<0.005		0.019		0.009	0.01
Lead	0.01 (MAC)c	IS	nd	nd	nd	nd	<0.0005	<0.00002		<0.00002		<0.00002	<0.00002
Magnesium	-	IS	19	21	15	28	23	19.8		21.5		20.2	19.8
Manganese	0.05 [AO]	IS	0.012	0.007	0.032	0.027	0.240	0.104		0.043		0.119	0.179
Potassium	-	IS	2.2	0.67	0.61	0.54	0.62	0.5		0.7		0.7	0.4
Sodium	200 [AO]	IS	3.9	1.2	1.2	0.89	4.2	0.9		0.8		1.6	0.8
Zinc	5 [AO]	IS	0.006	nd	0.01	nd	0.006	<0.005		<0.005		0.039	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7
		Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19
Alkalinity(as CaCO3)	30 - 500 [OG]	262	312	259	Dry	288	Dry	283	376	270	362	291	304
Chloride	250 [AO]	1.0	1.4	1.40		1.1		2.9	1.8	1.0	0.7	0.8	0.5
Nitrate(as N)	10 (MAC) d	0.1	<0.1	<0.10		0.1		<0.05	<0.1	<0.05	<0.05	0.08	0.27
Nitrite(as N)	1 (MAC) d	<0.1	<0.1	<0.10		<0.1		<0.05	0.3	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		<0.01	<0.01	<0.02		<0.01		<0.01	<0.01	0.02	0.04	0.20	0.05
Total Kjeldahl Nitrogen(as N)		0.99	0.39	<0.10		<0.05		0.06	0.2	0.5	0.5	0.9	0.3
Organic Nitrogen	0.15	0.99	0.39	<0.10		<0.05		0.06	0.20	0.48	0.46	0.70	0.25
Phenols		<0.001	<0.001	<0.001		<0.001		<0.001	<0.001	<0.001	0.009	<0.002	<0.002
Dissolved Organic Carbon(DOC)	5 [AO]	2.8	4.5	1.2		1.7		1.6	3.5	1.4	2.6	3.8	3.5
Conductivity (us/cm)		504	549	478		497		524	663	489	704	524	606
pH		7.87	7.69	8.45		7.88		7.83	7.75	7.96	7.37	8.02	7.78
Sulphate (as SO4)	250 (AO)	2	1	2.17		3		3	2	2	2	2	2
Hardness(as CaCO3)	80-100 [OG]	299	324	248		286		311	396	281	398	310	389
Aluminum	0.1 [OG]	0.03	0.02	0.004		0.02		0.02	0.06	0.05	0.07	0.04	0.25
Barium	1 [MAC]	0.010	0.009	0.007		0.009		0.011	0.013	0.010	0.012	0.008	0.017
Boron	5 [IMAC]	<0.005	0.011	<0.010		0.006		<0.005	0.009	0.005	0.006	<0.005	0.007
Cadmium	0.005 (MAC)	<0.00002	<0.00002	<0.001		0.00002		0.000073	0.000015	<0.000015	0.000028	0.000016	0.000094
Calcium	-	83.3	89.2	68.5		78.0		85.1	110	74.6	111	83.5	105
Chromium	0.05 (MAC)	<0.002	<0.002	<0.003		<0.002		<0.002	<0.002	<0.002	<0.002	<0.002	<0.001
Copper	1 [AO]	<0.002	0.0003	<0.003		<0.002		<0.002	<0.002	<0.002	<0.002	<0.002	0.0024
Iron	0.3 [AO]	0.010	0.214	<0.010		0.006		<0.005	0.086	0.005	0.091	<0.005	0.287
Lead	0.01 (MAC)c	0.00003	<0.00002	<0.002		<0.00002		<0.00002	0.00003	<0.00002	<0.00002	0.00047	0.00063
Magnesium	-	22.1	24.6	18.8		22.1		23.9	29.4	22.9	29.3	24.7	30.7
Manganese	0.05 [AO]	0.239	0.333	0.111		0.081		0.017	0.206	0.004	0.203	0.022	0.048
Potassium	-	0.7	0.7	0.41		0.5		0.5	0.5	0.4	0.3	0.4	0.5
Sodium	200 [AO]	1.1	1.0	0.82		1.0		1.1	1.0	1.0	0.8	1.1	1.0
Zinc	5 [AO]	0.006	<0.005	<0.005		<0.005		0.006	<0.005	<0.005	<0.005	0.014	0.007

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW7	OW7	OW7	OW7	OW7	OW7	OW7	OW7
		Jul-20	Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	282	313	279	342	270	339	280	355
Chloride	250 [AO]	1.3	1.6	1.7	0.8	0.9	1.2	1.7	2.3
Nitrate(as N)	10 (MAC) d	0.11	0.07	0.08	<0.05	0.06	0.13	0.15	0.13
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		0.05	0.03	0.02	0.05	0.02	<0.01	<0.01	<0.05
Total Kjeldahl Nitrogen(as N)		0.3	0.2	0.7	1	0.7	0.9	0.6	0.4
Organic Nitrogen	0.15	0.25	0.17	0.68	0.95	0.68	0.9	0.6	0.4
Phenols		<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	2.4	1.9	2.6	5	2.5	0.9	1.0	3.4
Conductivity (us/cm)		517	608	528	601	534	602	496	648
pH		7.76	7.95	7.92	7.8	7.78	7.85	7.90	7.54
Sulphate (as SO4)	250 (AO)	2	3	2	1	2	3	2	2
Hardness(as CaCO3)	80-100 [OG]	293	367	319	342	295	356	156	333
Aluminum	0.1 [OG]	0.03	0.05	0.06	0.06	0.02	0.05	0.02	0.07
Barium	1 [MAC]	0.012	0.014	0.011	0.013	0.010	0.019	0.009	0.013
Boron	5 [IMAC]	0.006	<0.005	0.005	0.007	<0.005	0.005	<0.005	0.008
Cadmium	0.005 (MAC)	0.000017	0.000355	0.000022	0.000038	0.000030	0.000031	<0.000015	<0.000015
Calcium	-	78.8	100	87	94.3	79.3	97.0	72.7	91.1
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001
Copper	1 [AO]	<0.002	0.002	0.011	<0.002	0.0010	0.0027	0.0071	0.001
Iron	0.3 [AO]	0.018	<0.005	0.016	0.022	<0.005	0.031	<0.005	0.255
Lead	0.01 (MAC)c	0.00003	0.0003	0.00010	0.00003	0.00003	0.00010	0.00002	0.00011
Magnesium	-	23.4	28.3	24.6	25.8	23.6	27.5	21.5	25.5
Manganese	0.05 [AO]	0.184	0.001	0.059	0.047	0.021	0.007	<0.001	0.155
Potassium	-	0.5	0.4	0.5	0.5	0.6	0.6	0.5	0.5
Sodium	200 [AO]	0.9	0.8	1.0	5.3	1.3	1.2	2.7	11.8
Zinc	5 [AO]	<0.005	0.005	<0.005	0.103	0.010	0.012	<0.005	0.021

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.



**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW11-16	OW11-16	OW11-16	OW11-16	OW11-16	OW11-16	OW11-16	OW11-16	OW11-16	OW11-16	OW11-16	OW11-16
		Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19	Jul-20	Nov-20	Jun-21	Nov-21	Jun-22
Alkalinity(as CaCO3)	30 - 500 [OG]	340	323	329	342	313	309	302	326	291	317	339	324
Chloride	250 [AO]	5.2	3.6	7.2	1.8	5.4	1.6	8.6	4.4	4.8	2.3	1.5	1.4
Nitrate(as N)	10 (MAC) d	2.4	0.97	2.3	0.87	2.53	0.87	4.79	1.49	2.82	0.80	1.04	0.75
Nitrite(as N)	1 (MAC) d	<0.1	<0.05	0.2	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		<0.01	<0.01	<0.01	0.08	0.03	0.16	0.06	0.04	0.01	0.02	0.01	<0.01
Total Kjeldahl Nitrogen(as N)		0.17	0.12	0.2	0.6	0.2	0.2	0.1	0.1	0.1	0.1	0.1	0.2
Organic Nitrogen	0.15	0.17	0.12	0.20	0.52	0.17	0.04	0.04	0.06	0.09	0.08	0.09	0.2
Phenols		<0.001	<0.001	<0.001	<0.001	0.016	<0.002	<0.002	<0.002	<0.002	<0.002	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	0.4	1.0	2.5	1.0	1.4	3.5	1.9	2.8	1.1	2.6	1.9	2.3
Conductivity (us/cm)		659	609	613	577	655	597	674	621	607	610	610	632
pH		7.88	7.91	7.96	7.97	7.65	8.07	7.85	7.83	7.75	7.99	7.96	7.88
Sulphate (as SO4)	250 (AO)	14	5	6	3	10	3	8	7	4	5	5	3
Hardness(as CaCO3)	80-100 [OG]	396	362	349	327	354	368	356	360	357	380	376	362
Aluminum	0.1 [OG]	0.04	0.03	0.05	0.05	0.05	0.05	0.05	0.04	0.04	0.07	0.07	0.07
Barium	1 [MAC]	0.032	0.026	0.027	0.023	0.028	0.023	0.027	0.034	0.029	0.029	0.029	0.027
Boron	5 [IMAC]	0.039	<0.005	0.022	0.007	0.024	<0.005	0.024	0.008	<0.005	0.010	0.023	<0.005
Cadmium	0.005 (MAC)	<0.00002	<0.000014	<0.000014	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015
Calcium	-	110	97.0	95.0	85.4	96.2	98.0	95.8	94.9	94.5	102	101	96.4
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.001	<0.002	<0.002	<0.002	<0.002	<0.001
Copper	1 [AO]	0.0002	<0.002	<0.002	<0.002	<0.002	0.002	0.0005	<0.002	0.002	<0.002	<0.002	0.0010
Iron	0.3 [AO]	<0.005	<0.005	<0.005	0.032	<0.005	<0.005	0.005	0.01	0.011	<0.005	0.063	0.054
Lead	0.01 (MAC)c	<0.00002	<0.00002	<0.00002	0.00004	<0.00002	0.00004	<0.00002	0.00011	0.00003	<0.00002	0.00011	0.00010
Magnesium	-	29.7	29.0	27.2	27.6	27.7	30.0	28.3	29.9	29.4	30.3	30.0	29.4
Manganese	0.05 [AO]	0.003	<0.001	<0.001	0.004	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.009	0.006
Potassium	-	0.5	0.4	0.4	0.3	0.4	0.4	0.5	0.5	0.5	0.5	0.5	0.5
Sodium	200 [AO]	6.5	2.1	2.6	1.7	4.1	2.0	3.6	2.4	3.2	2.6	3.2	1.7
Zinc	5 [AO]	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW11-16		
		Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	327	357	338
Chloride	250 [AO]	2.1	2.3	2.5
Nitrate(as N)	10 (MAC) d	2.47	2.05	1.66
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05
Ammonia(as N)		<0.01	<0.01	<0.05
Total Kjeldahl Nitrogen(as N)		0.2	0.1	0.2
Organic Nitrogen	0.15	0.2	0.1	0.2
Phenols		<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	0.5	1.0	4
Conductivity (us/cm)		612	646	627
pH		7.87	7.92	7.81
Sulphate (as SO4)	250 (AO)	4	5	4
Hardness(as CaCO3)	80-100 [OG]	354	355	325
Aluminum	0.1 [OG]	0.05	0.02	0.05
Barium	1 [MAC]	0.027	0.025	0.025
Boron	5 [MAC]	0.019	0.005	0.024
Cadmium	0.005 (MAC)	<0.000015	<0.000015	<0.000015
Calcium	-	93.8	93.3	87.1
Chromium	0.05 (MAC)	0.001	<0.001	<0.001
Copper	1 [AO]	0.0012	0.0008	0.0006
Iron	0.3 [AO]	0.036	<0.005	0.006
Lead	0.01 (MAC)c	0.00008	<0.00002	<0.00002
Magnesium	-	29.1	29.6	26
Manganese	0.05 [AO]	0.004	<0.001	<0.001
Potassium	-	0.5	0.5	0.5
Sodium	200 [AO]	2.3	1.8	2.8
Zinc	5 [AO]	<0.005	<0.005	<0.005

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12
		Jul-07	Dec-07	Jul-08	Dec-08	Jul-09	Dec-09	Mar-10	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13
Alkalinity(as CaCO3)	30 - 500 [OG]	381	359	359	383	365	372	369	384	366	360	365	359
Chloride	250 [AO]	21	17	19	17	17	9	11	4.7	6.2	7.1	6.1	4.9
Nitrate(as N)	10 (MAC) d	4.4	3.9	4.8	4.4	4.1	3.4	3.0	1.7	2.0	1.7	1.5	1.5
Nitrite(as N)	1 (MAC) d	nd	0.01	nd	nd	nd	nd	0.04	<0.1	<0.1	<0.1	<0.1	<0.1
Ammonia(as N)		0.19	IS	0.11	nd	0.06	IS	0.09	<0.01	<0.01	0.03	<0.01	<0.01
Total Kjeldahl Nitrogen(as N)		0.7	IS	3	0.8	6	IS	4	0.79	1.00	0.49	0.16	1.21
Organic Nitrogen	0.15	0.51	IS	2.89	nd	5.94	IS	3.91	<0.79	<1.00	0.46	0.16	1.21
Phenols		nd	IS	nd	nd	nd	IS	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	6.1	IS	2	2	2.3	IS	2.2	1.4	1.9	2.1	1.8	4.5
Conductivity (us/cm)		942	977	1000	994	993	919	904	813	914	873	831	821
pH		8.2	8.1	8.1	8	7.8	7.9	7.9	7.58	7.84	8.04	7.82	7.94
Sulphate (as SO4)	250 (AO)	157	148	164	157	160	120	130	84	125	127	119	89
Hardness(as CaCO3)	80-100 [OG]	580	490	530	560	550	470	490	459	538	487	478	426
Aluminum	0.1 [OG]	nd	nd	nd	nd	nd	IS	<0.005	0.03	0.04	0.02	0.04	0.03
Barium	1 [MAC]	0.081	0.073	0.081	0.086	0.085	IS	0.075	0.069	0.083	0.081	0.074	0.078
Boron	5 [IMAC]	0.52	0.48	0.45	0.46	0.53	IS	0.44	0.424	-	0.549	0.485	0.328
Cadmium	0.005 (MAC)	0.0006	0.0003	nd	0.0002	0.0002	IS	0.0001	<0.00002	<0.00002	0.00003	<0.00002	<0.00002
Calcium	-	98	88	89	92	95	IS	80	88.8	89.9	83.9	82.8	78.6
Chromium	0.05 (MAC)	nd	nd	nd	nd	nd	IS	<0.005	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	0.002	0.001	0.002	0.001	0.001	IS	<0.001	<0.002	<0.002	<0.002	<0.002	<0.002
Iron	0.3 [AO]	nd	nd	nd	nd	nd	IS	<0.01	<0.005	<0.005	<0.005	<0.005	<0.005
Lead	0.01 (MAC)c	nd	nd	nd	nd	nd	IS	<0.0005	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002
Magnesium	-	82	65	74	81	76	IS	70	57.8	76.3	67.4	65.8	55.8
Manganese	0.05 [AO]	0.003	0.077	0.002	nd	nd	IS	0.037	<0.001	<0.001	<0.001	<0.001	<0.001
Potassium	-	12	9.6	14	15	14	IS	12	10.6	15.9	12.2	11.1	12.0
Sodium	200 [AO]	9.7	8	12	11	11	IS	9.2	8.1	10.5	9.4	9.1	6.2
Zinc	5 [AO]	nd	nd	0.006	nd	nd	IS	<0.005	<0.005	0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12
		Nov-13	Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19
Alkalinity(as CaCO3)	30 - 500 [OG]	357	327	337	334	343	368	368	339	317	339	312	319
Chloride	250 [AO]	5.7	3.7	6.0	6.90	7.50	4.1	4.1	5.2	4.4	3.7	3.8	3.4
Nitrate(as N)	10 (MAC) d	1.5	1.1	2.0	2.37	1.98	1.2	1.3	1.26	2.0	1.68	1.63	1.66
Nitrite(as N)	1 (MAC) d	<0.1	<0.1	<0.1	<0.05	<0.25	<0.1	<0.1	<0.05	0.2	<0.05	<0.05	<0.05
Ammonia(as N)		<0.01	<0.01	<0.01	<0.02	<0.02	<0.01	<0.01	<0.01	<0.01	0.06	0.02	0.06
Total Kjeldahl Nitrogen(as N)		0.95	0.65	0.21	0.22	0.18	0.05	0.28	0.32	0.3	0.5	0.2	0.3
Organic Nitrogen	0.15	0.95	0.65	0.21	0.22	0.18	0.05	0.28	0.32	0.30	0.44	0.18	0.24
Phenols		<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.003	0.056
Dissolved Organic Carbon(DOC)	5 [AO]	5.4	3.3	3.9	2.0	1.8	2.1	1.6	1.9	4.0	2.0	3.2	5.6
Conductivity (us/cm)		709	726	770	827	772	745	782	778	776	709	762	732
pH		7.96	7.94	7.83	8.40	8.07	7.96	7.98	7.98	8.02	7.99	7.78	8.14
Sulphate (as SO4)	250 (AO)	109	52	93	99.5	96.8	75	90	69	71	59	75	63
Hardness(as CaCO3)	80-100 [OG]	405	378	428	407	397	410	458	443	434	396	410	427
Aluminum	0.1 [OG]	0.03	0.02	0.02	0.004	<0.004	0.02	0.03	0.02	0.05	0.05	0.06	0.05
Barium	1 [MAC]	0.067	0.044	0.069	0.066	0.068	0.068	0.076	0.070	0.073	0.065	0.069	0.060
Boron	5 [IMAC]	0.439	0.317	0.501	0.505	0.374	0.380	0.493	0.460	0.464	0.341	0.433	0.409
Cadmium	0.005 (MAC)	<0.00002	<0.00002	<0.00002	<0.001	<0.001	<0.00002	<0.00002	<0.000014	<0.000014	<0.000015	<0.000015	<0.000015
Calcium	-	71	70.9	74.4	70.5	70.9	75.4	82.2	77.5	74.9	76.7	73.1	79.1
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.003	<0.003	<0.002	<0.002	<0.002	0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	0.0008	<0.002	0.0015	<0.003	<0.003	<0.002	0.0007	<0.002	<0.002	<0.002	<0.002	<0.002
Iron	0.3 [AO]	<0.005	<0.005	<0.005	<0.010	<0.010	<0.005	<0.005	<0.005	0.005	<0.005	0.046	<0.005
Lead	0.01 (MAC)c	<0.00002	<0.00002	0.00002	<0.002	<0.002	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002	0.00004	0.00017
Magnesium	-	55.3	48.7	58.9	56.1	53.5	53.9	61.4	60.6	60.0	49.7	55.2	55.9
Manganese	0.05 [AO]	<0.001	<0.001	<0.001	<0.002	<0.002	0.001	<0.001	<0.001	<0.001	<0.001	0.003	<0.001
Potassium	-	9.4	11.1	12.2	13.6	12.3	10.2	12.3	10.9	12.4	9.4	12.1	10.2
Sodium	200 [AO]	7.7	5.8	7.5	7.66	7.08	6.6	8.3	7.9	7.2	6.3	6.9	6.3
Zinc	5 [AO]	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12	OW12
		Nov-19	Jul-20	Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	316	326	302	317	338	327	332	346	339
Chloride	250 [AO]	3.6	4.4	3.6	3.2	3.3	2.8	2.8	3.4	3.8
Nitrate(as N)	10 (MAC) d	1.38	0.87	0.63	0.73	0.56	0.51	0.44	0.47	0.42
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		0.05	0.1	0.03	0.02	0.02	<0.01	<0.01	<0.01	0.09
Total Kjeldahl Nitrogen(as N)		0.2	0.2	0.2	0.6	0.6	0.2	0.6	0.2	0.2
Organic Nitrogen	0.15	0.15	0.10	0.17	0.58	0.58	0.2	0.6	0.2	0.11
Phenols		<0.002	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	3.8	3.0	4.6	3.7	2.4	3.0	1.3	2.5	4.6
Conductivity (us/cm)		736	739	700	712	718	728	698	707	722
pH		8.01	7.89	7.95	8.11	8.08	8.00	8.09	7.98	7.81
Sulphate (as SO4)	250 (AO)	65	76	64	64	69	60	60	59	61
Hardness(as CaCO3)	80-100 [OG]	398	415	423	435	419	400	423	376	378
Aluminum	0.1 [OG]	0.06	0.03	0.05	0.07	0.08	0.02	0.14	0.02	0.04
Barium	1 [MAC]	0.069	0.079	0.078	0.077	0.073	0.072	0.075	0.065	0.075
Boron	5 [IMAC]	0.390	0.458	0.426	0.439	0.43	0.391	0.437	0.394	0.438
Cadmium	0.005 (MAC)	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	0.000018
Calcium	-	76.0	71.1	71.9	79.2	75.9	71.7	76.8	65.9	67.8
Chromium	0.05 (MAC)	0.001	<0.002	<0.002	<0.002	<0.002	0.002	0.002	0.001	0.001
Copper	1 [AO]	0.0032	<0.002	0.002	<0.002	<0.002	0.0015	0.0018	0.0014	0.001
Iron	0.3 [AO]	<0.005	<0.005	0.061	0.042	0.068	0.006	0.245	0.007	<0.005
Lead	0.01 (MAC)c	0.00006	0.00004	0.00008	0.00004	0.0001	0.00003	0.00019	0.00003	0.00002
Magnesium	-	50.6	57.8	59.2	57.6	55.7	53.7	56.3	51.5	50.8
Manganese	0.05 [AO]	<0.001	<0.001	0.002	0.003	0.005	<0.001	0.016	<0.001	<0.001
Potassium	-	10.3	11.4	11.4	10.7	10.4	9.9	10.6	9.5	10.5
Sodium	200 [AO]	5.9	6.5	6.4	6.5	6.5	5.5	5.9	5.6	5.9
Zinc	5 [AO]	<0.005	<0.005	0.009	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S
		Jul-07	Dec-07	Jul-08	Dec-08	Jul-09	Dec-09	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13	Nov-13
Alkalinity(as CaCO3)	30 - 500 [OG]	381	385	376	371	378	391	417	512	424	495	387	448
Chloride	250 [AO]	74	80	63	54	39	32	19.9	27.1	19.6	21.7	11.7	7.7
Nitrate(as N)	10 (MAC) d	5.5	6.7	6.3	7.9	5.8	10	3.0	2.4	3.8	3.4	2.6	3.7
Nitrite(as N)	1 (MAC) d	0.02	0.04	nd	nd	0.02	nd	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
Ammonia(as N)		0.16	0.1	0.11	0.1	0.21	0.62	<0.01	2.56	0.63	3.55	0.44	2.03
Total Kjeldahl Nitrogen(as N)		0.6	0.6	3	5	6	4	1.51	4.58	0.90	7.37	2.54	4.59
Organic Nitrogen	0.15	0.44	0.5	2.89	4.9	5.79	3.38	<1.51	2.02	0.27	3.82	2.10	2.56
Phenols		nd	nd	nd	nd	nd	nd	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	3.4	3.4	3.7	3.9	3.7	4.1	2.9	4.6	3.1	4.0	6.2	8.7
Conductivity (us/cm)		1680	2020	1840	1870	1620	1740	1300	1520	1390	1460	1210	1170
pH		8	7.9	7.9	7.8	7.6	7.7	7.44	7.55	7.64	7.64	7.77	7.72
Sulphate (as SO4)	250 (AO)	546	626	585	632	450	510	306	295	352	335	264	303
Hardness(as CaCO3)	80-100 [OG]	1100	1100	920	1000	860	850	712	847	722	889	609	621
Aluminum	0.1 [OG]	0.014	nd	nd	nd	nd	nd	0.04	0.05	0.04	0.05	0.04	0.06
Barium	1 [MAC]	0.086	81	0.079	0.078	0.068	0.055	0.055	0.073	0.069	0.063	0.049	0.053
Boron	5 [IMAC]	1.2	1.2	1.2	1.2	1.1	1.2	0.947	-	1.10	1.00	0.884	0.826
Cadmium	0.005 (MAC)	0.0013	0.0003	nd	0.0002	nd	nd	<0.00002	<0.00002	0.00015	0.00002	<0.00002	0.00004
Calcium	-	220	230	190	220	170	170	145	176	134	197	130	131
Chromium	0.05 (MAC)	nd	nd	nd	nd	nd	nd	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	0.002	0.002	0.003	0.002	0.001	0.002	<0.002	0.003	0.002	0.003	0.003	0.0038
Iron	0.3 [AO]	nd	nd	nd	nd	nd	nd	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
Lead	0.01 (MAC)c	nd	nd	nd	nd	nd	nd	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002
Magnesium	-	130	120	110	120	100	100	84.7	99.3	93.8	96.4	68.8	71.6
Manganese	0.05 [AO]	0.056	0.05	nd	nd	0.035	0.26	0.091	0.047	0.042	0.119	0.041	0.053
Potassium	-	30	37	32	36	33	33	32.4	39.9	34.2	36.1	26.4	26.7
Sodium	200 [AO]	53	48	46	48	39	37	23.2	33.4	23.8	26.8	17.4	19.7
Zinc	5 [AO]	nd	nd	nd	nd	nd	nd	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S
		Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19
Alkalinity(as CaCO3)	30 - 500 [OG]	421	385	400	484	472	518	409	432	444	426	385	463
Chloride	250 [AO]	4.9	13.1	<0.50	18.1	12.3	14.1	8.7	7.8	10.2	9.6	7.9	12.1
Nitrate(as N)	10 (MAC) d	2.9	4.1	3.25	2.34	1.6	1.7	2.01	2.4	1.18	1.83	1.73	1.43
Nitrite(as N)	1 (MAC) d	<0.1	<0.1	<0.25	<0.25	<0.1	<0.1	0.24	0.2	0.07	<0.05	0.33	0.25
Ammonia(as N)		1.00	1.64	0.52	1.07	1.26	6.16	0.78	3.15	2.56	5.56	1.82	7.49
Total Kjeldahl Nitrogen(as N)		1.73	2.09	0.84	2.50	1.70	6.82	1.74	3.9	2.9	5.6	2.2	7.9
Organic Nitrogen	0.15	0.73	0.45	0.32	1.43	0.44	0.66	0.96	0.75	0.34	0.04	0.38	0.41
Phenols		<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.017	<0.002	<0.002
Dissolved Organic Carbon(DOC)	5 [AO]	6.8	5.7	3.3	2.9	4.1	4.3	3.2	6.9	3.6	6.2	10.3	6.8
Conductivity (us/cm)		1290	1220	1230	1280	1140	1280	1100	1160	1030	1160	1010	1190
pH		7.73	7.62	8.25	7.97	7.68	7.63	7.75	7.73	7.73	7.3	7.98	7.61
Sulphate (as SO4)	250 (AO)	257	299	269	279	189	192	168	174	134	173	144	158
Hardness(as CaCO3)	80-100 [OG]	692	647	573	626	585	679	598	617	517	587	563	595
Aluminum	0.1 [OG]	0.04	0.03	0.011	0.005	0.04	0.04	0.04	0.06	0.07	0.07	0.07	0.07
Barium	1 [MAC]	0.054	0.049	0.047	0.061	0.050	0.068	0.050	0.058	0.049	0.062	0.048	0.074
Boron	5 [IMAC]	0.978	1.01	0.969	0.933	0.721	0.862	0.791	0.833	0.561	0.682	0.645	0.653
Cadmium	0.005 (MAC)	<0.00002	<0.00002	<0.001	<0.001	<0.00002	<0.00002	<0.000014	<0.000014	<0.000015	<0.000015	<0.000015	<0.000015
Calcium	-	148	136	121	137	127	151	131	134	111	134	127	135
Chromium	0.05 (MAC)	<0.002	<0.002	<0.003	<0.003	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.001
Copper	1 [AO]	<0.002	0.0021	0.004	<0.003	0.003	0.0026	<0.002	0.002	<0.002	0.002	0.010	0.0068
Iron	0.3 [AO]	<0.005	<0.005	<0.010	<0.010	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.010
Lead	0.01 (MAC)c	<0.00002	<0.00002	<0.002	<0.002	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002	0.00031	0.00008
Magnesium	-	78.3	74.6	65.8	69.0	65.1	73.6	65.7	68.6	58.3	61.4	59.7	62.7
Manganese	0.05 [AO]	0.065	0.049	0.036	0.055	0.050	0.061	0.067	0.088	0.066	0.094	0.070	0.114
Potassium	-	29.8	28.9	26.1	30.8	26.3	33.8	26.2	30.4	26.1	28.5	23.5	31.5
Sodium	200 [AO]	22.7	17.1	15.0	19.0	18.4	25.5	16.6	18.5	15.9	17.9	13.0	20.2
Zinc	5 [AO]	<0.005	<0.005	0.005	<0.005	<0.005	<0.005	0.017	<0.005	<0.005	<0.005	0.006	<0.005

**NOTES:**

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S	OW13 S
		Jul-20	Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	456	546	379	444	417	567	445	526
Chloride	250 [AO]	10.6	14.7	6.2	7.1	7.7	11.3	7.0	10.2
Nitrate(as N)	10 (MAC) d	0.99	<0.05	1.06	1.36	0.58	0.66	0.95	0.28
Nitrite(as N)	1 (MAC) d	0.12	<0.05	0.07	0.12	<0.05	<0.05	0.06	<0.05
Ammonia(as N)		2.84	8.02	2.42	3.84	2.89	6.69	2.86	6.54
Total Kjeldahl Nitrogen(as N)		3.2	9.7	2.8	4.7	3.2	5.1	4.3	8.1
Organic Nitrogen	0.15	0.36	1.68	0.38	0.86	0.31	<0.05	1.44	1.56
Phenols		<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	5.3	5.3	5.0	5.1	4.8	3.9	4.4	8.7
Conductivity (us/cm)		1060	1240	951	1010	975	1150	937	1110
pH		7.53	7.22	7.78	7.69	7.60	7.67	7.77	7.58
Sulphate (as SO4)	250 (AO)	125	95	128	121	83	86	90	76
Hardness(as CaCO3)	80-100 [OG]	560	647	553	549	487	551	463	508
Aluminum	0.1 [OG]	0.06	0.07	0.08	0.08	0.04	0.08	0.03	0.08
Barium	1 [MAC]	0.067	0.096	0.062	0.069	0.068	0.102	0.059	0.088
Boron	5 [IMAC]	0.630	0.61	0.596	0.589	0.471	0.549	0.449	0.515
Cadmium	0.005 (MAC)	0.000017	<0.000028	<0.000015	0.000023	0.000027	<0.000028	<0.000015	<0.000015
Calcium	-	124	143	127	127	111	125	106	119
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001
Copper	1 [AO]	<0.002	0.004	0.007	<0.002	0.0020	0.0035	0.0032	0.0025
Iron	0.3 [AO]	0.026	<0.005	<0.005	<0.005	0.009	0.048	<0.005	0.006
Lead	0.01 (MAC)c	0.00012	0.00004	0.00007	0.00003	0.00004	0.00010	0.00003	<0.00004
Magnesium	-	60.9	70.7	57.3	56.3	51.1	57.8	48.1	51.2
Manganese	0.05 [AO]	0.115	0.12	0.131	0.18	0.120	0.119	0.127	0.218
Potassium	-	25.2	32.3	23.8	26.2	21.5	28.3	19.4	25.1
Sodium	200 [AO]	14.6	24.8	11.6	14.4	11.6	17.9	10.1	16.1
Zinc	5 [AO]	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.



**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I
		Jul-07	Dec-07	Jul-08	Dec-08	Jul-09	Dec-09	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13	Nov-13
Alkalinity(as CaCO3)	30 - 500 [OG]	372	370	350	327	355	374	430	511	510	535	507	523
Chloride	250 [AO]	66	74	55	53	39	38	30.2	33.8	33.7	33.0	26.8	19.1
Nitrate(as N)	10 (MAC) d	3.8	5.1	4.5	5.1	5.4	6	2.5	1.5	1.8	1.6	1.3	0.7
Nitrite(as N)	1 (MAC) d	nd	nd	nd	nd	nd	nd	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
Ammonia(as N)		nd	nd	0.1	0.16	0.08	0.07	<0.01	0.11	0.88	1.33	1.16	1.08
Total Kjeldahl Nitrogen(as N)		0.4	0.4	1.4	3	5	5	0.62	1.00	1.30	2.55	3.40	2.86
Organic Nitrogen	0.15	nd	nd	1.3	2.84	4.92	4.93	<0.62	0.89	0.42	1.22	2.24	1.78
Phenols		nd	nd	nd	nd	nd	nd	<0.001	<0.001	<0.001	<0.001	<0.001	0.008
Dissolved Organic Carbon(DOC)	5 [AO]	2.9	2.8	3	3	2.7	4	2.9	3.8	3.9	4.6	9.2	10.9
Conductivity (us/cm)		1530	1830	1690	1610	890	1680	1440	1550	1520	1470	1470	1260
pH		8.1	7.9	7.9	8	7.7	7.7	7.39	7.55	7.70	7.49	7.69	7.75
Sulphate (as SO4)	250 (AO)	475	546	533	512	470	500	378	317	345	317	298	268
Hardness(as CaCO3)	80-100 [OG]	1000	990	840	770	890	910	791	909	809	884	737	714
Aluminum	0.1 [OG]	nd	nd	nd	nd	nd	0.006	0.04	0.06	0.04	0.05	0.05	0.05
Barium	1 [MAC]	0.078	0.09	0.059	0.057	0.065	0.072	0.061	0.072	0.075	0.069	0.063	0.064
Boron	5 [IMAC]	1.1	1.1	0.92	0.86	1.2	1.2	0.985	-	1.06	0.948	0.851	0.813
Cadmium	0.005 (MAC)	0.0004	0.0002	0.0007	0.0002	nd	0.0001	0.00004	<0.00002	<0.00002	<0.00002	0.00004	<0.00002
Calcium	-	220	220	180	160	180	180	162	188	154	193	160	152
Chromium	0.05 (MAC)	nd	nd	nd	nd	nd	nd	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	0.002	0.002	0.002	0.002	0.002	0.002	<0.002	<0.002	0.003	0.003	<0.002	0.0027
Iron	0.3 [AO]	nd	nd	nd	nd	nd	nd	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
Lead	0.01 (MAC)c	nd	nd	nd	nd	nd	nd	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002
Magnesium	-	120	110	98	90	110	110	93.2	107	97.5	103	82.3	81.5
Manganese	0.05 [AO]	nd	nd	nd	nd	0.004	nd	0.018	0.011	0.034	0.048	0.088	0.087
Potassium	-	26	26	25	25	30	28	24.8	31.8	27.0	28.6	22.6	21.5
Sodium	200 [AO]	52	48	44	37	40	40	30.9	39.7	37.7	34.2	33.8	33.4
Zinc	5 [AO]	nd	nd	0.007	0.008	nd	nd	0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I
		Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19
Alkalinity(as CaCO3)	30 - 500 [OG]	487	501	490	496	568	601	571	513	504	517	497	510
Chloride	250 [AO]	10.2	27.9	25.8	22.5	21.8	19.1	16.9	14.1	19.9	18.6	18.1	20.6
Nitrate(as N)	10 (MAC) d	1.2	1.3	1.69	1.64	0.7	0.4	0.62	0.6	0.19	0.30	0.42	0.31
Nitrite(as N)	1 (MAC) d	<0.1	<0.1	<0.25	<0.25	<0.1	<0.1	<0.05	<0.1	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		1.41	1.55	1.26	1.48	2.10	2.97	3.09	2.99	2.91	3.57	3.71	4.27
Total Kjeldahl Nitrogen(as N)		2.20	2.20	2.30	2.49	2.55	3.95	3.32	3.3	3.3	3.9	4.4	4.3
Organic Nitrogen	0.15	0.79	0.65	1.04	1.01	0.45	0.98	0.23	0.31	0.39	0.33	0.69	0.03
Phenols		<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.023	<0.002	<0.002
Dissolved Organic Carbon(DOC)	5 [AO]	6.9	7.5	4.1	3.0	4.6	4.3	4.6	7.3	3.8	6.4	5.9	8.0
Conductivity (us/cm)		1450	1350	1390	1310	1320	1320	1350	1250	1200	1270	1220	1260
pH		7.69	7.46	8.16	8.04	7.66	7.61	7.59	7.72	7.69	7.28	8.01	7.66
Sulphate (as SO4)	250 (AO)	268	252	279	281	214	182	168	155	165	147	153	139
Hardness(as CaCO3)	80-100 [OG]	767	725	664	662	676	731	717	669	603	645	667	1050
Aluminum	0.1 [OG]	0.04	0.03	0.058	<0.004	0.04	0.05	0.05	0.08	0.07	0.07	0.07	0.34
Barium	1 [MAC]	0.067	0.064	0.066	0.070	0.066	0.074	0.072	0.071	0.063	0.074	0.068	0.090
Boron	5 [IMAC]	0.862	0.902	0.900	0.878	0.768	0.894	0.808	0.783	0.619	0.678	0.684	0.667
Cadmium	0.005 (MAC)	<0.00002	<0.00002	<0.001	<0.001	0.00002	0.00003	0.000016	<0.000014	0.000015	0.000022	0.000016	0.000055
Calcium	-	166	154	137	145	144	160	153	144	128	144	146	252
Chromium	0.05 (MAC)	<0.002	<0.002	<0.003	<0.003	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	0.001
Copper	1 [AO]	0.002	0.0029	<0.003	<0.003	0.004	0.0028	0.003	<0.002	<0.002	<0.002	0.002	0.0055
Iron	0.3 [AO]	<0.005	<0.005	<0.010	<0.010	<0.005	0.010	<0.005	<0.005	<0.005	<0.005	<0.005	0.603
Lead	0.01 (MAC)c	<0.00002	0.00005	<0.002	<0.002	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002	0.00086	<0.00002	0.00104
Magnesium	-	85.5	82.9	78.2	72.9	76.9	80.6	81.3	75.1	68.9	69.4	73.6	103
Manganese	0.05 [AO]	0.117	0.115	0.133	0.131	0.173	0.176	0.224	0.196	0.189	0.203	0.243	0.374
Potassium	-	22.8	24.1	24.5	27.5	23.6	29.7	27.3	26.5	24.7	26.0	25.4	26.9
Sodium	200 [AO]	34.6	29.9	30.2	25.0	29.1	31.4	32.2	27.0	28.4	27.4	27.4	25.1
Zinc	5 [AO]	<0.005	<0.005	0.010	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I	OW13 I
		Jul-20	Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	556	512	526	533	517	555	593	545
Chloride	250 [AO]	19.4	15.1	15.3	13.7	15.0	13.6	15.7	12.4
Nitrate(as N)	10 (MAC) d	0.19	0.07	0.11	0.24	<0.05	0.18	0.11	0.14
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		4.16	4.84	3.86	0.02	4.57	2.97	5.17	4.63
Total Kjeldahl Nitrogen(as N)		4.6	4.9	5.2	2.4	5.5	3.0	5.0	4.2
Organic Nitrogen	0.15	0.44	0.06	1.34	2.38	0.93	0.03	<0.1	<0.1
Phenols		<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	7.4	4.5	6.7	4.3	6.3	3.3	5.8	9.3
Conductivity (us/cm)		1250	1210	1200	1150	1210	1170	1220	1160
pH		7.53	7.44	7.51	7.65	7.50	7.64	7.70	7.51
Sulphate (as SO4)	250 (AO)	135	121	125	118	113	99	101	90
Hardness(as CaCO3)	80-100 [OG]	662	656	666	626	626	557	601	538
Aluminum	0.1 [OG]	0.08	0.10	0.08	0.10	0.10	0.04	0.04	0.07
Barium	1 [MAC]	0.084	0.083	0.081	0.075	0.090	0.074	0.080	0.078
Boron	5 [IMAC]	0.661	0.638	0.639	0.615	0.570	0.558	0.550	0.534
Cadmium	0.005 (MAC)	<0.000028	0.000125	0.000022	<0.000015	0.000037	<0.000028	<0.000028	<0.000015
Calcium	-	143	141	148	142	140	123	133	121
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.002	0.002	<0.001	<0.001	<0.001
Copper	1 [AO]	<0.002	0.004	0.007	<0.002	0.0042	0.0018	0.0024	0.0023
Iron	0.3 [AO]	0.048	0.051	<0.005	0.034	<0.005	<0.005	<0.005	<0.005
Lead	0.01 (MAC)c	0.00015	0.0001	0.00004	<0.00002	0.00076	<0.00004	<0.00004	<0.00004
Magnesium	-	74.1	73.9	72.0	65.9	67.2	60.6	65.3	57.3
Manganese	0.05 [AO]	0.298	0.266	0.302	0.21	0.093	0.133	0.305	0.241
Potassium	-	26.1	27.5	28.4	26.7	25.4	23.5	22.6	23.7
Sodium	200 [AO]	26.5	24.4	25.0	21.6	25.3	21.8	23.1	19.7
Zinc	5 [AO]	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.006

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D
		Jul-07	Dec-07	Jul-08	Dec-08	Jul-09	Dec-09	Mar-10	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13
Alkalinity(as CaCO3)	30 - 500 [OG]	240	288	231	235	234	260	240	244	274	254	349	234
Chloride	250 [AO]	10	31	8	10	7	13	10	6.6	12.2	9.6	19.5	6.6
Nitrate(as N)	10 (MAC) d	nd	nd	0.1	nd	0.1	0.1	0.1	<0.1	<0.1	<0.1	<0.1	0.1
Nitrite(as N)	1 (MAC) d	nd	0.03	nd	0.3	nd	nd	<0.01	<0.1	<0.1	<0.1	<0.1	<0.1
Ammonia(as N)		0.13	0.15	0.22	0.28	0.26	0.25	<0.05	0.03	0.09	0.13	0.06	0.09
Total Kjeldahl Nitrogen(as N)		0.2	0.4	1	1.5	5	nd	0.5	0.35	0.33	0.15	0.51	0.90
Organic Nitrogen	0.15	0.07	0.25	0.78	1.22	4.74	nd	<0.45	0.32	0.24	0.02	0.45	0.81
Phenols		nd	nd	nd	nd	nd	nd	nd	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	1	2	1	0.7	0.7	1.6	0.9	0.7	2.7	1.0	2.3	2.6
Conductivity (us/cm)		516	1000	546	538	544	764	575	545	750	624	934	547
pH		8.2	8.1	8.2	8.2	8	8	8.0	7.73	7.87	8.05	7.74	7.95
Sulphate (as SO4)	250 (AO)	45	193	42	47	44	130	62	50	111	75	172	51
Hardness(as CaCO3)	80-100 [OG]	260	640	230	240	220	340	230	235	367	284	445	224
Aluminum	0.1 [OG]	nd	nd	nd	nd	nd	nd	nd	0.03	0.05	0.02	0.05	0.03
Barium	1 [MAC]	0.096	0.22	0.085	0.089	0.082	0.12	0.086	0.090	0.128	0.108	0.158	0.087
Boron	5 [IMAC]	0.044	0.45	0.04	0.057	0.043	0.19	0.045	0.053	-	0.104	0.289	0.061
Cadmium	0.005 (MAC)	0.0004	0.001	nd	nd	0.0003	nd	0.0001	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002
Calcium	-	61	140	54	55	51	79	55	56.1	87.3	66.8	104	53.2
Chromium	0.05 (MAC)	nd	nd	nd	nd	nd	nd	nd	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	nd	0.002	nd	0.001	nd	0.001	nd	<0.002	<0.002	<0.002	<0.002	<0.002
Iron	0.3 [AO]	0.46	0.72	nd	nd	0.64	1.2	nd	0.111	0.611	0.360	0.799	0.376
Lead	0.01 (MAC)c	nd	nd	nd	nd	nd	nd	0.0006	<0.00002	<0.00002	<0.00002	0.00006	<0.00002
Magnesium	-	26	69	23	24	21	36	23	22.9	36.2	28.4	45.2	22.1
Manganese	0.05 [AO]	0.014	0.032	0.022	0.01	0.012	0.019	0.015	0.013	0.016	0.016	0.024	0.012
Potassium	-	1	3.6	0.86	1	0.82	1.3	0.91	1.0	1.7	1.3	2.5	1.1
Sodium	200 [AO]	16	39	14	15	14	19	14	13.9	21.4	16.3	24.1	14.0
Zinc	5 [AO]	nd	nd	nd	nd	nd	nd	nd	<0.005	0.008	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINFLOSS LANDFILL**

Chemical Parameter	ODWQS	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D
		Nov-13	Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19
Alkalinity(as CaCO3)	30 - 500 [OG]	268	219	256	263	357	249	341	237	274	227	278	222
Chloride	250 [AO]	9.8	6.6	9.7	10.2	16.1	6.6	11.7	7.2	7.6	6.6	9.8	6.8
Nitrate(as N)	10 (MAC) d	<0.1	<0.1	<0.1	<0.10	<0.25	0.1	<0.1	<0.05	0.2	<0.05	0.05	0.19
Nitrite(as N)	1 (MAC) d	<0.1	<0.1	<0.1	<0.10	<0.25	<0.1	<0.1	<0.05	0.3	<0.05	<0.05	0.06
Ammonia(as N)		0.09	0.10	0.10	0.03	0.17	0.08	0.19	<0.01	0.13	0.14	0.28	0.20
Total Kjeldahl Nitrogen(as N)		0.22	0.22	0.31	0.11	0.28	0.07	0.30	0.09	0.4	0.2	0.4	0.2
Organic Nitrogen	0.15	0.13	0.12	0.21	0.08	0.11	-	0.11	0.09	0.27	0.06	0.12	-
Phenols		<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.004	<0.002
Dissolved Organic Carbon(DOC)	5 [AO]	3.9	2.5	4.1	1.8	1.5	1.0	1.6	1.2	3.1	1.3	2.3	14.4
Conductivity (us/cm)		569	536	612	647	911	543	824	560	677	521	716	545
pH		8	8.03	7.86	8.36	7.93	8.05	7.84	8.01	7.98	8.10	7.65	8.02
Sulphate (as SO4)	250 (AO)	85	46	79	69.9	148	51	112	42	59	46	74	46
Hardness(as CaCO3)	80-100 [OG]	278	237	293	270	457	233	412	257	330	220	321	245
Aluminum	0.1 [OG]	0.04	0.02	0.02	<0.004	<0.004	0.02	0.04	0.02	0.05	0.03	0.05	0.03
Barium	1 [MAC]	0.102	0.080	0.102	0.092	0.163	0.085	0.147	0.092	0.122	0.078	0.120	0.081
Boron	5 [IMAC]	0.127	0.046	0.141	0.114	0.301	0.055	0.270	0.071	0.187	0.052	0.161	0.061
Cadmium	0.005 (MAC)	<0.00002	<0.00002	<0.00002	<0.001	<0.001	<0.00002	0.00002	<0.000014	<0.000014	<0.000015	<0.000015	<0.000015
Calcium	-	65.4	57.5	68.8	63.9	105	55.5	97.5	60.7	76.6	50.6	76.6	57.9
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.003	<0.003	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	0.0002	<0.002	0.0002	<0.003	<0.003	<0.002	0.0005	<0.002	<0.002	<0.002	<0.002	0.008
Iron	0.3 [AO]	0.595	0.270	0.591	0.118	0.766	0.249	0.751	0.145	0.579	0.167	0.565	0.211
Lead	0.01 (MAC)c	<0.00002	<0.00002	<0.00002	<0.002	<0.002	<0.00002	<0.00002	<0.00002	<0.00002	<0.00002	0.0108	0.00003
Magnesium	-	27.9	22.7	29.4	26.7	47.2	23.0	41.0	25.6	33.8	22.8	31.6	24.3
Manganese	0.05 [AO]	0.015	0.013	0.018	0.023	0.028	0.016	0.025	0.022	0.022	0.014	0.018	0.015
Potassium	-	1.6	1	1.6	1.72	3.85	1.1	3.3	1.7	2.7	1.3	2.5	1.5
Sodium	200 [AO]	16.2	14.3	16.5	15.7	23.7	14.5	24.3	16.5	18.8	14.9	19.3	14.9
Zinc	5 [AO]	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D	OW13 D
		Nov-19	Jul-20	Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	289	235	304	237	340	227	285	243	265
Chloride	250 [AO]	10.8	7.6	10.1	6.4	10.1	6.3	7.6	7.1	7.8
Nitrate(as N)	10 (MAC) d	0.22	0.14	0.13	0.11	0.22	0.06	0.21	0.08	0.15
Nitrite(as N)	1 (MAC) d	0.18	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		0.31	0.19	0.46	0.22	0.53	0.20	0.34	0.15	0.22
Total Kjeldahl Nitrogen(as N)		0.4	0.3	0.6	0.3	0.7	0.6	0.5	0.2	1.7
Organic Nitrogen	0.15	0.09	0.11	0.14	0.08	0.17	0.4	0.16	0.05	1.48
Phenols		<0.002	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	2.8	4.1	2.5	2.0	2.3	1.7	1.2	2.0	3.6
Conductivity (us/cm)		730	539	763	572	760	547	643	542	606
pH		7.90	7.95	7.78	8.07	7.86	7.83	7.87	7.92	7.65
Sulphate (as SO4)	250 (AO)	74	48	79	52	76	46	60	48	51
Hardness(as CaCO3)	80-100 [OG]	324	246	373	271	357	233	300	221	243
Aluminum	0.1 [OG]	0.06	0.02	0.04	0.05	0.08	0.02	0.03	0.01	0.04
Barium	1 [MAC]	0.118	0.094	0.144	0.100	0.132	0.084	0.113	0.079	0.092
Boron	5 [IMAC]	0.170	0.073	0.190	0.086	0.195	0.056	0.144	0.043	0.070
Cadmium	0.005 (MAC)	<0.000015	0.000397	<0.000015	<0.000015	0.000951	<0.000015	<0.000015	<0.000015	<0.000015
Calcium	-	75.8	57.4	83.6	63.4	83.6	54.6	69.9	51.9	58.0
Chromium	0.05 (MAC)	<0.001	<0.002	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001
Copper	1 [AO]	0.0007	<0.002	<0.002	0.012	<0.002	0.0003	0.0004	0.0002	0.0004
Iron	0.3 [AO]	0.715	0.220	0.586	0.159	0.556	0.363	0.514	0.066	0.458
Lead	0.01 (MAC)c	0.00007	0.00002	0.00003	0.00039	0.00007	0.00003	0.00003	<0.00002	0.00002
Magnesium	-	32.7	24.8	39.8	27.4	35.9	23.5	30.4	22.3	23.8
Manganese	0.05 [AO]	0.021	0.018	0.029	0.017	0.030	0.014	0.024	0.016	0.015
Potassium	-	2.8	2	3.6	1.8	3.4	1.6	2.5	1.0	1.0
Sodium	200 [AO]	18.2	14.7	20.5	16.5	18.3	13.7	16.9	13.1	14.7
Zinc	5 [AO]	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

**NOTES:**

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14
		Jul-07	Jul-08	Jul-09	Dec-09	Mar-10	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13	Nov-13	Jul-14
Alkalinity(as CaCO3)	30 - 500 [OG]	702	633	600	IS	619	590	548	550	Dry	581	535	523
Chloride	250 [AO]	11	8	9	IS	12	3.4	3.0	4.3		5.3	2.8	2.9
Nitrate(as N)	10 (MAC) d	nd	nd	nd	IS	<0.1	<0.1	<0.1	<0.1		0.2	<0.1	0.1
Nitrite(as N)	1 (MAC) d	nd	nd	nd	IS	<0.01	<0.1	<0.1	<0.1		<0.1	<0.1	<0.1
Ammonia(as N)		14.5	11	16	IS	11	8.36	7.14	6.05		4.73	4.42	6.38
Total Kjeldahl Nitrogen(as N)		12	11	14	IS	11	10.6	7.22	6.77		8.06	7.24	7.93
Organic Nitrogen	0.15	0	0	0	IS	0	2.24	0.08	0.72		3.33	2.82	1.55
Phenols		0.006	0.001	0.004	IS	0.004	0.007	0.006	0.004		0.006	0.006	0.003
Dissolved Organic Carbon(DOC)	5 [AO]	8.7	9.2	8.9	IS	8.2	9.3	8.2	7.7		21.1	16.4	15.7
Conductivity (us/cm)		1160	1190	1120	IS	1170	1040	1050	1050		988	857	1060
pH		8	7.8	7.4	IS	7.4	7.09	7.15	7.34		7.27	7.32	7.35
Sulphate (as SO4)	250 (AO)	16	35	1	IS	34	8	5	22		8	22	19
Hardness(as CaCO3)	80-100 [OG]	590	560	520	IS	560	528	556	512		499	499	559
Aluminum	0.1 [OG]	0.009	0.007	0.007	IS	0.006	0.05	0.06	0.05		0.05	0.06	0.05
Barium	1 [MAC]	0.071	0.068	0.089	IS	0.072	0.087	0.082	0.062		0.054	0.05	0.062
Boron	5 [IMAC]	0.45	0.35	0.390	IS	0.30	0.286	-	0.329		0.166	0.142	0.228
Cadmium	0.005 (MAC)	0.0002	nd	0.0003	IS	0.0001	<0.00002	<0.00002	0.00004		0.00004	0.0001	<0.00002
Calcium	-	160	160	160	IS	170	142	181	159		166	167	182
Chromium	0.05 (MAC)	nd	nd	nd	IS	nd	<0.002	<0.002	<0.002		<0.002	<0.002	<0.002
Copper	1 [AO]	0.001	0.001	nd	IS	0.002	<0.002	<0.002	<0.002		<0.002	0.0004	<0.002
Iron	0.3 [AO]	0.69	1.9	6.5	IS	12	20.0	24.4	19.4		32.6	25.3	36.6
Lead	0.01 (MAC)c	nd	nd	nd	IS	nd	<0.00002	0.00002	<0.00002		0.00005	<0.00002	<0.00002
Magnesium	-	44	38	30	IS	33	42.3	24.8	27.6		20.5	20	25.3
Manganese	0.05 [AO]	4.7	5.3	2.7	IS	2	0.807	0.665	0.296		0.912	0.433	0.704
Potassium	-	25	22	22	IS	18	26.1	28.9	18.3		9.1	9.4	11.3
Sodium	200 [AO]	45	34	18	IS	15	8.2	6.9	8.4		5.8	4	6.7
Zinc	5 [AO]	nd	0.006	nd	IS	0.010	<0.005	<0.005	0.008		<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14	OW14
		Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19	Jul-20
Alkalinity(as CaCO3)	30 - 500 [OG]	597	506	531	677	519	530	501	519	458	510	460	491
Chloride	250 [AO]	7.7	4.77	3.76	5.6	16.7	8.8	6.8	10.4	6.5	7.1	21.6	14.1
Nitrate(as N)	10 (MAC) d	0.1	<0.25	<0.25	0.1	<0.1	<0.05	<0.1	0.05	0.07	<0.05	0.09	0.08
Nitrite(as N)	1 (MAC) d	<0.1	<0.25	<0.25	<0.1	<0.1	<0.05	<0.1	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		5.73	4.46	1.71	5.34	5.17	3.56	3.59	4.90	4.60	4.40	3.61	2.74
Total Kjeldahl Nitrogen(as N)		6.46	5.40	4.65	5.73	5.95	3.99	3.9	5.3	4.6	5.2	4.0	3.5
Organic Nitrogen	0.15	0.73	0.94	2.94	0.39	0.78	0.43	0.31	0.4	-	0.8	0.39	0.76
Phenols		0.003	<0.001	<0.001	0.001	<0.001	<0.001	<0.001	0.003	0.015	<0.002	0.002	<0.002
Dissolved Organic Carbon(DOC)	5 [AO]	9.8	7.0	5.0	7.1	6.0	7.4	10.3	15.3	9.6	10.1	11.6	10.3
Conductivity (us/cm)		1080	970	948	1020	81	1050	1020	1000	940	981	1030	976
pH		7.5	7.82	7.80	7.18	7.30	7.29	7.41	7.29	7.20	7.33	7.42	7.22
Sulphate (as SO4)	250 (AO)	34	15.1	26.0	9	18	22	49	34	13	13	54	36
Hardness(as CaCO3)	80-100 [OG]	574	471	505	516	578	580	572	523	506	554	534	553
Aluminum	0.1 [OG]	0.04	0.008	0.007	0.05	0.05	0.06	0.10	0.09	0.08	0.09	0.08	0.14
Barium	1 [MAC]	0.237	0.049	0.044	0.056	0.045	0.056	0.046	0.061	0.049	0.053	0.043	0.045
Boron	5 [IMAC]	0.216	0.186	0.161	0.215	0.173	0.162	0.161	0.205	0.160	0.182	0.144	0.186
Cadmium	0.005 (MAC)	0.00004	<0.001	<0.001	<0.00002	<0.00002	<0.000014	<0.000014	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015
Calcium	-	184	158	169	165	192	193	189	172	170	186	179	185
Chromium	0.05 (MAC)	0.003	<0.003	<0.003	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.001	<0.002
Copper	1 [AO]	0.0012	<0.003	<0.003	<0.002	0.0002	<0.002	<0.002	<0.002	<0.002	<0.002	0.0047	<0.002
Iron	0.3 [AO]	0.172	17.4	3.07	38.5	10.4	23.8	25.9	29.3	30.1	28.7	22.7	32.1
Lead	0.01 (MAC)c	<0.00002	<0.002	<0.002	<0.00002	<0.00002	<0.00002	<0.00002	0.00002	<0.00002	<0.00002	0.00007	0.00022
Magnesium	-	27.9	18.6	20.1	25.1	23.9	24.0	24.3	22.7	19.6	21.7	21.1	21.9
Manganese	0.05 [AO]	0.741	0.301	0.291	0.325	0.314	0.422	0.231	0.539	0.222	0.428	0.26	0.204
Potassium	-	15.7	9.33	8.68	8.7	9.8	7.8	7.2	9.1	8.5	7.8	7.1	5.8
Sodium	200 [AO]	7.9	4.91	3.64	4.5	3.9	5.1	5.5	7.0	7.0	7.2	6.1	7.6
Zinc	5 [AO]	0.022	<0.005	<0.005	<0.005	<0.005	0.006	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.



**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW14	OW14	OW14	OW14	OW14	OW14	OW14
		Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	445	479	512	488	517	573	619
Chloride	250 [AO]	13.7	19.9	25.5	60.8	60.4	51.6	42.8
Nitrate(as N)	10 (MAC) d	<0.05	<0.05	<0.05	<0.05	0.13	0.09	0.08
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		2.24	2.64	2.15	4.71	2.82	5.75	2.29
Total Kjeldahl Nitrogen(as N)		2.7	3.0	2.8	5.9	4.4	6.0	3.4
Organic Nitrogen	0.15	0.46	0.36	0.65	1.19	1.58	0.25	1.11
Phenols		0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	8.9	11.2	9.3	10.0	15.4	9.1	18.0
Conductivity (us/cm)		968	1000	1020	1200	1270	1270	1400
pH		7.28	7.22	7.51	7.32	7.32	7.35	7.23
Sulphate (as SO4)	250 (AO)	40	33	44	49	132	83	97
Hardness(as CaCO3)	80-100 [OG]	553	600	595	613	700	607	705
Aluminum	0.1 [OG]	0.09	0.10	0.10	0.07	0.06	0.06	0.12
Barium	1 [MAC]	0.034	0.042	0.034	0.060	0.047	0.061	0.055
Boron	5 [IMAC]	0.102	0.167	0.165	0.199	0.191	0.163	0.176
Cadmium	0.005 (MAC)	<0.000015	<0.000015	0.000038	<0.000028	<0.000028	<0.000028	<0.000015
Calcium	-	184	198	196	200	231	197	223
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001
Copper	1 [AO]	<0.002	<0.002	<0.002	0.0014	0.0008	0.0006	0.0009
Iron	0.3 [AO]	3.23	34.4	13.6	45.2	21.8	35.0	22.0
Lead	0.01 (MAC)c	0.00003	<0.00002	0.00005	0.00012	<0.00004	<0.00004	<0.00004
Magnesium	-	22.7	25.5	25.5	27.3	29.6	28.2	35.9
Manganese	0.05 [AO]	0.185	0.182	0.250	0.153	0.172	0.225	0.096
Potassium	-	5.7	5.2	5.0	8.8	8.2	8.3	6.6
Sodium	200 [AO]	7.5	6.9	6.7	13.8	28.6	19.9	32.0
Zinc	5 [AO]	<0.005	<0.005	0.012	<0.005	<0.005	<0.005	0.008

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW15	OW15 Dup#1	OW15	OW15	OW15	OW15	OW15	OW15	OW15	OW15	OW15	OW15
		Nov-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19	Jul-20	Nov-20	Jun-21	Nov-21
Alkalinity(as CaCO3)	30 - 500 [OG]	505	521	534	548	553	499	513	466	490	355	499	436
Chloride	250 [AO]	54.7	54.8	57.9	41.6	69.9	46.4	65.2	49.9	67.5	18.6	57.1	29.1
Nitrate(as N)	10 (MAC) d	<0.1	<0.1	<0.05	<0.1	<0.05	<0.05	<0.05	0.10	0.08	<0.05	<0.05	<0.05
Nitrite(as N)	1 (MAC) d	<0.1	<0.1	<0.05	<0.1	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		0.10	0.10	0.08	0.11	0.39	0.20	0.53	0.27	0.47	0.11	0.30	0.05
Total Kjeldahl Nitrogen(as N)		0.56	0.65	0.46	0.7	3.4	3.3	2.3	0.7	0.7	0.6	8.9	11.6
Organic Nitrogen	0.15	0.46	0.55	0.38	0.59	3.01	3.10	1.77	0.43	0.23	0.49	8.6	11.55
Phenols		<0.001	<0.001	<0.001	<0.001	<0.001	0.021	<0.002	<0.002	<0.002	<0.002	<0.002	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	6.0	5.9	6.4	13.9	5.6	12.2	6.9	12.5	5.1	16.7	6.0	12.2
Conductivity (us/cm)		1370	1370	1540	1360	1530	1320	1520	1250	1500	842	1490	1000
pH		7.70	7.76	7.61	7.76	7.75	7.50	7.90	7.72	7.52	7.59	7.76	7.77
Sulphate (as SO4)	250 (AO)	212	213	217	157	267	156	277	162	291	62	235	105
Hardness(as CaCO3)	80-100 [OG]	766	764	768	684	748	676	805	576	810	411	819	564
Aluminum	0.1 [OG]	0.05	0.05	0.05	0.09	0.09	0.08	0.08	0.07	0.10	0.05	0.11	0.09
Barium	1 [MAC]	0.235	0.233	0.225	0.129	0.193	0.119	0.164	0.091	0.208	0.071	0.179	0.100
Boron	5 [IMAC]	0.261	0.260	0.264	0.209	0.296	0.219	0.349	0.174	0.366	0.046	0.347	0.196
Cadmium	0.005 (MAC)	0.00003	<0.00002	<0.000014	0.000014	<0.000015	<0.000015	<0.000015	<0.000028	<0.000028	<0.000015	<0.000028	<0.000015
Calcium	-	184	184	178	164	164	163	180	139	178	102	186	137
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.001	<0.002	<0.002	<0.002	<0.002
Copper	1 [AO]	0.0008	0.0008	<0.002	<0.002	<0.002	<0.002	<0.002	0.0043	<0.002	0.003	0.004	<0.002
Iron	0.3 [AO]	0.084	0.080	0.332	0.619	0.352	0.999	0.330	1.17	0.423	0.808	0.836	0.886
Lead	0.01 (MAC)c	<0.00002	<0.00002	0.00010	0.00022	0.00017	0.00020	0.00020	0.00022	0.00025	0.00019	0.00022	0.00017
Magnesium	-	74.1	74.1	78.8	66.7	82.3	65.4	86.4	55.7	89.1	38.2	86.1	53.8
Manganese	0.05 [AO]	0.854	0.846	0.407	0.472	0.290	0.466	0.334	0.391	0.378	0.258	0.405	0.365
Potassium	-	1.9	1.9	2.4	2.9	2.5	3.1	2.7	3.1	2.9	3.1	3.2	3.6
Sodium	200 [AO]	48.1	47.8	51.1	39.0	55.2	41.5	52.3	29.7	51.5	13.5	51.6	27.8
Zinc	5 [AO]	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW15	OW15	OW15	OW15
		Jun-22	Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	491	409	493	450
Chloride	250 [AO]	56.8	8.8	55.0	6.6
Nitrate(as N)	10 (MAC) d	<0.05	<0.05	<0.05	0.06
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		0.42	0.05	0.20	0.16
Total Kjeldahl Nitrogen(as N)		3.8	14.7	3.2	3.6
Organic Nitrogen	0.15	3.38	14.65	3.0	3.44
Phenols		<0.001	0.002	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	5.2	19.5	4.4	22
Conductivity (us/cm)		1510	756	1360	816
pH		7.76	7.78	7.88	7.68
Sulphate (as SO4)	250 (AO)	248	4	256	3
Hardness(as CaCO3)	80-100 [OG]	839	439	680	439
Aluminum	0.1 [OG]	0.58	0.25	0.04	0.07
Barium	1 [MAC]	0.180	0.067	0.146	0.077
Boron	5 [MAC]	0.364	0.074	0.313	0.075
Cadmium	0.005 (MAC)	<0.000028	<0.000015	<0.000028	<0.000015
Calcium	-	190	112	152	114
Chromium	0.05 (MAC)	0.002	0.001	<0.001	<0.001
Copper	1 [AO]	0.0021	0.0014	0.0005	0.0008
Iron	0.3 [AO]	1.55	1.15	0.427	2.49
Lead	0.01 (MAC)c	0.00089	0.00057	0.00012	0.00027
Magnesium	-	88.8	38.6	73.2	37.4
Manganese	0.05 [AO]	0.455	0.305	0.374	0.404
Potassium	-	3.2	3.3	2.4	3.1
Sodium	200 [AO]	44.9	9.4	38.4	7.9
Zinc	5 [AO]	<0.005	<0.005	<0.005	0.005

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW16	OW16	OW16	OW16	OW16	OW16	OW16	OW16	OW16	OW16	OW16	OW16
		Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19	Jul-20	Nov-20	Jun-21	Nov-21	Jun-22
Alkalinity(as CaCO3)	30 - 500 [OG]	303	289	280	274	263	263	268	271	262	265	275	272
Chloride	250 [AO]	6.7	7.4	6.1	8.4	7.6	7.8	9.2	8.3	7.1	7.3	7.4	7.3
Nitrate(as N)	10 (MAC) d	0.6	0.68	0.2	0.48	0.38	0.27	0.21	0.68	0.33	0.41	0.35	0.75
Nitrite(as N)	1 (MAC) d	0.2	0.33	0.3	0.08	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Ammonia(as N)		0.04	<0.01	0.06	0.10	0.12	0.19	0.20	0.17	0.08	0.06	<0.01	0.08
Total Kjeldahl Nitrogen(as N)		0.37	0.27	0.3	18.7	3.2	0.5	0.5	0.4	0.3	22.9	34.0	5.7
Organic Nitrogen	0.15	0.33	0.27	0.24	18.6	3.08	0.31	0.30	0.23	0.22	22.84	34.0	5.62
Phenols		<0.001	<0.001	<0.001	<0.001	0.025	<0.002	<0.002	<0.002	<0.002	<0.002	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	3.9	2.2	3.2	1.5	4.4	8.5	4.3	2.7	4.3	4.6	2.3	2.7
Conductivity (us/cm)		585	573	569	554	573	558	572	550	563	557	551	568
pH		7.99	7.93	8.01	8.04	7.81	7.99	7.97	7.79	7.82	8.00	7.98	7.85
Sulphate (as SO4)	250 (AO)	10	7	16	12	15	26	39	13	13	14	18	13
Hardness(as CaCO3)	80-100 [OG]	338	325	314	275	325	315	315	305	332	326	305	324
Aluminum	0.1 [OG]	0.03	0.03	0.05	0.05	0.05	0.05	0.05	0.03	0.05	0.07	0.05	0.15
Barium	1 [MAC]	0.081	0.072	0.066	0.064	0.080	0.056	0.081	0.091	0.095	0.088	0.079	0.071
Boron	5 [IMAC]	0.014	<0.005	0.012	0.009	0.010	0.007	0.011	0.012	<0.005	0.011	0.011	<0.005
Cadmium	0.005 (MAC)	0.00004	<0.000014	<0.000014	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015	<0.000015
Calcium	-	90.8	85.7	83.5	71.3	88.5	83.4	84.5	80.0	86.4	86.8	81.4	85.5
Chromium	0.05 (MAC)	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.001	<0.002	<0.002	<0.002	<0.002	<0.001
Copper	1 [AO]	0.0303	<0.002	<0.002	<0.002	<0.002	0.006	0.0027	<0.002	0.012	<0.002	<0.002	0.0010
Iron	0.3 [AO]	0.023	<0.005	0.005	0.010	0.023	0.005	0.146	0.046	0.132	0.076	0.120	0.290
Lead	0.01 (MAC)c	<0.00002	<0.00002	<0.00002	0.00006	0.00005	0.00002	0.00007	0.00006	0.00007	0.00003	0.00007	0.00023
Magnesium	-	27.0	26.9	25.6	23.6	25.3	26.0	25.2	25.6	28.2	26.5	24.6	26.7
Manganese	0.05 [AO]	0.366	0.218	0.117	0.116	0.177	0.073	0.135	0.096	0.154	0.104	0.124	0.091
Potassium	-	0.9	1.0	1.0	0.9	0.8	1.0	0.8	1.2	1.0	0.9	0.9	1.1
Sodium	200 [AO]	4.7	3.7	3.2	3.1	3.7	3.1	3.3	3.0	3.6	3.1	3.0	2.7
Zinc	5 [AO]	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.005	<0.005	<0.005	<0.005

NOTES:

1. All results expresses in mg/L unless otherwise noted.
2. ODWQS is the Ontario Drinking Water Quality Standards, MOE, revised 2001.
3. MAC maximum acceptable concentration ODWQS.
4. IMAC indicates an interim maximum acceptable concentration ODWQS.
5. AO indicates an aesthetic objective ODWQS, not health related.
6. OG indicates an operational guideline ODWQS, not health related.
7. c indicates that the guideline applies to water at the point of consumption.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. nd indicates parameter not detected.
8. d, where nitrate and nitrite are present the total of the two should not exceed 10 mg/L.
9. < indicates parameter not detected above method detection limit.
10. <T indicates a detection of a Trace amount less than the method detection limit.
11. S.E. indicates a sampling error.
12. nd indicates parameter not detected.
13. IS indicates insufficient sample for analysis.
14. Shaded values indicate exceedance of ODWQS.

**TABLE E-2  
HISTORICAL WELL WATER QUALITY  
KINLOSS LANDFILL**

Chemical Parameter	ODWQS	OW16		
		Nov-22	May-23	Sep-23
Alkalinity(as CaCO3)	30 - 500 [OG]	302	295	311
Chloride	250 [AO]	6.6	7.7	6.9
Nitrate(as N)	10 (MAC) d	0.44	0.59	0.28
Nitrite(as N)	1 (MAC) d	<0.05	<0.05	<0.05
Ammonia(as N)		0.03	0.01	0.12
Total Kjeldahl Nitrogen(as N)		26.7	8.5	<0.1
Organic Nitrogen	0.15	26.67	8.49	<0.1
Phenols		<0.001	<0.001	<0.001
Dissolved Organic Carbon(DOC)	5 [AO]	5.7	3.9	8.3
Conductivity (us/cm)		579	575	607
pH		7.87	8.09	7.56
Sulphate (as SO4)	250 (AO)	16	15	16
Hardness(as CaCO3)	80-100 [OG]	347	300	327
Aluminum	0.1 [OG]	0.04	0.02	0.06
Barium	1 [MAC]	0.096	0.080	0.092
Boron	5 [MAC]	0.014	0.008	0.018
Cadmium	0.005 (MAC)	<0.000015	<0.000015	<0.000015
Calcium	-	91.8	79.0	87.1
Chromium	0.05 (MAC)	<0.001	<0.001	<0.001
Copper	1 [AO]	0.0011	0.0003	0.0007
Iron	0.3 [AO]	0.257	0.052	0.177
Lead	0.01 (MAC)c	0.00007	0.00002	0.00005
Magnesium	-	28.5	25.0	26.5
Manganese	0.05 [AO]	0.189	0.108	0.193
Potassium	-	1.0	1.0	0.8
Sodium	200 [AO]	3.6	2.9	3.6
Zinc	5 [AO]	<0.005	<0.005	<0.005

**APPENDIX F**

**2023 Landfill Correspondence**

Ministry of the Environment  
Southwestern Region  
Barrie District Office  
1580 20th St E  
Owen Sound ON N4K 6H6  
Fax: (519)371-2905  
Telephone: (519) 371-6191

Ministère de l'Environnement  
Direction régionale du Sud-Ouest  
Bureau du district de Barrie  
1580 rue 20th E  
Owen Sound ON N4K 6H6  
Télécopieur: (519)371-2905  
Téléphone : (519) 371-6191



July 16, 2007

Mr. Hugh Nicol  
Township of Huron-Kinloss  
21 Queen Street  
PO Box 130  
Ripley, ON, N0G 2R0

**RECEIVED**  
**JUL 19 2007**  
TOWNSHIP OF  
HURON-KINLOSS

**RE: Kinloss Landfill Site - 2006 Annual Report**

Dear Mr. Nicol,

We have received a copy of the report titled "Township of Huron-Kinloss 2006 Annual Operations and Monitoring Report, Kinloss Landfill Site", dated March 2007 and prepared by R.J. Burnside & Associates Limited. A copy of the report was sent to the Ministry's technical support section for their review and their comments follow:

The landfill does not appear to be resulting in any major impacts to ground water quality. However, there are some issues that should be addressed in time for the next annual monitoring report.

- Two wells (OW7 and OW12) have traditionally been considered to be "background" wells. Well OW7 is quite often dry during the sampling events, and is thus not ideal as a background well. Well OW12, even though apparently up-gradient of the waste and exhibiting low concentrations of chloride, still exhibits concentrations of some parameters (eg. nitrate, total dissolved solids, sulphate) that are considerably higher than exhibited at other wells (OW5, OW6, OW7). Thus, it is possible that this well samples water that has been impacted by leachate. We are not convinced that either OW7 or OW12 are ideal as background wells.

A discussion about whether another well (eg. OW6) may be more appropriate should be provided. Samples obtained from this well have consistently shown concentrations of indicator parameters that are lower than in waters from OW12. Could this well be considered to be "cross-gradient" to the waste and thus useful as a "background" well?

- The concentrations of sulphate in waters sampled by OW13 and OW13INT are typically elevated, sometimes above the calculated RUG. The consultant has suggested that these are not representative of leachate impact because sulphate concentrations were much lower at Well OW4, which is otherwise more clearly impacted by leachate (eg. elevated

chloride, TDS, etc). Could these high sulphate concentrations be the result of a redox transition along the flowpath between OW4 and OW13? Consider that 1) iron, manganese and ammonia are elevated at OW4, but are significantly less at OW13; and, 2) nitrate and sulphate are not detected and lower, respectively, at OW4, whereas they are both elevated at OW13. These two patterns suggest that reducing conditions prevail around OW4, while oxidizing conditions prevail around OW13. Are the elevated sulphate concentrations a leachate impact? Is there an RUG issue at the eastern property boundary?

- Future reports would benefit from the inclusion of a hydrogeologic cross section. This is a useful tool for the visualization of topography and stratigraphy, and the relationship between the location of the waste, observation wells and property boundaries.
- Are the lands to the east that are leased by the Township a part of a formal Contaminant Attenuation Zone?

The ministry's surface water review did not identify any concerns with the report.

If you have any questions concerning this letter, please contact the undersigned at (519) 371-6191.

Yours truly,



---

Ian Mitchell, P.Eng.  
District Engineer  
Owen Sound Area Office

File Storage Number: SI BR HK C6 610

cc. David Hopkins - Burnside & Associates, Guelph  
Mark Harris/Scott Abernethy - MOE, London  
Helmut Pfeiffer - MOE, Owen Sound



**Ministry of the Environment and  
Climate Change**  
Southwestern Region  
Owen Sound District Office  
3rd Flr  
101 17th St  
Owen Sound ON N4K 0A5  
Fax: (519) 371-2905  
Tel: (519) 371-6191

**Ministère de l'Environnement et de  
l'Action en matière de changement  
climatique**  
Direction régionale du Sud-Ouest  
Bureau du district d'Owen Sound  
101 rue 17th, 3ème étage  
Owen Sound ON N4K 0A5  
Télécopieur: (519) 371-2905  
Tél:(519) 371-6191



August 20, 2015

Mr. Hugh Nichol  
Township of Huron-Kinloss  
PO Box 130  
21 Queen Street  
Ripley, ON N0G 2R0

Dear Mr. Nichol,

**RE: Kinloss Landfill Site - 2014 Annual Report**

We have received a copy of the report titled "Annual Monitoring Report – 2014, Kinloss Landfill Site, Township of Huron-Kinloss" dated March 2015 and prepared by WSP Canada Inc. A copy of this report was forwarded to our Regional Technical Support Section and comments from our Regional Hydrogeologist are provided in the attached memorandum.

If you have any questions concerning the attached, please contact the undersigned at (519) 371-6191.

Yours truly,

A handwritten signature in black ink that reads "Ian Mitchell". The signature is written in a cursive style and is positioned above a horizontal line.

Ian Mitchell, P.Eng.  
District Engineer  
Owen Sound District Office

File Storage Number: SI BR HK C6 610

enclosure

cc. Simon Thuss, MOECC, London  
Neil McLean, WSP, Owen Sound  
Natasha Munn, MOECC, Owen Sound

Ministry of the Environment  
and Climate Change

733 Exeter Road  
London ON N6E 1L3  
Tel: 519 873-5000  
Fax: 519 873-5020

Ministère de l'Environnement  
et de l'Action en matière de  
changement climatique

733, rue Exeter  
London ON N6E 1L3  
Tél.: 519 873-5000  
Fax: 519 873-5020



---

## MEMORANDUM

File No. SI BR HK C8 610

TO: Ian Mitchell  
District Engineer  
Owen Sound District

FROM: Simon Thuss  
Hydrogeologist  
Water Resources Unit – Technical Support Section

DATE: August 14, 2015

RE: Annual Monitoring Report - 2014  
Kinloss Landfill Site, Township of Huron-Kinloss  
IDS Reference No. 0481-9V5RQD

---

As requested, I have reviewed the following report:

- "Annual Monitoring Report – 2014, Kinloss Landfill Site, Township of Huron-Kinloss" dated March 2015 and prepared by WSP Canada Inc.

The review was limited to the hydrogeological aspects of the landfill monitoring program as presented in the report.

The landfill site is situated on the south half of Lot 16, Concession 6 in the former Township of Kinloss, now within the amalgamated Township of Huron-Kinloss. The landfill site is operated under Provisional Certificate of Approval (C of A) No. A272801, most recently amended in April 2003. It is understood that the acceptance of household waste was discontinued in 2002; however, the site has not been permanently closed. Currently, only recyclable and burnable materials are collected at the site.

The current monitoring network includes eleven monitoring wells and two surface water monitoring stations. Groundwater level monitoring and sample collection is carried out twice per year (typically July and October).

The stratigraphy at the site generally consists of surficial sand or sand and gravel (up to 16.5 metres in

thickness), overlying lower permeability silt till. The shallow groundwater flow within the surficial granular deposit is indicated to be towards the east.

Landfill leachate impacts are observed within the surficial granular deposit downgradient of the landfill at monitoring wells OW4, OW13S and OW13I. Samples collected from these locations are characterized by elevated concentrations of several leachate indicator parameters, including: alkalinity, hardness, chloride, sulphate, nitrate, ammonia, TKN, organic nitrogen, DOC, boron, sodium, iron and manganese.

A Reasonable Use assessment was completed using the measured concentrations of alkalinity, boron, chloride, DOC and sodium. Consistent with previous results, the alkalinity and DOC concentrations at the downgradient monitoring wells continue to exceed the corresponding Reasonable Use Guideline (RUG) criteria.

The Township holds a 99-year lease on a portion of the property to the east of the site for the purpose of establishing a buffer zone for contaminant attenuation; however, the C of A for the site has not been amended to formally recognize this area as a Contaminant Attenuation Zone (CAZ).

Upon completing the review of the 2014 report, the following comments are provided:

1. In a previous letter dated July 16, 2012, the Consultant indicated to the Ministry that the exceedances of the RUG criteria at the OW13 well nest were anticipated to be representative of a "slug" of leachate impacted groundwater flowing past the monitoring point. At that time, the Consultant proposed an additional three years of monitoring to evaluate the groundwater quality at the downgradient property boundary. Given the ongoing exceedances of the RUG criteria at this location, additional work should now be undertaken to delineate the leachate plume and confirm that the impacts are sufficiently attenuated within the buffer area. Ideally, this would be achieved through the installation of additional monitoring wells downgradient of the property boundary; however, it is understood that the area may not be readily accessible by drilling rig. The Consultant is encouraged to discuss the monitoring plan with the Ministry prior to proceeding with the work.
2. As illustrated on Map 3 in the report, the shallow groundwater flow direction is inferred to be towards the east; however, the map indicates that a "drainage divide" is present near the western limit of the landfilled area, suggesting that there may also be a component of groundwater flow to the west in this portion of the site. Consideration should be given to the installation of an additional monitoring well to the west of the fill area to characterize the groundwater quality and flow direction in this area.
3. Monitoring wells OW9 and OW11 are reported to be "inactive" and are not included in the

monitoring program. Based on the borehole logs included in the report, these wells were not installed to a sufficient depth to intersect the shallow groundwater table. Since these wells are not suitable for monitoring, they should be properly abandoned in accordance with Ontario Regulation 903.

4. Monitoring wells OW4 to OW11 were reportedly constructed with slotted ABS pipe installed in excavated test pits. There is some potential that precipitation and surface runoff may "short-circuit" to these wells since the permeability of the backfill would be enhanced relative to the undisturbed native deposits. As such, the groundwater chemistry observed at these locations may not fully represent the ambient shallow groundwater conditions at the site. The Consultant should comment on the integrity of these wells and any implications for the data collected at these locations. Consideration should be given to supplementing the existing monitoring network with properly constructed monitoring wells at key locations to confirm the groundwater conditions in the shallow overburden.
5. The report indicates that hardness, iron and manganese were excluded from the Reasonable Use assessment because the background concentrations of these parameters have typically been elevated relative to the corresponding Ontario Drinking Water Quality Standards (ODWQS). Although the background concentrations may be slightly elevated, the concentrations of these parameters increase significantly downgradient of the landfill and are considered to be representative of leachate impacts. For example, the iron concentration at downgradient well OW4 generally ranges from 10 to 20 mg/L, while the background concentration appears to be less than 1 mg/L. Appropriate RUG criteria for hardness, iron and manganese should be developed and included in the assessment for future reports.
6. Sulphate was not included in the Reasonable Use assessment as this parameter is reportedly present in elevated concentrations in background well OW6; however, a review of the historical data does not support this conclusion. The sulphate concentration in OW6 has ranged between approximately 10 and 26 mg/L over the period of record and appears to be representative of the background groundwater quality. In comparison, the sulphate concentration at downgradient wells OW13S and OW13I have ranged between 252 and 626 mg/L. As such, the elevated sulphate appears to be representative of leachate impacts and should be included in the Reasonable Use assessment going forward.
7. Ammonia appears to be elevated downgradient of the landfill, with concentrations ranging between 15 and 40 mg/L at OW4. Ammonia can be nitrified to produce nitrate and nitrite in aerobic environments. Historically, nitrate concentrations as high as 10 mg/L have been measured in samples collected from OW13S and OW13I, and low concentrations of nitrite have also been occasionally detected in samples from these locations. In comparison, nitrate and nitrite

are typically not detected in the background well OW6. The elevated nitrate and relatively low ammonia concentrations at OW13S / OW13I suggest that nitrification of ammonia is actively occurring in the leachate plume downgradient of the landfill. As such, nitrate and nitrite should also be included in the Reasonable Use assessment.

8. A review of the historical data for OW13S and OW13I suggests that the conditions within the plume at the southeast property boundary may be becoming more reducing over time. Since approximately 2011, the concentration of ammonia in these wells has followed an increasing trend, with a corresponding decrease in the concentrations of nitrate and sulphate. Future monitoring reports should include a discussion of these trends and include time series plots for all key leachate indicator parameters.
9. Several minor editorial errors were noted in the report. Figure 4 (Indicator Parameters – Fall) appears to be missing from the report, and the data for downgradient wells OW13S and OW13I was not included on Figure 3 (Indicator Parameters – Spring). Appendix C appears to be missing the borehole logs for OW13S, OW13I and OW13D.

If you have any questions or require clarification on any of the points provided herein, please contact me at [Simon.Thuss@ontario.ca](mailto:Simon.Thuss@ontario.ca) or 519-873-5033.

Yours truly,



Simon Thuss, P. Geo.  
Hydrogeologist  
Technical Support Section  
Southwestern Region

**Limitations:**

*The purpose of the preceding review is to provide advice to the Ministry of the Environment and Climate Change regarding subsurface conditions based on the information provided in the above referenced documents. The conclusions, opinions and recommendations of the reviewer are based on information provided by others, except where otherwise specifically noted. The Ministry cannot guarantee that the information that has been provided by others is accurate or complete. A lack of specific comment by the reviewer is not to be construed as endorsing the content or views expressed in the reviewed material.*



101-16945-00

October 8, 2015

Mr. Ian Mitchell, P. Eng., District Engineer  
Ministry of the Environment and Climate Change  
Owen Sound District Office  
Third Floor  
101 17<sup>th</sup> Street East  
OWEN SOUND, ON  
N4K 0A5

Re: MOECC Response to Kinloss Landfill Site – 2014 Annual Monitoring Report

Dear Mr. Mitchell:

The Township of Huron Kinloss (Township) has asked WSP Canada Ltd. (WSP) to form a response to the technical memorandum generated by Mr. Simon Thuss on August 14, 2015 regarding the Kinloss Landfill Site. The following nine (9) points are intended to be in response to the nine (9) points in Mr. Thuss' memorandum:

1. The continued presence of impacts at OW13S and OW13I suggest landfill impacted water may persist in this portion of the Site. WSP agrees with the Ministry of the Environment and Climate Change (MOECC) recommendation for installation of additional monitoring wells downgradient of the OW13 well nest. However, as the lands are within the leased buffer lands (Legal CON 6 PT LOT 17 PT LOT 18, comprising 43.5 ha or 107.5 ac owned by Barry Johnston), which act as a contaminant attenuation zone (CAZ), some discussion with the landowner may be required. The presence of the small tributary of Kinloss Creek and the high water table in the vicinity of the OW13 well nest are factors that must be taken into consideration. WSP recommends the installation of one (1) shallow (+/-6 m) monitoring well adjacent to the west side of the tributary, directly downgradient of the OW13 well nest. This monitoring well would be installed in order to investigate the groundwater adjacent to the tributary. WSP proposes one (1) additional shallow (+/-6 m) monitoring well be installed on the east side of the tributary. This well will serve as confirmation that leachate impacts to groundwater are not leaving the buffer lands, and will also allow refinement for increased interpretation of the groundwater contours and flow direction in the buffer lands. These two (2) monitoring wells will allow RUG compliance to be determined at the eastern boundary.

WSP Canada Inc.  
1450 - 1st Ave W,  
Suite 101  
Owen Sound ON N4K 6W2  
[www.wspgroup.com](http://www.wspgroup.com)



Drilling of the proposed monitoring wells within a wetland may pose access challenges requiring road construction and winter drilling to enable O. Reg. 903 to be complied with, regarding water around the casing. WSP proposes to scout suitable locations for the wells during the Fall 2015 monitoring event at the landfill.

2. The drainage divide represented in Maps of the Kinloss Waste Disposal Site is expected to impact overland surface water flow at the Site, but not significantly impact groundwater flow, which is predominantly to the east, and largely affected by the soil stratigraphy. Furthermore, the waste is landfilled downgradient (east) of this divide.
3. The Township will explore the option of deepening wells OW9 and OW11 to intersect the water table at these locations. This would further refine groundwater contours upgradient of the waste and provide insight into the possible impacts of the nearby run off water divide on the nearby flow direction of groundwater, as discussed by the MOECC in Comment 2.
4. WSP acknowledges that implementation of wells in test pits is not an ideal method of installation and may lead to biased sampling results. However, OW11-85 is one of the upgradient "dry" monitoring points. Effectively, it is unlikely that leachate will be able to impact this location. Further, the wells were installed in 1985. Ergo, it is reasonable to assume that they have established an equilibrium with the surrounding shallow aquifer. Effectively, WSP recommends retaining the shallow OW4-85, referenced by the MOECC in Comment 4, as is, in order to continue to evaluate the long term trend of groundwater down gradient of the waste without changing the well, which may alter the existing trend.

In addition, WSP inspects the wells during each field monitoring event. Any required maintenance or well conditions that are felt to not reflect actual groundwater conditions are reported and passed on to the Township. The Township then deals with these concerns within a reasonable time frame. WSP proposes to continue the field screening of well integrity in the future and continuation of this method of maintenance.

5. WSP acknowledges that iron, hardness and manganese are commonly used in defining leachate impacts. WSP will give further consideration to the inclusion of these parameters in future RUG guidelines.
6. WSP acknowledges that sulphate is commonly used in defining leachate impacts. WSP will give further consideration to the inclusion of this parameter in future RUG guidelines.

101-16945-00  
October 8, 2015  
Mr. Ian Mitchell, P.Eng., District Engineer



7. Ammonia may be nitrified to produce nitrate and nitrite in oxidizing environments. As noted by the MOECC in Comment 5, iron and manganese are elevated in the downgradient groundwater. The dissolved presence of iron and manganese parameters is only possible in reduced environments, albeit, this only typically occurs at a lower pH than observed in the field and laboratory sampling. Effectively, the groundwater environment downgradient of the landfill appears to be highly reduced.

WSP suspects that other factors may be affecting the concentration of nitrate at this location, and that mixing of oxidized and reduced groundwater may be occurring in this location. This statement formed a part of the reasoning behind the original suspicion of the leachate impacts at OW13S and OW13I being a slug moving through the down gradient area. WSP believes that further investigation should be conducted on this topic before acceptance of these parameters in the RUG.

8. WSP agrees with Comment 8 and suggests incorporation of our response for this comment with those of Comment 7.
9. Editorial comments noted.

Should you have any further questions or comments, please do not hesitate to contact the undersigned.

Yours truly,

WSP Canada Inc.

A handwritten signature in black ink that reads "Neil McLean".

Neil McLean, M.Sc., P. Geo.  
Geoscientist  
/nrm/dlw

cc Mr. Stephen Cobean, P.Eng., WSP Canada Inc.  
Mr. Hugh Nichol – Township of Huron Kinloss



**Ministry of the Environment and  
Climate Change**

Southwestern Region  
Owen Sound District Office  
3rd Flr  
101 17th St  
Owen Sound ON N4K 0A5  
Fax: (519) 371-2905  
Tel: (519) 371-8191

**Ministère de l'Environnement et de  
l'Action en matière de changement  
climatique**

Direction régionale du Sud-Ouest  
Bureau du district d'Owen Sound  
101 rue 17th, 3ème étage  
Owen Sound ON N4K 0A5  
Télécopieur: (519) 371-2905  
Tél:(519) 371-8191



August 16, 2016

Mr. Hugh Nichol  
Township of Huron-Kinloss  
PO Box 130  
21 Queen Street  
Ripley, ON N0G 2R0

Dear Mr. Nichol,

**RE: Kinloss Landfill Site - 2015 Annual Report**

We have received a copy of the report titled "Annual Monitoring Report – 2015, Kinloss Landfill Site, Township of Huron-Kinloss" dated March 2016 and prepared by WSP Canada Inc. A copy of this report was forwarded to our Regional Technical Support Section and comments from our Regional Hydrogeologist are provided in the attached memorandum.

If you have any questions concerning the attached, please contact the undersigned at (519) 371-6191.

Yours truly,

A handwritten signature in cursive script that reads "Ian Mitchell".

---

Ian Mitchell, P.Eng.  
District Engineer  
Owen Sound District Office

File Storage Number: SI BR HK C6 610

enclosure

cc. Simon Thuss, MOECC, London  
Neil McLean, WSP, Owen Sound  
Sierra Gillies, MOECC, Owen Sound

Ministry of the Environment  
and Climate Change

733 Exeter Road  
London ON N6E 1L3  
Tel: 519 873-5000  
Fax: 519 873-5020

Ministère de l'Environnement  
et de l'Action en matière de  
changement climatique

733, rue Exeter  
London ON N6E 1L3  
Tél.: 519 873-5000  
Fax: 519 873-5020



---

## MEMORANDUM


File No. SI BR HK C6 610

TO: Ian Mitchell  
District Engineer  
Owen Sound District

FROM: Simon Thuss  
Hydrogeologist  
Water Resources Unit – Technical Support Section

DATE: August 9, 2016

RE: Annual Monitoring Report - 2015  
Kinloss Landfill Site, Township of Huron-Kinloss  
IDS Reference No. 3866-A7VQEQ



---

As requested, I have reviewed the following report:

- "Annual Monitoring Report – 2015, Kinloss Landfill Site, Township of Huron-Kinloss" dated March 2016 and prepared by WSP Canada Inc.

The review was limited to the hydrogeological aspects of the landfill monitoring program as presented in the report.

The landfill site is situated on the south half of Lot 16, Concession 6 in the former Township of Kinloss, now within the amalgamated Township of Huron-Kinloss. The landfill site is operated under Provisional Certificate of Approval (C of A) No. A272801, most recently amended in April 2003. It is understood that the acceptance of household waste was discontinued in 2002; however, the site has not been permanently closed. Currently, only recyclable and burnable materials are collected at the site.

I previously reviewed the 2014 Annual Report for the Kinloss Landfill Site, with comments provided in a memorandum dated August 14, 2015. WSP Canada Inc. responded to these previous comments in a letter dated October 8, 2015.

In response to my previous comments, the Consultant has proposed to carry out some additional site

work in 2016. As detailed in the October 8, 2015 letter and the 2015 Annual Report, monitoring wells OW9 and OW11 will be deepened/replaced, facilitating better characterization of the background groundwater quality and the groundwater flow direction in the western portions of the site. In addition, two new monitoring wells will be installed downgradient of the OW13 well nest to evaluate groundwater quality within the leased buffer lands to the east of the site.

Consistent with data collected in previous years, in 2015 landfill leachate impacts were observed within the surficial granular deposit downgradient of the landfill at monitoring wells OW4, OW13S and OW13I. Samples collected from these locations are characterized by elevated concentrations (relative to background) of several leachate indicator parameters, including: alkalinity, hardness, chloride, sulphate, nitrate, ammonia, TKN, organic nitrogen, DOC, boron, sodium, iron and manganese.

A Reasonable Use assessment was completed using the measured concentrations of alkalinity, boron, chloride, DOC and iron. Consistent with previous results, concentrations of alkalinity (at OW13S and OW13I) and DOC (at OW13I spring 2015 only) continue to exceed the corresponding Reasonable Use Guideline (RUG) criteria.

Upon completing the review of the 2015 report, the following comments are provided:

1. In response to my previous comments, the Consultant re-evaluated the RUG criteria and added iron to the list of parameters used in the assessment for the 2015 annual report. I maintain my opinion that several other parameters (including at least hardness, manganese and sulphate) should also be included in the RUG assessment as these parameters are elevated in the downgradient wells and are thus indicative of leachate impacts at the Kinloss Landfill site.

For example, using the average background concentrations measured at OW6 between 2007 and 2015, the RUG criteria for hardness and sulphate would be approximately 285 and 133 mg/L, respectively. A RUG criterion of 0.23 mg/L for manganese could also be developed using the maximum background concentration observed at OW6 (May 2015).

Given these values, the current concentrations of hardness and sulphate at both OW13S and OW13I would exceed the RUG criteria (in addition to the exceedances of alkalinity and DOC identified by the Consultant). Though not considered a compliance point, samples from OW4 would also exceed the RUG criteria for alkalinity, DOC, hardness, iron and manganese. The inclusion of these additional parameters in the RUG assessment provides a more comprehensive evaluation of the leachate impacts to groundwater quality downgradient of the landfill.

All relevant indicator parameters (i.e. all parameters which are elevated above background concentrations within the leachate or downgradient of the landfill) should be included in the RUG

assessment for future monitoring reports. This will be of particular importance when evaluating the groundwater quality within the leased buffer lands to the east of the site.

2. The elevated concentrations of ammonia in samples from OW4 (typically >20 mg/L) and OW13S/OW13I (typically 0.5 to 3.5 mg/L) are indicative of leachate impacts. Although reducing conditions are anticipated within the leachate plume near OW4 and OW13, it is anticipated that the ammonia may be converted to nitrate where the plume mixes with more oxic groundwater downgradient of the site. Accordingly, my previous comments recommended that nitrate and nitrite should be included in the RUG assessment in future reports.

It is acknowledged that the RUG assessment may be complicated by the presence of organic nitrogen within the shallow aquifer. For example, elevated concentrations of organic nitrogen and TKN have been historically measured in samples from the background well OW6. However, concentrations of other nitrogen compounds (ammonia, nitrate, nitrite) are typically low at this location (<0.3 mg/L for ammonia, nitrate and nitrite not detected).

The use of nitrate and nitrite in the RUG assessment should be reconsidered once additional data is available to characterize groundwater quality upgradient and downgradient of the landfill (i.e. new wells to be installed in 2016).

3. The 2015 annual report suggests that groundwater quality appears to be improving at OW13S and OW13I since (aside from alkalinity), only DOC was identified above the RUG criteria in OW13I during the spring 2015 monitoring event. However, as detailed in the two comments above, this evaluation does not consider the other relevant leachate indicator parameters.

A review of the historical data suggests that the concentration of several leachate indicator parameters (primarily chloride, sulphate, hardness, alkalinity and conductivity) at OW13S and OW13I peaked in approximately 2007. The chloride concentration has since decreased significantly and is now starting to approach background concentrations. Although hardness, sulphate and conductivity have also followed a declining trend since approximately 2007, these parameters are still significantly elevated relative to background conditions. This data suggest that while there has been some improvement in groundwater quality at the OW13 well nest since 2007, this location remains impacted by leachate.

Future reports should include time-series plots for key indicator parameters (in addition to chloride) to further characterize any trends in groundwater quality at the site.

4. There appears to be two minor errors in the calculated RUG criteria as summarized in Table 4 of the 2015 annual report. Since boron is considered a "health-related" parameter, a constant of 0.26

should be used in the RUG calculation. Accordingly, given the average background concentration of 0.023 mg/L, and an ODWS IMAC of 5 mg/L, the RUG criterion for boron should be 1.27 mg/L.

The RUG criterion for iron (0.5 mg/L) is less than the average background concentration (0.7 mg/L). In cases where the background concentration exceeds the applicable ODWS, it is suggested that the RUG criterion be set at the maximum observed background concentration (1.4 mg/L for iron at OW8).

All RUG criteria should be re-evaluated once additional background data becomes available.

If you have any questions or require clarification on any of the points provided herein, please contact me at [Simon.Thuss@ontario.ca](mailto:Simon.Thuss@ontario.ca) or 519-873-5033.

Yours truly,



Simon Thuss, P.Geo.  
Hydrogeologist  
Technical Support Section  
Southwestern Region

**Limitations:**

*The purpose of the preceding review is to provide advice to the Ministry of the Environment and Climate Change regarding subsurface conditions based on the information provided in the above referenced documents. The conclusions, opinions and recommendations of the reviewer are based on information provided by others, except where otherwise specifically noted. The Ministry cannot guarantee that the information that has been provided by others is accurate or complete. A lack of specific comment by the reviewer is not to be construed as endorsing the content or views expressed in the reviewed material.*

**Ministry of the Environment,  
Conservation and Parks**  
Southwestern Region  
Owen Sound District Office  
3rd Flr  
101 17th St  
Owen Sound ON N4K 0A5  
Fax: (519) 371-2905  
Tel: (519) 371-6191

**Ministère de l'Environnement, de la  
Protection de la nature et des  
Parcs**  
Direction régionale du Sud-Ouest  
Bureau du district d'Owen Sound  
101 rue 17th, 3ème étage  
Owen Sound ON N4K 0A5  
Télécopieur: (519) 371-2905  
Tél:(519) 371-6191



RECEIVED

SEP 17 2018

September 13, 2018

Mr. Hugh Nicol  
Township of Huron-Kinloss  
PO Box 130  
21 Queen Street  
Ripley ON N0G 2R0

Dear Mr. Nicol,

**RE:** Kinloss Landfill 2017 Annual Report

We have received a copy of the report titled “Annual Monitoring Report (2017), Kinloss Landfill Site” dated March 2018 and prepared by WSP. Staff from our technical support section reviewed the above report, as well as the 2016 annual report, and our regional hydrogeologist provides the following comments on the hydrogeological aspects of the 2016 and 2017 annual reports. Our hydrogeologist attended the site on September 5, 2018, to supplement his understanding of the conditions on the site and surrounding area.

Consistent with data collected in previous years, the 2016/2017 data indicates leachate impacts within the surficial granular deposit downgradient of the landfill at monitoring wells OW4, OW13S and OW13I. Samples collected from these locations are characterized by elevated concentrations (relative to background) of several leachate indicator parameters, including: alkalinity, hardness, sulphate, nitrate, ammonia, TKN, DOC, boron, sodium, iron and manganese.

Based on data collected from the new downgradient monitoring wells, offsite leachate impacts appear to extend to at least OW15, with elevated concentrations of several leachate indicator parameters at this location. The groundwater chemistry observed at OW16 appears to be consistent with background conditions at the site. It is noted that the saturated organic soils in the area of OW15 and OW16 may influence the shallow groundwater chemistry for these wells (e.g. DOC, manganese).

Upon reviewing the 2016 and 2017 monitoring reports for the Kinloss landfill site, the following comments are provided:

1. In response to previous review comments, the Consultant has argued that it is “excessive” to include several parameters (including nitrate and nitrite) in the Reasonable Use Assessment. The Consultant has claimed that certain parameters (e.g. manganese and

sodium) are redundant since other parameters (iron and chloride) are already being evaluated. Based on this response, it appears that there may be some misunderstanding regarding the purpose of the Reasonable Use assessment. The Reasonable Use assessment is not intended as a simple test to identify the presence or absence of leachate in groundwater. The Reasonable Use Guideline establishes procedures for determining what constitutes the reasonable use of groundwater on property adjacent to sources of contaminants, and establishes limits on the discharge of contaminants from landfill sites and other waste disposal facilities. Given the many factors that can affect the geochemical conditions within the leachate plume (e.g. heterogeneous distribution of waste, weathering/decomposition of waste over time, changing redox conditions over time and/or distance along the plume), the critical contaminants with respect to Reasonable Use may vary by time and monitoring location at a given site.

For these reasons, the Reasonable Use assessment should consider all contaminants that potentially originate from the landfill site. In general, the standard practice used at other similar landfill sites is to develop Reasonable Use criteria for all parameters that have corresponding drinking water standards. In completing the assessment, consideration is given to other sources of contamination that may affect specific monitoring locations (e.g. road salt impacts adjacent to roadways).

If the Consultant requires additional guidance on this issue, a teleconference or meeting can be scheduled to discuss these concerns.

2. Specific to nitrate and nitrite, the Consultant believes that these parameters should not be included in the Reasonable Use Assessment “due to the typical lack of these parameters in reducing groundwater conditions, typically associated with leachate impacted groundwater”.

It is our hydrogeologist’s opinion, as previously stated, that elevated concentrations of ammonia have been observed downgradient of the landfill, and that ammonia may potentially be nitrified to produce nitrate and nitrite as the plume mixes with more oxidic groundwater downgradient of the site. Accordingly, nitrate and nitrite should be included in the Reasonable Use assessment. It is acknowledged that nearby sources (e.g. agricultural activities or decomposition of organic nitrogen) may also contribute to nitrate in groundwater.

3. There appears to be a calculation error in the Reasonable Use criterion for hardness. As shown in Table 4, the Reasonable Use criterion for hardness (248 mg/L) is less than the background concentration measured at OW11-16 (396 mg/L). In cases where the background concentration exceeds the applicable drinking water standard, it is suggested that the Reasonable Use criterion be set at the maximum observed background concentration.
4. The report should include an updated east-west cross-section, including the new wells OW11-16, OW15 and OW16. The cross-section should include the interpreted stratigraphy, limits of the waste, and current groundwater levels.

5. The ECA should be amended to formally recognize the leased buffer lands as a Contaminant Attenuation Zone for the site.
6. As previously recommended, the report should include time series plots for several key indicator parameters (in addition to chloride). The purpose of these plots is to further characterize any groundwater quality trends at the site.

Please contact me at (519) 371-6191, if you would like to arrange a teleconference to discuss the above comments or if you have any questions concerning this letter.

Yours truly,



---

Ian Mitchell, P.Eng.  
District Engineer  
Owen Sound District Office

File Storage Number: SI BR HK C6 610

cc. Natasha Munn, MECP Owen Sound  
Simon Thuss, MECP London  
Norm Bell, WSP, Owen Sound



Ministry of the Environment,  
Conservation and Parks  
Southwestern Region  
Owen Sound District Office  
3rd Flr  
101 17th St  
Owen Sound ON N4K 0A5  
Fax: (519) 371-2905  
Tel: (519) 371-6191

Ministère de l'Environnement, de la  
Protection de la nature et des  
Parcs  
Direction régionale du Sud-Ouest  
Bureau du district d'Owen Sound  
101 rue 17th, 3ème étage  
Owen Sound ON N4K 0A5  
Télécopieur: (519) 371-2905  
Tél:(519) 371-6191



RECEIVED

OCT 17 2018

October 2, 2018

Mr. John Yungblut  
Township of Huron-Kinloss  
PO Box 130  
21 Queen Street  
Ripley ON N0G 2R0

Dear Mr. Yungblut

**RE: Kinloss Landfill 2017 Annual Report**

Further to my letter to the municipality dated September 13, 2018, containing groundwater comments for the Kinloss Landfill Site 2017 Annual Monitoring Report, our regional surface water specialist has reviewed the annual report and provides the following comments:

This site is currently mothballed. The site is currently capped and the landfill has not accepted waste since August 2002. Only recyclables are collected and transferred from the site (page 2). Surface water sampling is completed in spring and fall from two sites (upstream and downstream) from a creek running adjacent to the landfill.

Page 13 of the report notes that only zinc exceeded the PWQO in the downstream (SW2) location. A subsequent duplicate was collected and it was determined that upstream (SW1) also exceeded the PWQO for zinc.

All sampled parameters remain within historical norms (Appendix G.2); accordingly there are no surface water issues associated with the site.

No changes are recommended to the surface water monitoring program for 2018 (page 18). Our surface water reviewer has no additional comments.

If you have any questions concerning this letter, please contact me at (519) 371-6191.

Yours truly,

A handwritten signature in black ink that reads "Ian Mitchell".

---

Ian Mitchell, P.Eng.  
District Engineer  
Owen Sound District Office

File Storage Number: SI BR HK C6 610

cc. Natasha Munn, MECP Owen Sound  
Hugh Geurts, MECP London  
Norm Bell, WSP, Owen Sound



December 13, 2018

Mr. Ian Mitchell, District Engineer  
Ministry of the Environment, Conservation and Parks  
101 17th Street East  
3rd Floor  
OWEN SOUND, ON  
N4K 0A5

**Subject: Response to MECP Comments on 2017 Annual Monitoring Report - Kinloss Landfill**

Dear Mr. Mitchell:

Thank you for providing WSP Canada Inc. (WSP) with the opportunity to review the comments prepared by the Ontario Ministry of the Environment, Conservation and Parks (MECP) (Southwestern Region) on September 13, 2018 following their hydrogeologist's review of the 2017 Annual Monitoring Report (2017 AMR), Kinloss Landfill Site (Site), dated March 2018 as prepared by WSP. WSP has also received comments from MECP dated October 2, 2018 relating to the surface water monitoring.

WSP have reviewed the September 13, 2018 comments (repeated below in italics) and have prepared the following responses for your consideration. These responses may influence the scope of work required by WSP to address these comments to the satisfaction of the MECP. No comments are required with respect to the October 2, 2018 letter.

In preparing our response to the September 13, 2018 comments, WSP reviewed the content of the 2017 AMR and consulted our team responsible for landfill monitoring in other jurisdictions. We have proposed a solution to become more consistent with the MECP expectations and to provide more clarity with respect to the task of monitoring to identify potential impacts related to the inactive landfill. In addition to a response to each comment, WSP has prepared a concise list of recommended actions to be followed for the preparation of the 2018 AMR, pending direction from the Township of Huron-Kinloss (Township) and agreement from MECP (where appropriate).

- 1 In response to previous comments, the consultant has argued that it is "excessive" to include several parameters (including nitrate and nitrite) in the Reasonable Use Assessment. The Consultant has claimed that certain parameters (e.g. manganese and sodium) are redundant since other parameters (iron and chloride) are already being evaluated. Based on this response, it appears that there may be some misunderstanding regarding the purpose of the Reasonable Use assessment. The Reasonable Use assessment is not intended as a simple test to identify the presence or absence of leachate in groundwater. The Reasonable Use Guideline establishes procedures for determining what constitutes the reasonable use of groundwater on property adjacent to sources of contaminants, and establishes limits on the discharge of contaminants from landfill sites and other waste disposal facilities. Given the many factors within the leachate plume (e.g. heterogeneous distribution of waste, weathering/decomposition of waste over time, changing*

Suite 101  
1450, 1st Avenue West  
Owen Sound, ON, Canada N4K 6W2

T: +1 519 376-7612  
F: +1 519 376-8008  
wsp.com



*redox conditions over time and/or distance along the plume), the critical contaminants with respect to Reasonable Use may vary by time and monitoring location at a given site.*

*For these reasons the Reasonable Use assessment should consider all contaminants that potentially originate from the landfill site. In general, the standard practice used at other similar landfill sites is to develop Reasonable Use criteria for all parameters that have corresponding drinking water standards. In completing the assessment, consideration is given to other sources of contamination that may affect specific monitoring locations (e.g. road salt impacts adjacent to roadways).*

*If the Consultant requires additional guidance on this issue, a teleconference or meeting can be scheduled to discuss these concerns.*

WSP understands the purpose of the Reasonable Use Assessment process. It is our experience that there is some flexibility in the application of this approach between MECP jurisdictions. The approach followed at this site has been based on observations that this is an inactive landfill site where the impacts from ongoing generation of landfill leachate appear to be reducing naturally (see discussion in response to point 6) and the interest of our client to work to minimize efforts related to ongoing monitoring and reporting associated with inactive landfills.

Review of the available monitoring data indicates that the current monitoring program includes the following parameters that have an Ontario Drinking Water Quality Standard (ODWQS) value:

- Alkalinity
- Chloride
- Nitrate\*
- Nitrite\*
- Organic Nitrogen\*
- Dissolved Organic Carbon
- Sulphate
- Hardness
- Aluminium\*
- Barium\*
- Boron
- Cadmium\*
- Chromium\*
- Copper\*
- Iron
- Lead\*
- Manganese
- Sodium\*; and
- Zinc\*.

In response to the MECP comment, WSP proposes to calculate Reasonable Use Criteria (RUC) for this entire suite of parameters based on the concentrations measured at background well (OW11-16). Parameters marked with an asterisk are not currently included in the evaluation of reasonable use criteria (Tables 4 and 4A). Note that the observed concentrations of many of the metals parameters are less than the method detection limits.

*Specific to nitrate and nitrite, the Consultant believes that these parameters should not be included in the Reasonable Use Assessment “due to the typical lack of these parameters in reducing groundwater conditions, typically associated with leachate impacted groundwater.*



*It is our hydrogeologist's opinion, as previously stated, that elevated concentrations of ammonia have been identified downgradient of the landfill and that ammonia may potentially be nitrified to produce nitrate and nitrite as the plume mixes with more oxic groundwater downgradient of the site. Accordingly, nitrate and nitrite should be included in the Reasonable Use assessment. It is acknowledged that nearby sources of agricultural activities or decomposition of organic nitrogen may also contribute to nitrate in groundwater.*

WSP agrees that RUC values are to be calculated for nitrate and nitrite as there is a drinking water quality objective for these values. WSP has consulted our team involved in landfill monitoring across Ontario and have found that a variety of approaches are used to monitor nitrogen transformations in areas where there is anaerobic water in which ammonia is the stable form of nitrogen species (and where nitrate and nitrite are typically absent). As there is no drinking water standard available for ammonia, WSP proposes to use the RUC calculated for nitrate (as N) to identify situations when concentrations of ammonia (as N) have potential to transform to nitrate. This approach may show some historical circumstances where elevated ammonia concentrations have been elevated relative to the RUC value, but overall recent samples are likely to comply. WSP would like to have confirmation from MECP that this approach will be acceptable.

- 2 There appears to be a calculation error in the Reasonable Use criterion for hardness. As shown in Table 4, the Reasonable Use criterion for hardness (248 mg/L) is less than the background concentration measured at OW11-16 (396 mg/L). In cases where the background concentration exceeds the applicable drinking water standard, it is suggested that the Reasonable Use criterion be set at the maximum observed background concentration.*

WSP has reviewed Tables 4 and 4A in the 2017 AMR and have observed that some of the RUC reported in the 2017 AMR are in error.

Firstly, the method employed by WSP to calculate the RUC for Hardness as presented in Table 4 is based on the average parameter values observed at OW6 between 2007 and 2015. The value for Hardness shown in Table 4 was obtained using the formula provided in the guidance is 179 mg/L. This value does not reflect the direction that a maximum background value is to be used when background concentrations are greater than the ODWQS value. Note that the background concentrations were considered for some parameters (eg. Iron and manganese).

To be correct in terms of the MECP comment provided above, this value is to reflect the maximum hardness value observed, which would be 284 mg/L. The RUC values for hardness presented in Table 4 have not been updated to reflect monitoring data obtained since 2016 and have consistently used the calculated value for hardness and not the maximum value.

Secondly, Table 4A in the 2017 AMR presents the RUC calculated using OW11-16 as the background monitor and this table shows a RUC for Hardness of 248 mg/L. This RUC value was calculated using the formula provided in the guidance, and does not reflect the maximum background value. Use of the maximum value observed at OW11-16 would increase the RUC value to 296 mg/L and would reduce the number of occurrences of an exceedance of the RUC in the monitoring. Hardness continues to be elevated in the monitoring wells downgradient of the landfill.

Review of the chloride concentrations for OW11-16 indicates that this well can reasonably be considered as reflecting background water quality, however the hardness values are elevated relative to OW5, OW6, OW7, OW13-D (most events); and OW16. Hardness values appear to be elevated at wells where landfill leachate is present.

Table 4 has continued to be used to present reasonable use values based on OW6 as background as there is a longer data record available for OW6 relative to OW11-16. This practice is explained in the



2017 AMR. WSP understands that OW11-16 was installed with the expectation that this would be used in the future as the background well once sufficient data is available (three years).

WSP proposes that for the 2018 report, that the reasonable use calculations be updated to reflect use of OW11 as the background well and to ensure that the calculation consistently reflects the practice of assuming the maximum value when the background value is higher than the drinking water quality objective. This is a reasonable approach for Hardness in Ontario, as most groundwater has hardness values that are greater than the range for the ODWQS.

In review of the RUC calculations, WSP also noted that the RUC for Manganese in Table 4 did not reflect that background concentrations at OW6 were greater than the ODWQS. The corrected value for the RUC is 0.23 mg/L.

- 3 The report should include an updated east-west cross-section, including the new wells OW11-15, OW15 and OW16. The cross-section should include the interpreted stratigraphy, limits of the waste, and current groundwater levels.*

The current cross-section was prepared by a previous consultant, prior to the installation of OW11-15, OW15 and OW16. WSP agrees that this section line can be updated to reflect new data along an “approximate flowpath” from OW11-16 through OW14, OW4, OW13 (3 levels), OW15 and OW16. WSP also recommends including the surface water feature on the cross-section to better reflect the groundwater flow path.

Although WSP agrees that this section line can be updated, we do not believe that presentation of this section line will change the understanding of conditions, although it will more clearly illustrate the current distribution of monitoring points along the primary groundwater flowpath beneath and downgradient of the landfill and discharge relationships to the stream.

- 4 The ECA should be amended to formally recognize the leased buffer lands as a Contaminant Attenuation Zone for the site.*

WSP notes that this landfill is currently operating under amended Certificate of Approval No. A272901. WSP agrees that it is appropriate to update the amended Certificate of Approval No. A272901 for this site to an Environmental Compliance Approval (ECA) to recognize the leased buffer lands as a Contaminant Attenuation Zone (CAZ). Assistance from MECP is requested to ensure that the Township understands the technical effort, including costs to negotiate with MECP, associated with submitting the request to update the Certificate of Approval to an ECA.

- 5 As previously recommended, the report should include time series plots for several key indicator parameters (in addition to chloride). The purpose of these plots is to further characterize any groundwater quality trends at the site.*

The trend plots presented for chloride illustrate an interesting trend for the conservative contaminant parameters associated with landfill leachate. Chloride concentrations show that a pulse of elevated concentrations passed OW4 between 2000 and 2010. Since 2010, the chloride concentrations at this location have remained low. A similar pulse has been observed to pass through other monitoring locations (OW14 – 2003-2007; OW13D – 2013; OW13-I – 2004-2014 (although tail continues to 2017)). These data show that the highest concentrations at downgradient monitors is substantially lower than was observed at OW4-85. These trends are consistent with what would be expected from a landfill that closed in 2002.

This type of trend indicates that the primary release of contaminants from this source occurred as a pulse that is now reflected by concentrations that are less elevated relative to background than the original.



With this as the typical behaviour shown for a conservative parameter from the landfill, a non-conservative parameter would be expected to behave in one of two ways:

- 1 Follow a similar trend of a pulse passing through with a lower peak concentration and a shorter time (due to degradation/transformation). Peak concentrations would be observed at distances further downgradient along the flowpath.
- 2 For a parameter that is stable in anoxic conditions within a landfill leachate, the above trend could be accompanied by an increase in concentrations of the oxygenated species (for example ammonia would transform to nitrate/nitrite; sulphide would transform to sulphate). Typically, the profile of the second species would also form a pulse (potentially with a longer tail).

WSP agrees that there may be benefit in revisiting the presentation of trend plots, to confirm that these “pulse trends” are occurring and that there are no trends of increasing parameter concentrations in a downgradient well. The current trend plots (Figure 4) do not clearly show the pulses, nor allow the reader to distinguish trends at different spots along the flow path.

WSP proposes to replace the current trend plot in Figure 4 (Chloride vs time) with additional trend plots for select parameters along a profile that corresponds to the primary flow path through the site. This flowpath would be defined by OW11-16 (upgradient) OW14; OW4; OW13-I; OW15 and OW16. Concentration trend plots for selected parameter would be plotted on an individual graph and presented on a single page for these six monitors. A page would be prepared for the following parameters: Chloride, Boron, Barium, Sulphate, Ammonia, Nitrate, and DOC. WSP has prepared this list based on the list of indicator parameters and the suitability of these parameters to reflect the presence of potential contaminants in both an anaerobic or aerobic groundwater state and a range of solute velocities in groundwater. Other parameters can be plotted in the event that evidence of an increasing trend is observed at a downgradient monitor. The graph scales will be selected to be consistent for the available monitoring record and for the observed concentration range of each parameter.

## RECOMMENDED ACTIONS

Pending authorization from the Township of Huron-Kinloss and agreement of MECP, WSP proposes to consider incorporating the following changes in the 2018 AMR.

- 1 Prepare updated RUC calculations for all parameters with a drinking water standard. The complete list of parameters is presented in response to comment 1. A Reasonable Use criterion value for ammonia (as N) will be developed based on the Nitrate (as N) concentration and ODWQS to reflect the potential risks associated with transformation of ammonia to nitrate. Updated RUC calculations will reflect average background concentrations at OW11-16 and, where background values are higher than the drinking water quality objective, the maximum value observed at OW11-16. The RUC will be updated in each annual report as new background values are calculated each year. These values are expected to be relatively stable moving forward as a longer data record is available for OW11-16. Moving forward, Table 4A will replace Table 4.
- 2 Prepare an updated plan and cross-section along the groundwater flow path as requested by MECP. This updated section will illustrate the new wells and will include the surface water course. This drawing will need to be regenerated as the current drawing was prepared by others and has not been updated regularly.
- 3 Initiate the process to amend the ECA to formally recognize the leased buffer lands as a Contaminant Attenuation Zone for the site.
- 4 Replace Figure 4 with a series of trend plots to illustrate parameter concentration changes over time at key points in the groundwater flow path for a series of parameters that are associated with the landfill leachate. Plots would be prepared to illustrate parameter concentration trends for:



OW11-16 (upgradient) OW14; OW4; OW13-I; OW15 and OW16 in separate graphs presented on a single page. Graphs would be prepared for the following parameters that reflect the presence of landfill impacts: Chloride; Boron, Barium, Sulphate; Ammonia; Nitrate; and DOC. Plots on each page will be prepared with consistent time scales and concentration scales to illustrate the changes in concentration along the flow path over time. Review of this figure will focus on identifying potential presence of increasing parameter trends, particularly in locations downgradient of the landfill. When increasing trends are observed, WSP shall review data for other parameters and prepare additional trend plots.

- 5 WSP believes that these updated concentration trend plots will effectively replace the current bar graphs presented as Figure 3 as well as Figure 4, and request that MECP provide direction that the current Figure 3 may also be removed/replaced.

WSP will be pleased to provide the Township with a fee estimate to reflect the additional effort required to address the MECP concerns and update the 2018 reports in accordance with these recommendations upon agreement to the proposed changes by MECP and to prepare the ECA amendment.

Please feel free to contact us to discuss these comments.

Yours truly,

Norman A. Bell, P.Geol.  
Senior Hydrogeologist / Project Geoscientist

Lloyd A. Lemon, M.Sc., P.Geol.  
Senior Project Geoscientist, Team Lead -  
Environmental Management

LAL/NAB

cc: Mr. John Yungblut, Township of Huron-Kinloss  
Ms. Natasha Munn, MECP  
Mr. Simon Thuss, MECP

WSP ref.: 121-60018-11

G:\2010\OS\401 - Environment\101-16945-00 - Kinloss WDS\Reports\Monitoring 2017\Response to MECP Comments\20181213\_N Bell\_L  
Lemon\_Response to MECP Comments on 2017 AMR - Kinloss Landfill\_Letter.pdf.docx



Ministry of the Environment,  
Conservation & Parks  
Owen Sound District Office

101 17<sup>th</sup> Street East, 3<sup>rd</sup> Floor  
Owen Sound ON N4K 0A5  
Tel.: 519-371-2901  
Fax.: 519-371-2905

Ministère de l'Environnement, de la Protection de  
la nature et des Parcs  
Bureau de district d'Owen Sound

101 17<sup>ème</sup> rue Est, 3<sup>e</sup> étage  
Owen Sound ON N4K 0A5  
Tél. : 519-371-2901  
Télééc. : 519-371-2905



November 30, 2020

Mr. John Yungblut  
Township of Huron-Kinloss  
PO Box 130  
21 Queen Street  
Ripley ON N0G 2R0

Via email: [jyungblut@huronkinloss.com](mailto:jyungblut@huronkinloss.com)

Dear Mr. Yungblut,

Re: Kinloss Landfill 2019 Annual Report  
MOE File: SI BR HK C6 610

We have received a copy of the report titled “2019 Annual Monitoring Report, Kinloss Landfill Site”, dated July 2020, and prepared by WSP. A copy of this report was forwarded to our Regional Technical Support Section for review. Our Regional Hydrogeologist reviewed the report and provides the following comments limited to the hydrogeological aspects of the landfill monitoring program as presented in the 2019 report.

The results of the 2019 groundwater monitoring program were generally consistent with data collected in previous years. Leachate impacts are observed in monitoring wells downgradient of the landfill, including OW4, OW13S, OW13I and OW15. Samples collected from these locations are characterized by elevated concentrations of several leachate indicator parameters in excess of the Reasonable Use Guideline (RUG) criteria, including alkalinity, hardness, iron, DOC and manganese. Iron, DOC, and manganese are also slightly elevated at several upgradient or cross-gradient locations, indicating that there is some natural variability in the background concentration of these parameters. Samples collected at OW16 continue to return results similar to background groundwater quality, indicating that the leachate plume is sufficiently attenuated on the downgradient property.

Upon reviewing the 2019 monitoring reports for the Kinloss landfill site, the following comments are provided:

1. Section 3.5 of the report argues that it is “excessive” to include several parameters (including nitrate and nitrite) in the Reasonable Use Assessment. However, as detailed in the December 13, 2018 letter from WSP, the consultant has previously agreed to include these parameters in the assessment. As mentioned previously, if the Consultant requires additional guidance on this issue, it is recommended that a teleconference be scheduled to discuss these concerns.

2. As detailed in the December 13, 2018 letter from WSP, the consultant has proposed to use the RUG criterion for nitrate (as N) to set a compliance limit for the concentration of ammonia at the boundary well locations. It is suggested that that a compliance criterion for ammonia is not needed at this time, provided that the downgradient ammonia concentration remains low and nitrate and nitrite are included in the RUG assessment going forward.

In the letter dated December 13, 2018, from WSP, they acknowledged that the ECA should be amended to formally recognize the CAZ on the leased lands located to the east of the site. Could you please provide an update on the status of the ECA amendment application to recognize the leased buffer lands as CAZ.

If you have any questions concerning this letter or the attached memo, please contact me at (519) 374-1388.

Sincerely,



Ian Mitchell  
District Engineer  
Owen Sound District

cc. Stephen Taziar, WSP Owen Sound, [Stephen.Taziar@wsp.com](mailto:Stephen.Taziar@wsp.com)  
Lisa Hines, MECP, Owen Sound  
Simon Thuss, MECP, London

Ministry of the Environment,  
Conservation & Parks  
Owen Sound District Office

101 17<sup>th</sup> Street East, 3<sup>rd</sup> Floor  
Owen Sound ON N4K 0A5  
Tel.: 519-371-2901  
Fax.: 519-371-2905

Ministère de l'Environnement, de la Protection de  
la nature et des Parcs  
Bureau de district d'Owen Sound

101 17<sup>ème</sup> rue Est, 3<sup>e</sup> étage  
Owen Sound ON N4K 0A5  
Tél. : 519-371-2901  
Télééc. : 519-371-2905



December 4, 2020

Mr. John Yungblut  
Township of Huron-Kinloss  
PO Box 130  
21 Queen Street  
Ripley ON N0G 2R0

Via email: [jyungblut@huronkinloss.com](mailto:jyungblut@huronkinloss.com)

Dear Mr. Yungblut,

Re: Kinloss Landfill 2019 Annual Report  
MOE File: SI BR HK C6 610

Further to my letter to you dated November 30, 2020, containing groundwater comments for the Kinloss Landfill Site 2019 Monitoring Report, our regional surface water specialist has reviewed the 2019 annual report.

During 2019 monitoring year, surface water samples were collected on June 12 and November 20 from SW1 and SW2 locations. The samples were analyzed for field parameters, general chemistry, nutrients and selected metals. The following is a summary of analytical results:

- The PWQO for aluminum exceeded in both SW1 and SW2 samples collected on June 12, 2019.
- The PWQO for iron also exceeded in SW1 sample collected on November 20, 2019.
- Other water quality parameters were measured below PWQO, where available.

Our surface water reviewer has the following comments based the 2019 surface water monitoring data for the Kinloss Landfill Site:

1. Measured concentrations of aluminum and iron in 2019 samples were slightly higher than their concentrations reported for past monitoring events. Since levels higher than PWQO were also measured in samples collected from the upstream location, no action is required at this time.
2. In general, water quality measured at both, upstream and downstream, surface water monitoring locations is similar and therefore suggest that the landfill Site does not have significant adverse effects on the Creek's water quality.
3. It is agreed that surface water monitoring should continue as per the requirements of the current ECA.

If you have any questions concerning this letter, please contact me at (519) 374-1388.

Sincerely,

A handwritten signature in cursive script that reads "Ian Mitchell".

Ian Mitchell  
District Engineer  
Owen Sound District

cc. Stephen Taziar, WSP Owen Sound, [Stephen.Taziar@wsp.com](mailto:Stephen.Taziar@wsp.com)  
Lisa Hines, MECP, Owen Sound  
Nilima Gandhi, MECP, London



Kinloss Landfill

## Inspection Report

System Number:  
Inspection Start Date: 11/18/2021  
Inspection End Date: 12/02/2021  
Inspected By: Ian Mitchell  
Badge #: 701

A handwritten signature in black ink that reads "Ian Mitchell".

---

(signature)

**NON-COMPLIANCE/NON-CONFORMANCE ITEMS**

The following item(s) have been identified as non-compliance/non-conformance, based on a "No" response captured for a legislative or best management practice (BMP) question (s), respectively.

**Question Group: Other Inspection Findings**

<b>Question ID</b>	949100	
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>
Were the inspection questions sufficient to address other identified non-compliance items?	Legislative	Not Applicable
<b>Observation/Corrective Action(s)</b>		
The following instances of non-compliance were also noted during the inspection: The Environmental Compliance Approval should reflect the current status of the site. In this case the site is temporarily closed. The ECA does not reflect this situation and needs to be amended. It appears this amendment requirement was missed when the site changed operational status a number of years ago.		

**Question Group: Records / Reports**

<b>Question ID</b>	OOL 45	
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>
Has the Certificate of Requirement been registered on Title?	Legislative	EPA   27   (1)
<b>Observation/Corrective Action(s)</b>		
No Appendix H of the 2020 annual report documents there is a registration on title of a lease which appears to be for buffer lands. Documentation confirming the actual landfill site is registered on title could not be located in the Ministry's file. The Township should ensure that the landfill Site is registered on title. The Township should provide confirmation in writing that the Site is registered on title, including a copy of the Certificate of Prohibition by December 31, 2021. If the actual site is not registered on title, then this will need to be done.		

### INSPECTION DETAILS

This section includes all questions that were assessed during the inspection.

**Ministry Program: Regulated Activity:** WASTE : Landfills

<b>Question ID</b>	OOL 1	
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>
Does the Open landfill site have an Environmental Compliance Approval (ECA)?	Legislative	EPA   27   (1)
<b>Observation</b>		
Yes Certificate of Approval A272801 dated October 1, 1980 and amended in 1993 for submission of annual report. The ECA was also amended 1996 requiring groundwater and surface water monitoring.		

<b>Question ID</b>	OOL 5	
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>
Is the landfill required to take and test monitoring well samples to determine the quality of the ground water?	Information	Not Applicable
<b>Observation</b>		
Yes		

<b>Question ID</b>	OOL 6	
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>
Are monitoring well samples taken and tested to determine the quality of the groundwater?	Legislative	EPA   27   (1), EPA   R.R.O. 1990, Reg. 347   11   (7)
<b>Observation</b>		
Yes		

<b>Question ID</b>	OOL 7	
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>
Is the ministry satisfied with the groundwater monitoring program at the site?	Legislative	EPA   27   (1), EPA   R.R.O. 1990, Reg. 347   11   (7)
<b>Observation</b>		
Yes		

--

<b>Question ID</b>	OOL 10		
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>	
Are measures taken to manage leachate to prevent off-site contamination?	Legislative	EPA   27   (1), EPA   R.R.O. 1990, Reg. 347   11   (7)	
<b>Observation</b>			
Yes 30 acres of buffer lands to the east allow for leachate attenuation. The agreement to allow these lands to be used for contamination attenuation (99 year lease) was registered on title by instrument # 264927, dated February 28, 1990.			

<b>Question ID</b>	OOL 12		
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>	
Is the landfill required to manage landfill gas generated at the site?	Information	Not Applicable	
<b>Observation</b>			
Yes There are three gas monitoring probes on site			

<b>Question ID</b>	OOL 34		
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>	
Has an annual operations report been submitted?	Legislative	EPA   27   (1)	
<b>Observation</b>			
Yes The 2020 Annual Monitoring report was submitted on July 7, 2021			

<b>Question ID</b>	OOL 35		
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>	
Is the ministry satisfied with the annual report submitted?	Legislative	EPA   27   (1)	
<b>Observation</b>			
Yes			

<b>Question ID</b>	OOL 37		
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>	
Is there an ECA condition requiring financial assurance?	Information	Not Applicable	
<b>Observation</b>			
No			



--

<b>Question ID</b>	OOL 45	
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>
Has the Certificate of Requirement been registered on Title?	Legislative	EPA   27   (1)
<b>Observation</b>		
<p>No Appendix H of the 2020 annual report documents there is a registration on title of a lease which appears to be for buffer lands. Documentation confirming the actual landfill site is registered on title could not be located in the Ministry's file. The Township should ensure that the landfill Site is registered on title. The Township should provide confirmation in writing that the Site is registered on title, including a copy of the Certificate of Prohibition by December 31, 2021. If the actual site is not registered on title, then this will need to be done.</p>		

<b>Question ID</b>	949100	
<b>Question</b>	<b>Question Type</b>	<b>Legislative Requirement</b>
Were the inspection questions sufficient to address other identified non-compliance items?	Legislative	Not Applicable
<b>Observation</b>		
<p>The following instances of non-compliance were also noted during the inspection: The Environmental Compliance Approval should reflect the current status of the site. In this case the site is temporarily closed. The ECA does not reflect this situation and needs to be amended. It appears this amendment requirement was missed when the site changed operational status a number of years ago.</p>		

**182357** The Registry Act  
DECLARATION UNDER  
SECTION 23 OF THE ACT

H.

I...V.F..Bawtborue.....of the Township of Kinloss do solemnly declare that I am a party to Provisional Certificate of Approval Waste Disposal Site (Prov. Cert. No. A 272801) which affects the following lands

All and Singular that certain parcel or tract of land and premises, situate, lying and being in the Township of Kinloss, in the County of Bruce, and being composed of part of Lot 16 in the Sixth Concession of the said Township more particularly described as follows:

BEGINNING at the southeast angle of said Lot 16;

THENCE northerly along the easterly limit of said Lot 16, a distance of 610.5 feet to the point of commencement of the parcel herein conveyed;

THENCE westerly parallel to the southerly limit of said Lot 16, a distance of 709.5 feet;

THENCE northerly parallel to the easterly limit of Lot 16, a distance of 585.75 feet;

THENCE easterly parallel to the southerly limit of said Lot 16, a distance of 709.5 feet more or less to the easterly limit of said Lot 16;

THENCE southerly along the easterly limit of said Lot 16, a distance of 585.75 feet more or less to the point of commencement.

TOGETHER WITH a right-of-way for persons, animals and vehicles in favour of the Grantee, its successors and assigns and their invitees and licencees, over part of Lot 16 more particularly described as follows:

BEGINNING at the southeast angle of Lot 16;

THENCE northerly along the easterly limit of Lot 16, a distance of 610.5 feet;

THENCE westerly parallel to the southerly limit of Lot 16, a distance of 528.0 feet to the point of commencement of said right-of-way;

THENCE continuing westerly parallel to the southerly limit of said Lot 16, a distance of 20 feet;

THENCE southerly parallel to the easterly limit of said Lot 16, a distance of 610.5 feet more or less to the southerly limit of Lot 16;

THENCE easterly along the southerly limit of Lot 16, a distance of 20 feet;

THENCE northerly parallel to the easterly limit of Lot 16, a distance of 610.5 feet more or less to the point of commencement of said right-of-way.

I make this solemn declaration conscientiously believing it to be true and knowing that it is of the same force and effect as if made under oath.

Declared before me  
at the Village.... of Ripley...  
this 24th..... day of November...

1980  
Martine Collins  
A Commissioner, etc.

*Seal*  
[Signature]  
Signature of Clerk  
Township of Kinloss

RECEIVED  
MAR 04 2022  
TOWNSHIP OF HURON-KINLOSS



Ministry  
of the  
Environment

Ontario

Provisional Certificate No. A 272801

### PROVISIONAL CERTIFICATE OF APPROVAL WASTE DISPOSAL SITE

Under The Environmental Protection Act, 1971 and the regulations and subject to the limitations thereof, this Provisional Certificate of Approval is issued to:

Township of Kinloss  
Holywood, Ontario  
NOG 2B0

for the use and operation of a 6 hectare (15 acre) landfilling site

all in accordance with the following plans and specifications: 1. Plan of operation submitted to the Owen Sound District Office of MDE under cover of a letter dated August 23, 1979.  
2. Site plan entitled "Kinloss Township Waste Disposal Site."

Located: Part Lot 16, Concession 6  
Township of Kinloss  
County of Bruce

which includes the use of the site only for the disposal of the following categories of waste (NOTE: Use of the site for additional categories of wastes requires a new application and amendments to the Provisional Certificate of Approval) Domestic, commercial and 10% non-hazardous solid industrial (limited to miscellaneous debris from agriculture such as wire, stumps and scrap metal) wastes.

and subject to the following conditions:

1. No operation shall be carried out at the site after sixty days from this condition becoming enforceable unless this Certificate including the reasons for this condition has been registered by the applicant as an instrument in the appropriate Land Registry Office against title to the site and a duplicate registered copy thereof has been returned by the applicant to the Director.

*Seal*

Dated this 1st day of October, 1980.

*[Signature]*

Director, Section 39,  
The Environmental Protection Act, 1971



Ministry of the  
Environment

Ontario

## NOTICE

TO: Township of Kinloss  
Holywood, Ontario  
MOG 280

You are hereby notified that Provisional Certificate of Approval No. A 272801 has been issued to you subject to the conditions outlined therein.

The reasons for the imposition of these conditions are as follows:

The reason for the condition requiring registration of the Certificate is that Section 46 of The Environmental Protection Act, 1971 prohibits any use being made of the lands after they cease to be used for waste disposal purposes within a period of twenty-five years from the year in which such land ceased to be used unless the approval of the Minister for the proposed use has been given. The purpose of this prohibition is to protect future occupants of the site and the environment from any hazards which might occur as a result of waste being disposed of on the site. This prohibition and potential hazard should be drawn to the attention of future owners and occupants by the Certificate being registered on title.

You may by written notice served upon me and the Environmental Appeal Board within 15 days after receipt of this Notice, require a hearing by the Board.

This Notice should be served upon:

The Secretary,  
Environmental Appeal Board,  
1 St. Clair Ave. West,  
5th Floor,  
Toronto, Ontario.  
M4V 1K7

AND

The Director,  
Section 39  
Ministry of the Environment,

DATED this 1st day of October, 1980.

*Seal*

*[Signature]*

Director,  
Section 39  
Ministry of the Environment.

182357

*Kinloss*  
DATED THE 1st DAY OF  
OCTOBER

182357

No. 182357  
I CERTIFY that this instrument is registered as is

10:52 AM

NOV 25 1980

In the  
Land Registry Office  
at Wellington,  
Ontario.  
*[Signature]*  
DEPUTY LAND REGISTRAR

BETWEEN

THE DIRECTOR  
-and-

TOWNSHIP OF KINLOSS

PROPERTY OF  
L.R.O. #9  
INDEXED FOLIO 52  
ENTERED ARCHIVE  
FILMED PAGES 4

PROVISIONAL CERTIFICATE  
OF APPROVAL  
UNDER  
THE ENVIRONMENTAL  
PROTECTION ACT, 1971

10:52

PAGE LOT 16, CONCESSION 6  
TOWNSHIP OF KINLOSS  
COUNTY OF BRICK  
TOWNSHIP OF KINLOSS  
HORNPOOD, ONTARIO  
REG 280

REGISTRATION FEE	15.00
LAND TRANSFER TAX	
RETAIL SALES TAX	

## Wellwood, Debbie

---

**From:** Hines, Lisa (MECP) <Lisa.Hines@ontario.ca>  
**Sent:** June 12, 2023 1:43 PM  
**To:** Hutchesson, Sarah; John Yungblut  
**Cc:** Jane Eybergen; Tamasauskas, Kaurel  
**Subject:** RE: Submission of Annual Monitoring Reports - Huron and Kinloss Landfill Sites

Good afternoon Sarah,

Surface water reviews of the 2022 Annual Monitoring Reports for the Huron Landfill and Kinloss Landfill have been completed. The following comments were provided by the ministry's technical reviewer:

### Huron Landfill:

Based on my review of 2022 surface water monitoring results for the Huron landfill Site, I have the following comments:

1. Surface water quality measured for both river monitoring locations (SW1, SW2) is similar and do not suggest significant impact from landfill activities. Slight exceedances of aluminum and iron at the downstream location do not require any action.
2. Water quality measured for the ponded water (SW3) showed exceedances of several parameters, indicative of leachate impacts. It is recommended to continue monitoring SW3 location and track changes in contamination level in future monitoring efforts.
3. Surface water monitoring program and its reporting to MECP should continue as per the existing ECA requirements.

### Kinloss Landfill:

Based on my review of the 2020-2022 surface water monitoring data for the Kinloss Landfill Site, I have the following comments:

1. During 2020-2022 monitoring events, certain measurements of aluminum, zinc and TP in surface water samples exceeded their PWQOs. Since these concentrations are not at alarming levels, no action required at this time.
2. In general, water quality measured at both, upstream and downstream, surface water monitoring locations is similar and hence suggest that the landfill Site does not have significant impact on the Creek's water quality.
3. It is agreed that surface water monitoring should continue as per the requirements of the current ECA.

Regards,

Lisa Hines  
Senior Environmental Officer  
*Ministry of the Environment, Conservation and Parks*  
Owen Sound District Office  
101-17<sup>th</sup> Street East, 3<sup>rd</sup> Floor, Owen Sound, ON N4K 0A5  
E: [Lisa.Hines@ontario.ca](mailto:Lisa.Hines@ontario.ca)

P: 519-270-6627

F: 519-371-2905

NOTICE: This electronic transmission, including any accompanying attachments, may contain confidential and privileged information that could be privileged and/or exempt from disclosure under applicable law, and is intended for the use of the recipient(s) named above. If you have received this communication in error, please notify the sender immediately by return email and permanently delete the copy you received. Thank you.

---

**From:** Hutchesson, Sarah <sarah.hutchesson@wsp.com>

**Sent:** March 30, 2023 8:14 PM

**To:** Hines, Lisa (MECP) <Lisa.Hines@ontario.ca>; John Yungblut <jyungblut@huronkinloss.com>

**Cc:** Jane Eybergen <jeybergen@huronkinloss.com>; Tamasauskas, Kaurel <Kaurel.Tamasauskas@wsp.com>

**Subject:** Submission of Annual Monitoring Reports - Huron and Kinloss Landfill Sites

**CAUTION -- EXTERNAL E-MAIL - Do not click links or open attachments unless you recognize the sender.**

Hi Lisa,

We are submitting two (2) 2022 Landfill Annual Monitoring Reports (AMR) on behalf of the Township of Huron-Kinloss today.

We are submitting the reports electronically, consistent with requests from the MECP. My next email will have the link to the folder titled 'Submitted March 2023 HK', where you will be able to access the final version of the 2022 AMRs being submitted today, March 30<sup>th</sup>, 2023, on behalf of the Township of Huron-Kinloss:

1. 2022 AMR – Huron Landfill, due to the MECP by March 31<sup>st</sup>, 2023 as per ECA No. A272601
2. 2022 AMR – Kinloss Landfill, due to the MECP by March 31<sup>st</sup>, 2023 as per ECA No. A272801

I have included John Yungblut and Jane Eybergen from the Township of Huron-Kinloss on this and the submission email.

Please let me know if I can forward the link to the 2022 Huron-Kinloss Landfill AMR folder to anyone else at the MECP.

Please let me know that you have received this email, as well as that you can access the 2022 AMRs being submitted today.

Sincerely,

Sarah



**Sarah Hutchesson**

Environmental Engineer

M.Sc., P.Eng.

*She/Her*

T+ 1 705-712-0185

M+ 1 705-441-6016

WSP Canada Inc.

561 Bryne Drive Units C&D

Barrie, Ontario

NOTICE: This communication and any attachments ("this message") may contain information which is privileged, confidential, proprietary or otherwise subject to restricted disclosure under applicable law. This message is for the sole use of the intended recipient(s). Any unauthorized use, disclosure, viewing, copying, alteration, dissemination or distribution of, or reliance on, this message is strictly prohibited. If you have received this message in error, or you are not an authorized or intended recipient, please notify the sender immediately by replying to this message, delete this message and all copies from your e-mail system and destroy any printed copies. You are receiving this communication because you are listed as a current WSP contact. Should you have any questions regarding WSP's electronic communications policy, please consult our Anti-Spam Commitment at [www.wsp.com/cas](http://www.wsp.com/cas). For any concern or if you believe you should not be receiving this message, please forward this message to [caslcompliance@wsp.com](mailto:caslcompliance@wsp.com) so that we can promptly address your request. Note that not all messages sent by WSP qualify as commercial electronic messages.

AVIS : Ce message, incluant tout fichier l'accompagnant (« le message »), peut contenir des renseignements ou de l'information privilégiés, confidentiels, propriétaires ou à divulgation restreinte en vertu de la loi. Ce message est destiné à l'usage exclusif du/des destinataire(s) voulu(s). Toute utilisation non permise, divulgation, lecture, reproduction, modification, diffusion ou distribution est interdite. Si vous avez reçu ce message par erreur, ou que vous n'êtes pas un destinataire autorisé ou voulu, veuillez en aviser l'expéditeur immédiatement et détruire le message et toute copie électronique ou imprimée. Vous recevez cette communication car vous faites partie des contacts de WSP. Si vous avez des questions concernant la politique de communications électroniques de WSP, veuillez consulter notre Engagement anti-pourriel au [www.wsp.com/lcap](http://www.wsp.com/lcap). Pour toute question ou si vous croyez que vous ne devriez pas recevoir ce message, prière de le transférer au [conformitelcap@wsp.com](mailto:conformitelcap@wsp.com) afin que nous puissions rapidement traiter votre demande. Notez que ce ne sont pas tous les messages transmis par WSP qui constituent des messages électroniques commerciaux.

-LAEmlHhHzdJzBITWfa4Hgs7pbKl



**APPENDIX G**

# Summary of Surface Water Results

G-1 Summary of Surface Water Results (Pre-2007 – R.J. Burnside)

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

CREEK - UPSTREAM

	SEP 95	MAY 96	SEP 96	MAY 97	SEP 97	MAY 98
alkalinity	239	155	209	188	238	234
pH	7.50	8.2	7.7	7.73	7.5	7.97
conductivity	461	273	356	366	441	376
chloride	7.3	1.0	2.0	<1	4	2
hardness	263	161	195	203	229	277
D.O.C.	8.3	6.8	10.0	3.8	7.1	5.4
phenols	3.6	<1	<1	<1	<1	<1
turbidity	0.437	0.10	0.10	0.10	1.3	0.5
total phos.	0.02	0.009	0.016	<0.01	0.007	0.004
soluble phos.	<0.01	<0.04	0.05	<0.01	<0.01	<0.01
colour		60	49	16	33	41
magnesium	20.5	12.5	13.9	17.2	23.4	18.9
calcium	71.4	43.8	55.3	52.9	53.2	79.6
sodium	1.1	0.70	0.85	0.8	0.83	1.20
iron		0.041	0.033	<0.02	3.88	0.17
nitrite	0.1	<0.03	<0.03	<0.01	0.01	<0.02
ammonia	0.12	<0.05	<0.05	1.01	0.06	<0.05
TKN (nitrogen)	0.48	0.39	0.64			-
nitrate	0.1	<0.03	<0.03	<0.05	<0.05	<0.1
Nickel						<0.05
Arsenic						-
Cadmium		<0.003	<0.003	<.0003	<0.005	<0.002
Chromium		<0.005	<0.005	<0.002	<0.02	<0.02
Copper		<0.003	<0.003	<0.002	<0.02	<0.01
Mercury						-
Manganese		0.014	0.012	0.004	1.62	-
Lead		<0.025	<0.025	0.0001	<0.04	<0.03
Selenium						-
Zinc		0.006	<0.005	0.004	<0.01	0.49
Silver						<0.01

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

CREEK - UPSTREAM

	MAY 99	MAY 00	SEP 00			
alkalinity	200	200	213			
pH	7.72	7.52	8.06			
conductivity	360	396	391			
chloride	2	2	3			
hardness	227	234	236			
D.O.C.	9.3	8.6	9.8			
phenols	<1	<1	<1			
turbidity	1.26	0.81	0.27			
total phos.	0.007	0.008	0.002			
soluble phos.	<0.01	<0.01	<0.01			
colour	47	45	43			
magnesium	16.1	19.5	18.8			
calcium	64.3	61.7	63.5			
sodium	1.21	1.06	1.05			
iron	0.27	0.17	0.19			
nitrite	<0.02	<0.02	<0.02			
ammonia	<0.05	<0.05	<0.05			
TKN (nitrogen)	-	-	-			
nitrate	0.10	<0.1	0.12			
Nickel	<0.05	<0.05	<0.05			
Arsenic	-	-	-			
Cadmium	<0.002	<0.0001	<0.0001			
Chromium	<0.02	<0.01	<0.01			
Copper	<0.01	<0.002	<0.002			
Mercury	-	-	-			
Manganese	-	-	-			
Lead	<0.03	<0.0005	<0.0005			
Selenium	-	-	-			
Zinc	<0.01	<0.01	0.02			
Silver	<0.01	<0.01	<0.01			

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

CREEK DOWNSTREAM

	MAY 97	SEP 97	MAY 98	OCT 98	MAY 99	OCT 99
alkalinity	225	262	258	240.	230.	270
pH	8.06	8.12	8.30	8.50	8.03	8.28
conductivity	437	512	430	509.	440.	465
chloride	3.7	7	4	5.	5.	4
hardness	246	232	272	286.	257.	307
D.O.C.	2.9	3.1	2.6	3.4	7.1	1.9
phenols	<1	<1	<1	<1	<1	12
turbidity	0.10	0.7	0.3	2.0	0.89	0.27
total phos.	<0.01	0.022	0.012	<0.013	0.020	0.017
soluble phos.	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
colour	12	18	14	19.	37.	6
magnesium	22.4	27.5	21.8	22.8	19.6	24.2
calcium	61.6	47.5	73.0	76.9	70.7	83.0
sodium	1.9	2.19	2.00	3.07	3.02	3.34
iron	<0.02	<0.04	0.09	0.09	0.13	0.08
nitrite	<0.01	<0.01	<0.02	<0.02	<0.02	<0.02
ammonia	0.38	0.06<	<0.05	<0.05	<0.05	<0.05
TKN (nitrogen)			-	-	-	-
nitrate	0.07	0.13	<0.1	<0.1	0.15	<0.1
Nickel			<0.05	<0.05	<0.05	<0.05
Arsenic			-	-	-	-
Cadmium	0.0006	<0.005	0.005	<0.002	<0.02	0.021
Chromium	<0.002	<0.02	<0.02	<0.02	<0.02	<0.01
Copper	<0.002	<0.02	<0.01	<0.01	<0.01	<0.01
Mercury			-	-	-	-
Manganese	0.018	0.02	-	-	-	-
Lead	0.0002	<0.04	0.03	0.03	<0.03	<0.03
Selenium			-	-	-	-
Zinc	0.004	<0.01	0.68	<0.01	0.11	0.14
Silver			<0.01	<0.01	0.01	<0.01

GROUNDWATER SAMPLING  
KINLOSS TOWNSHIP LANDFILL SITE (W99613)

CREEK DOWNSTREAM

	MAY 00	SEP 00				
alkalinity	232	262				
pH	7.95	8.28				
conductivity	440	462				
chloride	4	4				
hardness	271	278				
D.O.C.	5.8	6.0				
phenols	<1	21				
turbidity	1.48	2.26				
total phos.	0.033	0.009				
soluble phos.	<0.01	<0.01				
colour	27	25				
magnesium	23.8	23.2				
calcium	69.2	72.9				
sodium	2.69	2.07				
iron	0.08	0.09				
nitrite	<0.02	<0.02				
ammonia	0.10	<0.05				
TKN (nitrogen)	-	-				
nitrate	<0.1	<0.1				
Nickel	<0.05	<0.05				
Arsenic	-	-				
Cadmium	<0.0001	<0.0001				
Chromium	<0.01	<0.01				
Copper	<0.002	<0.002				
Mercury	-	-				
Manganese	-	-				
Lead	<0.0005	<0.0005				
Selenium	-	-				
Zinc	<0.01	0.12				
Silver	<0.01	<0.01				

Appendix D  
Surface Water Chemistry  
Kinross Landfill Site

Parameter	Units	PWQO	SW1 May-00	SW2 May-00	SW1 Sep-00	SW2 Sep-00	SW1 May-01	SW2 May-01	SW1 Sep-01	SW2 Sep-01	SW1 May-02	SW2 May-02	SW1 Sep-02	SW2 Sep-02
<b>General Chemistry</b>														
pH Value	pH units		7.52	7.95	8.06	8.28	8.08	8.24	7.8	8.28	8.33	8.24	DRY	8.08
pH Value (Field)	pH units		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	DRY	NA
Temperature (Field)	°C		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	DRY	8
Ammonia as N	mg/L	0.020	< 0.05	0.1	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	DRY	15.1
Ammonia (un-ionized)	mg/L		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	DRY	< 0.05
Nitrate (as N)	mg/L		< 0.1	< 0.1	0.12	< 0.1	< 0.1	< 0.1	< 0.1	< 0.1	< 0.1	3.94	DRY	< 0.00136
Nitrite (as N)	mg/L		< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	4.47	DRY	0.41
Nitrate + Nitrite (as N)	mg/L		< 0.1	< 0.1	0.12	< 0.1	< 0.1	< 0.1	< 0.1	< 0.1	< 0.1	3.94	DRY	< 0.02
Carbon, Diss. Org. as C	mg/L		8.6	5.8	9.8	6	6.2	4	7.8	< 0.1	3.94	4.47	DRY	0.41
Total Phosphorus (as P)	mg/L		0.008	0.033	0.002	0.009	0.002	4	7.8	< 0.1	3.94	4.47	DRY	0.41
Diss. Organic Phosphorus (as P)	mg/L		< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.002	4	7.8	3.5	3.1	DRY	1.7
Conductivity	us/cm		396	440	< 0.01	< 0.01	< 0.01	< 0.01	0.025	0.005	0.011	0.017	DRY	0.445
Conductivity (Field)	us/cm		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	DRY	< 0.01
Sulphate (as SO4)	mg/L		391	462	382	437	469	528	500	510	510	510	DRY	< 0.01
Alkalinity (CaCO3)	mg/L		13	18	2	5	3	4	4	10	NA	NA	DRY	NA
Chloride (as Cl)	mg/L		200	232	213	262	212	246	234	260	265	254	DRY	NA
Colour	TCU		2	4	3	4	4	4	5	5	9	8	DRY	272
Calculated Hardness (as CaCO3)	mg/L		45	27	43	25	31	24	34	17	< 6	9	DRY	6
Turbidity	NTU		234	271	236	278	258	288	258	311	274	292	DRY	6
Total Phenolics (4-AAP)	mg/L	0.001	0.81	1.48	0.27	2.26	0.2	0.43	0.65	0.18	2.31	5.95	DRY	297
Total Carbons	meq/L		< 0.001	< 0.001	< 0.001	0.021	NA	< 0.001	< 0.001	< 0.001	< 0.002	< 0.002	DRY	104
Total Anions	meq/L		4.75	5.56	4.78	5.67	5.21	5.86	5.21	6.34	5.72	< 0.002	DRY	< 0.002
Ion Balance	% diff.		4.33	5.13	4.39	5.46	4.42	5.12	4.9	5.55	5.91	5.98	DRY	6.06
Calculated T.D.S.	mg/L		4.67	4.08	4.18	1.89	8.22	6.82	3.04	6.88	1.59	0.98	DRY	5.91
			223	265	223	274	230	265	244	287	299	311	DRY	1.25
<b>Trace Metals</b>														
Aluminum, Al	mg/L	0.075	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	0.08	0.012	0.115	0.093	0.149	DRY	0.245
Beryllium, Be	mg/L	1.100	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	0.024	0.038	< 0.001	< 0.001	DRY	< 0.001
Boron, B	mg/L	0.200	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	0.01	0.01	0.01	0.01	DRY	0.02
Cadmium, Cd	mg/L	0.0005	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	0.0001	0.001	0.0004	0.0003	DRY	0.0005
Calcium, Ca	mg/L		81.7	69.2	83.5	72.9	72.4	78.9	68.5	81.7	74.8	79.5	DRY	79.4
Chromium, Cr	mg/L		< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.005	< 0.005	< 0.005	< 0.005	DRY	< 0.005
Cobalt, Co	mg/L	0.0009	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.001	< 0.001	0.004	0.004	DRY	< 0.001
Copper, Cu	mg/L	0.005	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	0.002	0.002	DRY	< 0.002
Iron, Fe	mg/L	0.3	0.17	0.08	0.19	0.09	< 0.02	0.1	0.2	0.28	0.1	0.18	DRY	0.61
Lead, Pb	mg/L	0.005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	0.0007	< 0.0005	0.0005	DRY	0.0013
Magnesium, Mg	mg/L		18.5	23.8	18.8	23.2	18.7	22.1	21.1	28	21.3	22.8	DRY	24
Molybdenum, Mo	mg/L	0.040	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.05	< 0.02	< 0.02	< 0.02	< 0.02	DRY	< 0.002
Nickel, Ni	mg/L	0.025	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.02	< 0.02	< 0.02	< 0.02	DRY	< 0.002
Potassium, K	mg/L		0.81	1.09	0.56	1.16	0.22	0.72	< 1	< 1	1.7	1.9	DRY	< 1
Silica, Reactive (as SiO2)	mg/L	0.0001	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	4.74	2.19	4.37	2.1	DRY	NA
Silver, Ag	mg/L		4.89	6.32	5.82	7.81	3.32	1.1	2.07	1.3	2.9	4.4	DRY	< 0.0001
Sodium, Na	mg/L		1.06	2.69	1.06	2.07	1.11	2.07	1.3	2.9	4.4	4.7	DRY	2.8
Vanadium, V	mg/L	0.0050	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.0001	< 0.0001	< 0.0001	< 0.0001	DRY	< 0.0001
Zinc, Zn	mg/L	0.020	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.01	< 0.002	< 0.002	< 0.002	< 0.002	DRY	0.007

Note:  
Shading indicates exceedance of the Provincial Water Quality Objectives  
Exceedences of the PWQO due to detection limits are not noted

Appendix D  
Surface Water Chemistry  
Kinross Landfill Site

Parameter	Units	PWQO	SW1 May-03	SW2 May-03	SW1 Oct-03	SW2 Oct-03	SW1 May-04	SW2 May-04	SW1 Sep-04	SW2 Sep-04
<b>General Chemistry</b>										
pH Value	pH units		7.99	8.14	7.8	8	7.95	7.98	7.73	8.21
pH Value (Field)	pH units		7.38	8.81	7.74	7.86	7.77	7.84	6.96	8.02
Temperature (Field)	°C		19.3	14.8	11.7	11.5	21.9	17.7	20.5	15.4
Ammonia as N	mg/L		< 0.05	< 0.05	< 0.05	< 0.05	0.05	0.05	0.07	0.05
Ammonia (un-ionized)	mg/L	0.020	< 0.0004	< 0.0074	< 0.0006	< 0.0007	0.0013	0.0011	0.0003	0.0014
Nitrate (as N)	mg/L		0.24	0.27	0.27	0.15	0.31	0.38	0.1	0.32
Nitrite (as N)	mg/L		< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02	< 0.02
Nitrate + Nitrite (as N)	mg/L		0.24	0.27	0.27	0.15	0.31	0.38	< 0.1	0.32
Carbon, Diss. Org. as C	mg/L		8.7	4.8	7.3	4.6	8.9	6	6.5	2
Total Phosphorus (as P)	mg/L		0.006	0.006	0.003	0.01	< 0.002	< 0.002	< 0.002	< 0.002
Diss. Organic Phosphorus (as P)	mg/L		< 0.01	< 0.01	< 0.01	< 0.01	< 0.002	< 0.002	< 0.002	< 0.002
Conductivity	us/cm		370	463	438	495	372	438	567	537
Conductivity (Field)	us/cm		346	428	412	455	352	411	510	477
Sulphate (as SO4)	mg/L		14	21	11	17	8	11	3	15
Alkalinity (as CaCO3)	mg/L		182	223	231	258	193	219	290	276
Chloride (as Cl)	mg/L		4	5	7	8	5	5	12	7
Colour	TCU		45	24	26	18	40	30.1	43	11.8
Calculated Hardness (as CaCO3)	mg/L		195	230	235	269	198	227	308	277
Turbidity	NTU		0.1	< 0.1	0.35	0.48	0.31	0.25	3.8	0.38
Total Phenolics (4-AAP)	mg/L	0.001	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002
Total Cations	meq/L		3.95	4.71	4.78	5.52	4	4.67	8.31	5.68
Total Anions	meq/L		4.06	5.06	5.07	5.69	4.15	4.78	6.2	6.09
Ion Balance	% diff.		1.41	3.67	2.87	1.65	1.78	1.17	0.87	3.64
Calculated T.D.S.	mg/L		199	246	244	279	200	234	305	293
<b>Trace Metals</b>										
Aluminum, Al	mg/L	0.075	0.029	0.028	0.022	0.014	< 0.006	0.046	0.512	0.095
Beryllium, Be	mg/L	1.100	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001
Boron, B	mg/L	0.200	0.011	0.013	0.011	0.013	0.009	0.012	0.007	0.007
Cadmium, Cd	mg/L	0.0006	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	0.0005	0.0013	0.0003
Chromium, Cr	mg/L		54	61.7	66.7	73	54.8	61.9	66.9	74.9
Cobalt, Co	mg/L		< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005
Copper, Cu	mg/L	0.0009	< 0.0001	< 0.0001	< 0.0001	0.0003	0.0001	0.0001	0.0009	0.0001
Iron, Fe	mg/L	0.005	< 0.0005	< 0.0005	0.0006	0.0007	0.0008	0.0019	0.005	0.0011
Lead, Pb	mg/L	0.3	0.04	0.04	< 0.03	< 0.03	< 0.03	0.1	4.64	0.22
Magnesium, Mg	mg/L	0.005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	0.0039	0.0008
Molybdenum, Mo	mg/L		14.8	18.5	17.3	21.1	14.8	17.7	22.8	21.9
Nickel, Ni	mg/L	0.040	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001
Potassium, K	mg/L	0.025	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001
Silica, Reactive (as SiO2)	mg/L		0.5	0.8	0.8	0.8	< 0.001	< 0.001	0.001	< 0.001
Silver, Ag	mg/L		1.55	1.82	3.9	6.8	1.21	1.6	1.4	0.8
Sodium, Na	mg/L	0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0001
Vanadium, V	mg/L		0.9	2	1.5	2.7	0.9	2.2	2.8	2.4
Zinc, Zn	mg/L	0.0060	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	< 0.0005	0.0015	< 0.0005
		0.020	0.031	0.039	0.04	< 0.005	< 0.005	< 0.005	0.024	0.008

Note:  
Shading indicates exceedance of the Provincial Water Quality Obj  
Exceedences of the PWQO due to dection limits are not noted



Appendix D  
 Historical Surface Water Quality Data  
 Kinloss Landfill Site

Parameter	Units	PWQO	TDL	SW1 5/25/2005	SW2 5/25/2005	SW1 9/28/2005	SW2 9/28/2005
<b>FIELD MONITORING RESULTS</b>							
Temperature	°C						
pH	pH		N/A	15.1	11.1	18.8	13.7
Conductivity	uS/cm		N/A	4.00	7.63	7.22	7.73
<b>INORGANICS</b>							
Unionized Ammonia (Calculated)	mg/L	0.02	N/A				
Total Ammonia-N	mg/L		0.05	N/A	N/A	N/A	N/A
Conductivity	uS/cm			ND	ND	ND	ND
Nitrite (N)	mg/L		2	415	478	425	499
Dissolved Organic Carbon	mg/L		0.3	ND	ND	ND	ND
Total Organic Carbon (TOC)	mg/L		0.1	6.0	3.5		
pH	pH		1			15	6.5
Phenol-4AAP	mg/L	0.001	0.01	8.11	8.25	8.00	8.20
Total Phosphorus	mg/L		0.002	0.017	0.008	0.003	0.004
Turbidity	NTU		0.1	2.9	0.40	1.0	0.037
Total Alkalinity (Total as CaCO3)	mg/L		1	212	245	190	250
Chloride (Cl)	mg/L		1	4.3	5.8	6.0	7.0
Total p-Alkalinity	mg/L		1	ND	ND		
Nitrate (N)	mg/L		0.2	0.10	0.20	1.5	ND
Phosphate-P	mg/L		1	ND	ND	2	ND
Sulphate (SO4)	mg/L		1	3.00	10.2	38.0	27.0
<b>CALCULATED VALUES</b>							
Anion Sum	me/L		N/A	4.43	5.29		
Bicarb. Alkalinity (calc. as CaCO3)	mg/L		1	209	241	188	246
Calculated TDS	mg/L		1	220	266	242	278
Carb. Alkalinity (calc. as CaCO3)	mg/L		1	3	4	2	4
Cation Sum	me/L		N/A	4.81	5.84		
Dissolved Hardness (CaCO3)	mg/L		N/A	240	290	210	250
Ion Balance (% Difference)	%		N/A	4.18	4.99		
Langelier Index (@ 20C)	N/A		N/A	0.849	1.10	0.651	1.03
Langelier Index (@ 4C)	N/A		N/A	0.599	0.852	0.401	0.782
Saturation pH (@ 20C)	N/A		N/A	7.27	7.15	7.37	7.19
Saturation pH (@ 4C)	N/A		N/A	7.52	7.40	7.62	7.44
<b>METALS</b>							
Dissolved Aluminum (Al)	mg/L	0.075	0.005	0.021	0.012		
Dissolved Beryllium (Be)	mg/L	1.100	0.0005	ND	ND		
Dissolved Boron (B)	mg/L	0.200	0.01	0.01	0.01		
Dissolved Cadmium (Cd)	mg/L	0.0005	0.0001	ND	ND		
Dissolved Calcium (Ca)	mg/L		0.2	64.2	78.0	57.6	67.4
Dissolved Chromium (Cr)	mg/L		0.005	ND	ND		
Dissolved Cobalt (Co)	mg/L	0.0009	0.0005	0.0008	ND		
Dissolved Copper (Cu)	mg/L	0.005	0.001	0.011	0.0030		
Dissolved Iron (Fe)	mg/L	0.3	0.05	ND	ND		
Dissolved Lead (Pb)	mg/L	0.005	0.0005	ND	ND		
Dissolved Magnesium (Mg)	mg/L		0.05	18.8	23.4	17.1	21.0
Dissolved Molybdenum (Mo)	mg/L	0.040	0.001	ND	ND		
Dissolved Nickel (Ni)	mg/L	0.025	0.001	ND	ND		
Dissolved Potassium (K)	mg/L		0.2	0.6	0.8	1	ND
Dissolved Silver (Ag)	mg/L	0.0001	0.0005	ND	ND		
Dissolved Sodium (Na)	mg/L		0.1	1.5	2.4	1.7	3.6
Dissolved Vanadium (V)	mg/L	0.008	0.001	ND	ND		
Dissolved Zinc (Zn)	mg/L	0.020	0.005	0.009	0.007		

N/A = Not Applicable

ND = Not detected

TDL = Typical Detection Limit. Actual detection limit varies with the concentration of each sample.

Spring metals samples were erroneously filtered by Maxxam Analytics and thus only the 'dissolved' concentration of each trace metal is reported. The total concentration of trace metals would have been somewhat higher and therefore could have exceeded the PWQO, however this information is not known.

Appendix D  
 Historical Surface Water Quality Data  
 Kinloss Landfill Site

Parameter	Units	PWQO	TDL	SW1 5/25/2005	SW2 5/25/2005	SW1 9/28/2005	SW2 9/28/2005
Total Aluminum (Al)	mg/L	0.075	0.005			0.028	0.010
Total Arsenic (As)	mg/L	0.005	0.001			ND	ND
Total Beryllium (Be)	mg/L	1.1	0.0005			ND	ND
Total Boron (B)	mg/L	0.2	0.01			ND	ND
Total Cadmium (Cd)	mg/L	0.0005	0.0001			0.017	0.022
Total Calcium (Ca)	mg/L		0.2			0.0001	ND
Total Chromium (Cr)	mg/L		0.005			63	76
Total Cobalt (Co)	mg/L	0.0009	0.0005			0.006	0.006
Total Copper (Cu)	mg/L	0.005	0.001			ND	ND
Total Iron (Fe)	mg/L	0.3	0.05			ND	ND
Total Lead (Pb)	mg/L	0.005	0.0005			0.12	0.071
Total Magnesium (Mg)	mg/L		0.05			ND	ND
Total Molybdenum (Mo)	mg/L	0.040	0.001			17	22
Total Nickel (Ni)	mg/L	0.025	0.001			ND	ND
Total Potassium (K)	mg/L		0.2			0.008	ND
Total Silicon (Si)	mg/L		0.05			1.6	1.2
Total Silver (Ag)	mg/L	0.0001	0.0005			2.2	3.4
Total Sodium (Na)	mg/L		0.1			ND	ND
Total Vanadium (V)	mg/L	0.006	0.001			1.6	3.3
Total Zinc (Zn)	mg/L	0.020	0.005			ND	ND

N/A = Not Applicable

ND = Not detected


TDL = Typical Detection Limit. Actual detection limit varies with the concentration of each sample.  
 Spring metals samples were erroneously filtered by Maxxam Analytics and thus only the 'dissolved' concentration of each trace metal is reported. The total concentration of trace metals would have been somewhat higher and therefore could have exceed the PWQO, however this information is not known.

Standard Surface Water Quality Package  
Kinloss Landfill Site


Parameter	Short I.D.	Unit	PWQO	M.D.L	SW1	SW2	SW1	SW2
Well Class					Up	Down	Up	Down
Well Owner					Town	Town	Town	Town
Date of Sampling					17-Apr-06	17-Apr-06	3-Oct-06	3-Oct-06
<b>FIELD MONITORING RESULTS</b>								
Temperature		°C						
pH		pH			16.8	12.7	16.8	12.7
Electrical Conductivity	Th. Cond.	uS/cm			7.72	7.48	7.72	7.48
<b>INORGANICS</b>								
pH		pH			374	454	374	454
Chloride	Cl <sup>-</sup>	mg/L		N/A	8.2	8.35	7.79	8.15
Electrical Conductivity	Th. Cond.	uS/cm		0.10	3.85	5.18	6.86	9.29
Total Hardness (as CaCO3)	Hard(Calc)	mg/L		2	388	469	452	544
Dissolved Organic Carbon (DOC)	DOC	mg/L			207	244	242	285
Total Dissolved Solids	Th. TDS	mg/L		1	4	2	9	5.3
Ammonia (un-ionized)	NH <sub>3</sub> un-ion	mg/L	0.02	20	214	262	262	294
Ammonia as N	NH <sub>3</sub> -N	mg/L			0.0003	<0.0001	0.0003	<0.0001
Nitrate as N	NO <sub>3</sub> -N	mg/L		0.02	<0.02	<0.02	<0.02	<0.02
Nitrite as N	NO <sub>2</sub> -N	mg/L		0.05	0.1	0.29	<0.05	0.14
(Nitrate + Nitrite) as N	NO <sub>2</sub> +NO <sub>3</sub>	mg/L		0.05	<0.05	<0.05	<0.05	<0.05
Bromide	Br <sup>-</sup>	mg/L		0.10	0.1	0.28	<0.05	<0.05
Sulphate	SO <sub>4</sub> <sup>2-</sup>	mg/L		0.05	<0.05	<0.05	<0.05	<0.05
Phosphate as P	PO <sub>4</sub> <sup>3-</sup>	mg/L		0.10	7.48	12.6	4.68	20.7
pH, Saturation	pHs	N/A			<0.10	<0.10	<0.10	<0.10
Phenols	Phenol	mg/L		N/A	7.22	7.07	7.08	6.95
Turbidity	Turbidity	NTU	0.001	0.001	<0.001	<0.001	<0.001	<0.001
p-Alkalinity (as CaCO3)	Alk 8.3	mg/L		5	<0.5	<0.5	<0.5	<0.5
t-Alkalinity (as CaCO3)	Alk 4.2	mg/L		10	198	233	231	268
<b>CALCULATED VLAUES</b>								
Anion Sum	Anion	mg/L		NA	3.52	4.37	4.09	5.08
Cation Sum	Cation	mg/L		NA	4.19	5	4.91	5.89
Ion Balance	CAB	%		NA	8.68	6.87	9.1	7.4
Carbonate (as CaCO3)	CO <sub>3</sub> <sup>2-</sup>	mg/L		5	<5	7	<5	<6
Bicarbonate (as CaCO3)	HCO <sub>3</sub> <sup>-</sup>	mg/L		5	198	228	231	268
Langlier Index	L.I.	N/A		NA	0.98	1.28	0.71	1.2
Aggressive Index	A.I.	N/A		NA	12.8	13.1	12.5	13
Ryznar Stability Index	R.S.I.	N/A		NA	8.2	5.8	6.37	5.75
<b>METALS</b>								
Silver	Ag	mg/L	0.0001	0.0001	<0.0001	<0.0001	<0.0001	<0.0001
Aluminum	Al	mg/L	0.075	0.004	0.004	0.01	0.008	0.012
Arsenic	As	mg/L	0.005	0.003	<0.003	<0.003	<0.003	<0.003
Boron	B	mg/L	0.20	0.010	<0.010	<0.010	<0.010	0.019
Barium	Ba	mg/L		0.002	0.014	0.022	0.021	0.032
Beryllium	Be	mg/L	0.011	0.002	<0.002	<0.002	<0.002	<0.002
Calcium	Ca	mg/L		0.05	56.5	65.4	68	76
Cadmium	Cd	mg/L	0.0005	0.0002	<0.0002	<0.0002	0.0013	<0.0002
Cobalt	Co	mg/L	0.0009	0.0005	<0.0005	<0.0005	<0.0005	<0.0005
Chromium	Cr	mg/L	0.0089	0.003	<0.003	0.003	<0.003	<0.003
Copper	Cu	mg/L	0.005	0.002	<0.002	<0.002	0.002	<0.002
Iron	Fe	mg/L	0.3	0.005	0.439	0.508	0.172	0.175
Potassium	K	mg/L		0.05	0.56	0.99	0.39	1.07
Magnesium	Mg	mg/L		0.05	15.9	19.7	18.7	23.2
Molybdenum	Mo	mg/L	0.04	0.002	<0.002	<0.002	<0.002	<0.002
Sodium	Na	mg/L		0.05	1.03	1.96	1.46	3.68
Nickel	Ni	mg/L	0.025	0.003	<0.003	<0.003	<0.003	<0.003
Total Phosphorus	P (Tot.)	mg/L	0.01	0.01	0.014	0.017	<0.02	<0.02
Lead	Pb	mg/L	0.005	0.001	<0.001	<0.001	<0.001	<0.001
Vanadium	V	mg/L	0.006	0.002	<0.002	<0.002	<0.002	<0.002
Zinc	Zn	mg/L	0.03	0.004	<0.004	<0.004	0.011	0.005

This table is to be reviewed with the comments in Appendix D


**KINLOSS LANDFILL SITE**  
**Chloride Concentration (mg/L) vs. Time**  
**Surface Water**



**KINLOSS LANDFILL SITE**  
**Conductivity (uS/cm) vs. Time**  
**Surface Water**




**KINLOSS LANDFILL SITE**  
**Hardness (mg/L) vs. Time**  
**Surface Water**



**KINLOSS LANDFILL SITE:**  
**D.O.C. (mg/L) vs. Time**  
**Surface Water**

Note:  
 Concentrations for Fall 2005 were  
 reported as TOTAL Organic Carbon  
 (T.O.C.) rather than D.O.C.



G-2 Summary of Surface Water Results (2007 – Present)



**Table G-2  
Surface Water Quality Results  
Kinloss Landfill - 2007 to 2023**

Surface Water Station				SW 1	SW 1	SW 1	SW 1	SW 1	SW 1	SW 1	SW 1	SW 1	SW 1	SW 1	SW 1	SW 1
Date				Jul-07	Dec-07	Jul-08	Dec-08	Jul-09	Dec-09	Mar-10	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13	Nov-13
	Units	RDL	PWQO													
<b>INORGANICS</b>																
Total Ammonia-N	mg/L	0.05		0.06	ND	0.05	0.05	0.05	ND	<0.05	<0.01	<0.01	0.03	<0.01	0.02	<0.01
Calculated Un-ionized Ammonia	mg/L	2	0.020 (10)	0.003	0	0.0018	0.0006	0.001	-	<0.004	<0.01	-	<0.02	<0.02	<0.02	<0.02
Conductivity	umho/cm			538	449	476	435	487	385	403	469	440	532	450	479	371
Total Dissolved Solids	mg/L	1		352	286	330	NA	NA	NA	NA	265	233	276	292	237	220
Dissolved Organic Carbon	mg/L	0.1		3.6	8.8	10.3	4.7	7.1	8.3	5.0	8.0	12.3	2.0	11.6	11.8	9.5
Orthophosphate	mg/L	0.01		ND	ND	ND	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total Phosphorus	mg/L	0.002	0.030 (9)	NA	NA	NA	0.009	0.01	ND	<0.002	<0.01	<0.01	0.01	0.02	<0.01	<0.01
pH	pH		6.5 - 8.5	8.3	8.1	8.1	8.1	7.9	8.2	8.1	7.72	7.94	8.07	7.37	7.97	8.09
Phenol-4AAP	mg/L	0.001	0.001	ND	ND	ND	ND	ND	ND	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Sulphate (SO4)	mg/L	1		13	43	ND	2	ND	ND	<1	1	11	<1	61	1	4
Turbidity				0.7	1.3	0.4	NA	0.8	0.2	0.4	0.4	1.3	7.0	1.2	1.1	0.5
Alkalinity (Total as CaCO3)	mg/L	1	(7)	287	183	257	229	260	200	213	256	212	274	200	253	223
Dissolved Chloride (Cl)	mg/L	1		8	9	5	5	5	4	5	4.1	4.3	5.4	6.5	4.1	4.4
Nitrite (N)	mg/L	0.01		ND	ND	ND	ND	ND	ND	<0.01	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
Nitrate (N)	mg/L	0.1		0.2	0.1	ND	0.4	ND	0.1	0.3	<0.1	<0.1	<0.1	<0.1	<0.1	0.2
Nitrate + Nitrite	mg/L	0.1		0.2	0.1	ND	0.4	ND	0.1	0.3	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
Hardness	mg/L									210	299	251	295	288	221	216
<b>METALS</b>																
Total Aluminum (Al)	µg/L	1	75 (8)	9200	6	ND	ND	11	ND	<5	30	20	20	50	20	30
Total Barium (Ba)	µg/L	5		18	13	27	12	25	12	16	24	17	32	26	20	11
Total Boron (B)	µg/L	10	200 (I)	ND	ND	ND	ND	ND	ND	<10	10	99	8	<5	10	<5
Total Cadmium (Cd)	µg/L	0.1	0.5 (3)	680	2.5	0.1	ND	0.5	0.2	<0.1	<0.02	<0.02	<0.02	0.04	<0.02	<0.02
Total Calcium (Ca)	µg/L	200		35000	60000	76000	65000	75000	58000	60000	81300	68200	80400	80100	60200	57500
Total Chromium (Cr)	µg/L	5	100	ND	ND	ND	ND	ND	ND	<5	<2	<2	<2	<2	<2	<2
Total Copper (Cu)	µg/L	1	5 (4)	69000	1	ND	ND	1	ND	<1	<2	<2	0.3	<2	2	0.3
Total Iron (Fe)	µg/L	50	300	300	ND	ND	ND	220	ND	<100	59	32	912	24	47	7
Total Lead (Pb)	µg/L	0.5	25 (5)	150	ND	ND	ND	ND	ND	<0.5	<0.02	<0.02	0.03	0.04	0.03	<0.02
Total Magnesium (Mg)	µg/L	50		89000	18000	22000	21000	23000	18000	18000	23300	19700	22900	21300	17100	17500
Total Manganese (Mn)	µg/L	2		14000	3	110	ND	140	2	7	18	13	1030	13	26	2
Total Potassium (K)	µg/L	200		8000	360	540	390	230	600	520	400	1000	300	700	300	400
Total Sodium (Na)	µg/L	100		4800	1400	1300	1200	1400	1100	1200	1500	1400	2100	2500	1600	1600
Total Zinc (Zn)	µg/L	5	30 (6)	270000	ND	ND	ND	8	ND	<5	<5	<5	<5	<5	<5	<5
<b>FIELD MEASUREMENTS</b>																
Temperature	Degrees C			22.5	1.3	19.2	1.6	15.2	3.1	10.6	24.2	9.86	25	15.2	24.6	2.6
Conductivity	µmhos			580	700	590	490	510	260	400	430	404	493	448	511	356
pH				7.20	7.79	7.99	8.00	8.07	8.58	8.60	8.3	7.55	7.15	7.65	7.65	7.90

**NOTES:**

- PWQO indicates Provincial Water Quality Objectives.
- (I) indicates interim PWQO
- Cadmium Interim PWQO = 0.5 µg/L (for Hardness >100 mg/L as CaCO3)
- Copper Interim PWQO = 5 µg/L (for Hardness >20 mg/L)
- Revised Interim PWQO = 5 µg/L (for Alkalinity > 80 mg/L (as CaCO3))
- Zinc Revised Interim PWQO = 20 µg/L

- Alkalinity should not be decreased by more than 25 % of the natural concentration.
- Interim PWQO = 75 µg/L for pH >6.5 to 9.0.
- PWQO = 0.020 mg/L to avoid nuisance algae growth, PWQO = 0.010 mg/L for high level of protection  
PWQO = 0.030 mg/L for prevention of excessive plant growth
- PWQO for un-ionized ammonia
- Shaded values indicates exceedance of PWQO.
- ND = Not detected
- NA = Not analyzed
- RDL = Reportable Detection Limit

**Table G-2  
Surface Water Quality Results  
Kinloss Landfill - 2007 to 2023**

Surface Water Station				SW1	SW1	SW1	SW1	SW1	SW1	SW1	SW1	SW1	SW1	SW1	
Date				Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19
	Units	RDL	PWQO												
<b>INORGANICS</b>															
Total Ammonia-N	mg/L	0.05		<0.01	<0.01	<0.02	<0.02	<0.01	0.02	<0.01	0.01	0.02	0.04	0.11	0.03
Calculated Un-ionized Ammonia	mg/L	2	0.020 (10)	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
Conductivity	umho/cm			455	432	447	464	485	468	490	416	470	418	408	420
Total Dissolved Solids	mg/L	1		252	224	-	-	276	262	259	222	258	232	225	209
Dissolved Organic Carbon	mg/L	0.1		12.4	10.2	5.7	5.5	8.0	7.7	8.1	11.4	7	12.7	8.1	8.1
Orthophosphate	mg/L	0.01		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total Phosphorus	mg/L	0.002	0.030 (9)	<0.01	<0.01	<0.01	<0.01	<0.01	0.02	<0.01	0.01	0.14	<0.01	0.01	0.02
pH	pH		6.5 - 8.5	8.05	7.97	8.44	8.08	7.92	7.97	7.98	8.03	8.44	8.01	8.03	8.07
Phenol-4AAP	mg/L	0.001	0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.002	<0.002	<0.002
Dissolved Sulphate (SO4)	mg/L	1		<1	1	0.97	2.98	<1	5	<1	2	<1	1	<1	2
Turbidity				0.5	0.9	<0.5	<0.5	-	-	0.8	1.8	0.8	1.6	0.5	1.5
Alkalinity (Total as CaCO3)	mg/L	1	(7)	233	230	238	248	283	243	265	224	251	214	213	206
Dissolved Chloride (Cl)	mg/L	1		2.3	3.9	<0.10	8.01	2.6	5.1	4.4	3.1	3.1	3.7	2.1	4.6
Nitrite (N)	mg/L	0.01		<0.1	<0.1	<0.05	<0.10	<0.1	<0.1	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Nitrate (N)	mg/L	0.1		<0.1	0.1	<0.05	<0.10	<0.1	0.1	<0.05	<0.05	<0.05	<0.05	0.05	0.16
Nitrate + Nitrite	mg/L	0.1		<0.1	<0.1	<0.05	<0.10	<0.1	-	-	-	<0.05	<0.05	0.10	0.20
Hardness	mg/L			305	224	231	249	287	288	265	233	287	258	257	218
<b>METALS</b>															
Total Aluminum (Al)	µg/L	1	75 (8)	30	20	8	<4	20	30	30	50	50	50	90	40
Total Barium (Ba)	µg/L	5		26	15	20	16	-	-	22	16	37	45	41	15
Total Boron (B)	µg/L	10	200 (I)	7	<5	<10	<10	6	<5	34	<5	9	5	108	5
Total Cadmium (Cd)	µg/L	0.1	0.5 (3)	<0.02	<0.02	<0.1	<0.1	<0.02	<0.2	<0.014	<0.014	<0.015	0.033	<0.015	<0.015
Total Calcium (Ca)	µg/L	200		84900	60000	63300	68800	78000	79000	72500	61300	78700	70200	71400	58900
Total Chromium (Cr)	µg/L	5	100	<2	<2	<3	<3	<2	<2	<1	<1	<2	<2	<1	2
Total Copper (Cu)	µg/L	1	5 (4)	<0.1	<0.1	<2	<2	<0.1	<0.1	0.2	<0.1	<0.1	4.6	0.1	1
Total Iron (Fe)	µg/L	50	300	76	53	<10	100	98	819	94	49	213	3630	130	411
Total Lead (Pb)	µg/L	0.5	25 (5)	<0.02	<0.02	<1	<1	<0.02	0.09	0.03	<0.02	<0.02	0.49	0.03	0.14
Total Magnesium (Mg)	µg/L	50		22600	18100	17700	18800	22500	22100	20300	19400	22000	20100	19200	17100
Total Manganese (Mn)	µg/L	2		30	14	28	24	82	382	125	24	129	823	19	164
Total Potassium (K)	µg/L	200		600	800	320	550	100	200	300	500	500	700	300	400
Total Sodium (Na)	µg/L	100		1600	1600	1640	2580	2000	3000	2000	1500	2800	2800	2900	1800
Total Zinc (Zn)	µg/L	5	30 (6)	8	6	<5	<5	<2	<5	<5	<5	18	17	12	25
<b>FIELD MEASUREMENTS</b>															
Temperature	Degrees C			23.9	9.0	18.4	8.6	21.2	7.2	24.5	6.8	24.2	7.1	20.6	4.1
Conductivity	µmhos			442	416	427	436	511	434	483	447	460	366	460	420
pH				7.39	7.80	7.58	7.36	7.62	7.38	7.15	7.65	7.11	7.88	7.43	7.45

NOTES:

- PWQO indicates Provincial Water Quality Objectives.
- (I) indicates interim PWQO
- Cadmium Interim PWQO = 0.5 µg/L (for Hardness >100 mg/L as CaCO3)
- Copper Interim PWQO = 5 µg/L (for Hardness >20 mg/L)
- Revised Interim PWQO = 5 µg/L (for Alkalinity > 80 mg/L (as CaCO3))
- Zinc Revised Interim PWQO = 20 µg/L

- Alkalinity should not be decreased by more than 25 % of the natural concentration.
- Interim PWQO = 75 µg/L for pH >6.5 to 9.0.
- PWQO = 0.020 mg/L to avoid nuisance algae growth, PWQO = 0.010 mg/L for high level of protection  
PWQO = 0.030 mg/L for prevention of excessive plant growth
- PWQO for un-ionized ammonia
- Shaded values indicates exceedance of PWQO.
- ND = Not detected
- NA = Not analyzed
- RDL = Reportable Detection Limit

**Table G-2  
Surface Water Quality Results  
Kinloss Landfill - 2007 to 2023**

Surface Water Station				SW1	SW1	SW1	SW1	SW1	SW1	SW1	SW1
Date				Jul-20	Nov-20	Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
	Units	RDL	PWQO								
<b>INORGANICS</b>											
Total Ammonia-N	mg/L	0.05		0.03	0.01	0.03	0.02	<0.01	0.02	<0.01	<0.05
Calculated Un-ionized Ammonia	mg/L	2	0.020 (10)	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
Conductivity	umho/cm			510	392	479	399	473	628	447	495
Total Dissolved Solids	mg/L	1		268	204	249	217	257	331	239	256
Dissolved Organic Carbon	mg/L	0.1		10.6	10.3	9.0	11.3	8.8	5.8	7.6	12.7
Orthophosphate	mg/L	0.01		NA	NA	NA	NA	NA	NA	NA	NA
Total Phosphorus	mg/L	0.002	0.030 (9)	0.02	0.05	<0.01	<0.01	<0.01	0.05	0.01	0.01
pH	pH		6.5 - 8.5	7.81	8.14	8.09	8.08	8.14	7.82	7.92	7.46
Phenol-4AAP	mg/L	0.001	0.001	<0.002	<0.002	0.002	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Sulphate (SO4)	mg/L	1		<1	2	1	1	<1	22	1	<1
Turbidity				4.1	0.3	2.7	0.2	0.3	5.4	5.5	1.1
Alkalinity (Total as CaCO3)	mg/L	1	(7)	272	201	248	217	262	258	252	273
Dissolved Chloride (Cl)	mg/L	1		3.7	3.5	3.2	3.1	2.6	31.5	2.4	4.5
Nitrite (N)	mg/L	0.01		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Nitrate (N)	mg/L	0.1		0.08	<0.05	<0.05	<0.05	<0.05	4.17	0.08	<0.05
Nitrate + Nitrite	mg/L	0.1		0.1	<0.05	<0.05	<0.05	<0.05	4.2	0.10	<0.10
Hardness	mg/L			275	214	266	230	267	300	233	279
<b>METALS</b>											
Total Aluminum (Al)	µg/L	1	75 (8)	30	40	20	30	60	100	20	70
Total Barium (Ba)	µg/L	5		36	13	25	13	20	30	20	31
Total Boron (B)	µg/L	10	200 (I)	9	<5	<5	5	<5	28	7	<5
Total Cadmium (Cd)	µg/L	0.1	0.5 (3)	<0.015	<0.015	<0.015	<0.015	<0.015	<0.015	<0.015	<0.015
Total Calcium (Ca)	µg/L	200		74900	59000	72900	62700	74000	78200	63900	77300
Total Chromium (Cr)	µg/L	5	100	<2	<2	3	<2	<1	<1	<1	<1
Total Copper (Cu)	µg/L	1	5 (4)	6	0.1	0.1	0.2	0.3	1.5	0.2	0.5
Total Iron (Fe)	µg/L	50	300	931	88	143	41	57	155	116	507
Total Lead (Pb)	µg/L	0.5	25 (5)	0.25	<0.02	0.04	<0.02	0.24	0.12	0.05	0.02
Total Magnesium (Mg)	µg/L	50		21500	16100	20400	17800	20000	25400	17700	20800
Total Manganese (Mn)	µg/L	2		1440	94	181	15	38	10	62	293
Total Potassium (K)	µg/L	200		400	400	400	400	400	4300	300	200
Total Sodium (Na)	µg/L	100		1900	1300	1800	1700	2100	13900	1600	2300
Total Zinc (Zn)	µg/L	5	30 (6)	<5	<5	<5	19	5	<5	5	48
<b>FIELD MEASUREMENTS</b>											
Temperature	Degrees C			18.6	8.0	20.1	5.0	14.9	5.3	18.3	17.8
Conductivity	µmhos			531	335	476	393	455	382	417	493
pH				6.85	7.81	7.54	7.30	7.23	8.06	7.79	7.37

NOTES:

- PWQO indicates Provincial Water Quality Objectives.
- (I) indicates interim PWQO
- Cadmium Interim PWQO = 0.5 µg/L (for Hardness >100 mg/L as CaCO3)
- Copper Interim PWQO = 5 µg/L (for Hardness >20 mg/L)
- Revised Interim PWQO = 5 µg/L (for Alkalinity > 80 mg/L (as CaCO3))
- Zinc Revised Interim PWQO = 20 µg/L

- Alkalinity should not be decreased by more than 25 % of the natural concentration.
- Interim PWQO = 75 µg/L for pH >6.5 to 9.0.
- PWQO = 0.020 mg/L to avoid nuisance algae growth, PWQO = 0.010 mg/L for high level of protection  
PWQO = 0.030 mg/L for prevention of excessive plant growth
- PWQO for un-ionized ammonia
- Shaded values indicates exceedance of PWQO.
- ND = Not detected
- NA = Not analyzed
- RDL = Reportable Detection Limit

**Table G-2  
Surface Water Quality Results  
Kinloss Landfill - 2007 to 2023**

Surface Water Station				SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	
Date				Jul-07	Dec-07	Jul-08	Dec-08	Jul-09	Dec-09	Mar-10	Jun-11	Oct-11	Jun-12	Oct-12	Jun-13	Nov-13
	Units	RDL	PWQO													
<b>INORGANICS</b>																
Total Ammonia-N	mg/L	0.05		0.07	ND	0.09	ND	0.05	ND	<0.05	<0.01	<0.01	0.02	<0.01	<0.01	<0.01
Calculated Un-ionized Ammonia	mg/L	2	0.020 (10)	0.003	-	0.003	ND	0.001	-	<0.003	<0.01	-	<0.02	<0.02	<0.02	<0.02
Conductivity	umho/cm			500	518	561	490	533	512	493	507	514	540	523	520	397
Total Dissolved Solids	mg/L	1		340	330	380	NA	NA	NA	NA	294	287	301	364	259	246
Dissolved Organic Carbon	mg/L	0.1		8.7	4.5	7.0	3.8	4.3	5.3	3.3	4.7	7.8	2.5	5.7	8.5	7.9
Orthophosphate	mg/L	0.01		ND	ND	ND	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total Phosphorus	mg/L	0.002	0.030 (9)	NA	NA	NA	0.011	0.013	0.004	0.004	0.01	<0.01	0.02	<0.01	0.01	<0.01
pH	pH		6.5 - 8.5	8.2	8.2	8.3	8.1	8.1	8.2	8.2	8.10	7.96	7.85	7.72	8.14	8.18
Phenol-4AAP	mg/L	0.001	0.001	0.001	ND	ND	ND	ND	ND	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Sulphate (SO4)	mg/L	1		ND	40	7	15	6	14	14	4	19	9	41	4	7
Turbidity				0.8	0.5	4.9	NA	1.3	0.6	0.6	1.5	0.6	6.9	1.4	3.8	1.7
Alkalinity (Total as CaCO3)	mg/L	1	(7)	277	227	298	249	280	251	245	277	246	289	314	272	243
Dissolved Chloride (Cl)	mg/L	1		6	10	8	7	7	11	11	4.8	6.0	6.1	7.5	4.8	4.7
Nitrite (N)	mg/L	0.01		ND	ND	ND	ND	ND	ND	<0.01	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
Nitrate (N)	mg/L	0.1		0.3	0.1	0.1	0.2	0.1	0.1	0.3	0.1	<0.1	0.3	<0.1	0.1	0.1
Nitrate + Nitrite	mg/L	0.1		0.3	0.1	0.1	0.2	0.1	0.1	0.3	<0.2	<0.2	<0.3	<0.2	<0.1	<0.1
Hardness	mg/L									250	330	312	309	349	237	243
<b>METALS</b>																
Total Aluminum (Al)	µg/L	1	75 (8)	10	9	140	17	12	12	52	50	20	70	40	60	70
Total Barium (Ba)	µg/L	5		29	27	41	19	31	23	25	30	36	34	44	27	21
Total Boron (B)	µg/L	10	200 (I)	14	ND	15	ND	14	ND	15	12	109	12	18	13	8
Total Cadmium (Cd)	µg/L	0.1	0.5 (3)	0.1	0.8	0.5	1	0.9	0.1	0.1	<0.02	<0.02	<0.02	<0.02	0.22	<0.02
Total Calcium (Ca)	µg/L	200		92000	70000	91000	68000	82000	73000	72000	88700	83500	81800	93200	63700	64100
Total Chromium (Cr)	µg/L	5	100	ND	ND	ND	ND	ND	ND	<5	<2	<2	35	6	<2	<2
Total Copper (Cu)	µg/L	1	5 (4)	ND	ND	1	ND	ND	ND	1	<2	<2	0.4	<2	2.4	0.3
Total Iron (Fe)	µg/L	50	300	580	ND	550	ND	ND	ND	<100	111	47	399	36	98	52
Total Lead (Pb)	µg/L	0.5	25 (5)	ND	ND	1.7	ND	ND	ND	<0.5	0.14	0.09	0.25	<0.02	0.62	0.17
Total Magnesium (Mg)	µg/L	50		25000	22000	27000	22000	26000	24000	22000	26300	25000	25400	28100	19000	20100
Total Manganese (Mn)	µg/L	2		360	8	220	9	43	13	15	49	15	66	10	50	21
Total Potassium (K)	µg/L	200		ND	880	1100	960	760	1100	1100	1000	1700	900	1300	700	800
Total Sodium (Na)	µg/L	100		2200	3800	3100	2900	2800	3200	2900	2600	3500	3100	4700	2400	2300
Total Zinc (Zn)	µg/L	5	30 (6)	ND	ND	7	ND	7	ND	<5	<5	<5	<5	<5	<5	<5
<b>FIELD MEASUREMENTS</b>																
Temperature	Degrees C			18.7	2.7	19.1	1.6	15.2	3.8	7.7	15	9.68	18.3	12.3	16.1	3.0
Conductivity	µmhos			520	390	530	560	540	270	440	480	471	482	498	549	398
pH				8.20	8.34	8.15	7.93	7.93	8.49	8.67	8.2	7.60	8.08	8.86	8.11	7.84

NOTES:

- PWQO indicates Provincial Water Quality Objectives.
- (I) indicates interim PWQO
- Cadmium Interim PWQO = 0.5 µg/L (for Hardness >100 mg/L as CaCO3)
- Copper Interim PWQO = 5 µg/L (for Hardness >20 mg/L)
- Revised Interim PWQO = 5 µg/L (for Alkalinity > 80 mg/L (as CaCO3))
- Zinc Revised Interim PWQO = 20 µg/L

- Alkalinity should not be decreased by more than 25 % of the natural concentration.
- Interim PWQO = 75 µg/L for pH >6.5 to 9.0.
- PWQO = 0.020 mg/L to avoid nuisance algae growth, PWQO = 0.010 mg/L for high level of protection  
PWQO = 0.030 mg/L for prevention of excessive plant growth
- PWQO for un-ionized ammonia
- Shaded values indicates exceedance of PWQO.
- ND = Not detected
- NA = Not analyzed
- RDL = Reportable Detection Limit

**Table G-2  
Surface Water Quality Results  
Kinloss Landfill - 2007 to 2023**

Surface Water Station				SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2	SW 2
Date				Jul-14	Oct-14	May-15	Oct-15	Jun-16	Nov-16	Jun-17	Nov-17	May-18	Nov-18	Jun-19	Nov-19
	Units	RDL	PWQO												
<b>INORGANICS</b>															
Total Ammonia-N	mg/L	0.05		<0.01	<0.01	<0.02	<0.02	<0.01	<0.01	<0.01	0.01	0.01	0.02	0.13	0.05
Calculated Un-ionized Ammonia	mg/L	2	0.020 (10)	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
Conductivity	umho/cm			505	512	515	570	517	560	522	503	486	515	470	490
Total Dissolved Solids	mg/L	1		276	269	-		296	311	287	269	276	292	258	253
Dissolved Organic Carbon	mg/L	0.1		9.2	8.1	3.6	3.5	5.4	2.9	4.9	8.4	4.6	7.8	6.1	6.3
Orthophosphate	mg/L	0.01		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total Phosphorus	mg/L	0.002	0.030 (9)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	0.01	0.08	<0.01	0.03	<0.01
pH	pH		6.5 - 8.5	8.12	7.98	8.59	8.15	8.17	8.14	8.18	8.06	8.58	8.14	8.13	8.17
Phenol-4AAP	mg/L	0.001	0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.002	<0.002	<0.002
Dissolved Sulphate (SO4)	mg/L	1		3	4	4.08	22.5	4	14	5	4	3	6	2	9
Turbidity				2.2	0.3	1.2	<0.5	-	-	0.8	0.7	2	0.6	0.7	0.7
Alkalinity (Total as CaCO3)	mg/L	1	(7)	259	266	268	286	294	287	277	266	272	283	245	232
Dissolved Chloride (Cl)	mg/L	1		4.6	5.8	5.48	9.05	4.8	5.8	5.7	4.7	4.6	5.8	3.9	6.7
Nitrite (N)	mg/L	0.01		<0.1	<0.1	<0.05	<0.10	<0.1	<0.1	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Nitrate (N)	mg/L	0.1		0.1	0.1	0.06	<0.10	0.2	0.2	<0.05	<0.05	<0.05	<0.05	0.08	0.16
Nitrate + Nitrite	mg/L	0.1		<0.1	<0.1	<0.06	<0.10	0.2	-	-	-	<0.05	<0.05	0.10	0.20
Hardness	mg/L			310	275	268	299	307	326	303	280	290	300	286	270
<b>METALS</b>															
Total Aluminum (Al)	µg/L	1	75 (8)	50	30	<4	<4	30	30	60	50	60	50	90	60
Total Barium (Ba)	µg/L	5		31	23	26	34	-	-	40	26	40	44	47	26
Total Boron (B)	µg/L	10	200 (I)	12	11	10	20	11	18	40	13	12	15	119	16
Total Cadmium (Cd)	µg/L	0.1	0.5 (3)	<0.02	<0.02	<0.1	<0.1	<0.02	<0.02	<0.014	<0.014	0.017	<0.015	<0.015	<0.015
Total Calcium (Ca)	µg/L	200		84500	72500	71700	79800	82000	86900	81600	72700	78200	80700	77800	72400
Total Chromium (Cr)	µg/L	5	100	<2	<2	<3	<3	<2	<2	<1	<1	<2	<2	<1	<1
Total Copper (Cu)	µg/L	1	5 (4)	<0.1	0.1	<2	<2	<0.1	<0.1	0.2	0.1	0.2	0.2	0.2	0.2
Total Iron (Fe)	µg/L	50	300	116	38	10	<0.10	49	11	68	34	62	54	96	28
Total Lead (Pb)	µg/L	0.5	25 (5)	0.16	<0.02	<1	<1	0.07	<0.02	0.03	<0.02	0.09	<0.02	0.06	0.02
Total Magnesium (Mg)	µg/L	50		24100	22900	21600	24300	24700	26500	24200	23800	23000	23900	22300	21700
Total Manganese (Mn)	µg/L	2		42	19	28	11	31	7	38	26	28	13	25	23
Total Potassium (K)	µg/L	200		1000	1400	820	1330	800	1100	800	1100	700	1400	600	1200
Total Sodium (Na)	µg/L	100		2700	2700	2510	3950	2800	4400	3900	2900	3200	4500	3600	2800
Total Zinc (Zn)	µg/L	5	30 (6)	7	5	<5	<5	<5	<5	50	<5	17	16	16	9
<b>FIELD MEASUREMENTS</b>															
Temperature	Degrees C			16.0	8.7	10.2	8.6	20.7	8.2	16.6	7.1	17.9	7.7	13.9	4.7
Conductivity	µmhos			486	489	483	524	534	518	504	531	473	435	520	497
pH				7.87	7.81	7.79	7.63	8.11	7.62	7.60	7.54	7.40	7.44	7.9	7.11

NOTES:

- PWQO indicates Provincial Water Quality Objectives.
- (I) indicates interim PWQO
- Cadmium Interim PWQO = 0.5 µg/L (for Hardness >100 mg/L as CaCO3)
- Copper Interim PWQO = 5 µg/L (for Hardness >20 mg/L)
- Revised Interim PWQO = 5 µg/L (for Alkalinity > 80 mg/L (as CaCO3))
- Zinc Revised Interim PWQO = 20 µg/L
- Alkalinity should not be decreased by more than 25 % of the natural concentration.
- Interim PWQO = 75 µg/L for pH >6.5 to 9.0.
- PWQO = 0.020 mg/L to avoid nuisance algae growth, PWQO = 0.010 mg/L for high level of protection  
PWQO = 0.030 mg/L for prevention of excessive plant growth
- PWQO for un-ionized ammonia
- Shaded values indicates exceedance of PWQO.
- ND = Not detected
- NA = Not analyzed
- RDL = Reportable Detection Limit

**Table G-2  
Surface Water Quality Results  
Kinloss Landfill - 2007 to 2023**

Surface Water Station				SW2	SW2	SW2	SW2	SW2	SW2	SW2	SW2
Date				Jul-20	Nov-20	7-Jun-21	Nov-21	Jun-22	Nov-22	May-23	Sep-23
	Units	RDL	PWQO								
<b>INORGANICS</b>											
Total Ammonia-N	mg/L	0.05		0.02	<0.01	0.03	0.03	0.02	0.01	<0.01	<0.05
Calculated Un-ionized Ammonia	mg/L	2	0.020 (10)	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
Conductivity	umho/cm			522	488	526	478	513	708	498	554
Total Dissolved Solids	mg/L	1		283	256	280	257	278	372	272	287
Dissolved Organic Carbon	mg/L	0.1		4.1	7.4	4.9	8.8	5.9	5.6	5.3	7.4
Orthophosphate	mg/L	0.01		NA	NA	NA	NA	NA			
Total Phosphorus	mg/L	0.002	0.030 (9)	0.01	0.03	0.01	0.01	0.01	0.04	0.03	0.02
pH	pH		6.5 - 8.5	8.19	8.12	8.31	8.13	8.27	7.76	8.17	8.10
Phenol-4AAP	mg/L	0.001	0.001	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
Dissolved Sulphate (SO4)	mg/L	1		5	10	5	4	3	32	4	5
Turbidity				0.6	0.6	0.5	1.0	0.3	3.6	0.4	0.9
Alkalinity (Total as CaCO3)	mg/L	1	(7)	271	242	266	255	281	232	276	301
Dissolved Chloride (Cl)	mg/L	1		5.9	5.8	5.5	4.9	4.8	71.5	4.8	6.2
Nitrite (N)	mg/L	0.01		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
Nitrate (N)	mg/L	0.1		0.2	<0.05	0.16	<0.05	0.09	2.71	0.09	0.15
Nitrate + Nitrite	mg/L	0.1		0.2	<0.05	0.20	<0.05	0.10	2.7	0.1	0.15
Hardness	mg/L			301	260	303	260	279	257	269	294
<b>METALS</b>											
Total Aluminum (Al)	µg/L	1	75 (8)	50	50	20	50	60	50	30	70
Total Barium (Ba)	µg/L	5		36	26	33	23	27	34	26	34
Total Boron (B)	µg/L	10	200 (I)	14	16	6	17	<5	59	10	9
Total Cadmium (Cd)	µg/L	0.1	0.5 (3)	<0.015	<0.015	<0.015	<0.015	<0.015	<0.015	<0.015	<0.015
Total Calcium (Ca)	µg/L	200		79800	71100	82000	70300	76200	66900	72300	78800
Total Chromium (Cr)	µg/L	5	100	3	<2	3	<2	<1	<1	<1	<1
Total Copper (Cu)	µg/L	1	5 (4)	0.8	0.4	0.2	0.2	0.4	1.2	0.3	0.6
Total Iron (Fe)	µg/L	50	300	90	34	43	68	51	120	39	48
Total Lead (Pb)	µg/L	0.5	25 (5)	0.61	0.03	0.06	0.04	0.03	0.11	0.02	0.04
Total Magnesium (Mg)	µg/L	50		24800	20000	24000	20400	21600	22000	21500	23700
Total Manganese (Mn)	µg/L	2		53	14	43	38	31	14	33	60
Total Potassium (K)	µg/L	200		1100	1300	1000	1200	700	5100	800	1000
Total Sodium (Na)	µg/L	100		3400	3100	2800	2700	2500	34500	2600	2900
Total Zinc (Zn)	µg/L	5	30 (6)	10	6	8	92	<5	<5	9	29
<b>FIELD MEASUREMENTS</b>											
Temperature	Degrees C			16.4	7.2	15.2	4.5	10.7	5.3	10.7	13.7
Conductivity	µmhos			534	407	494	466	486	582	459	546
pH				7.21	7.62	7.87	7.38	7.47	8.12	8.15	7.93

NOTES:

- PWQO indicates Provincial Water Quality Objectives.
- (I) indicates interim PWQO
- Cadmium Interim PWQO = 0.5 µg/L (for Hardness >100 mg/L as CaCO3)
- Copper Interim PWQO = 5 µg/L (for Hardness >20 mg/L)
- Revised Interim PWQO = 5 µg/L (for Alkalinity > 80 mg/L (as CaCO3))
- Zinc Revised Interim PWQO = 20 µg/L

- Alkalinity should not be decreased by more than 25 % of the natural concentration.
- Interim PWQO = 75 µg/L for pH >6.5 to 9.0.
- PWQO = 0.020 mg/L to avoid nuisance algae growth, PWQO = 0.010 mg/L for high level of protection  
PWQO = 0.030 mg/L for prevention of excessive plant growth
- PWQO for un-ionized ammonia
- Shaded values indicates exceedance of PWQO.
- ND = Not detected
- NA = Not analyzed
- RDL = Reportable Detection Limit

**APPENDIX H**

**Buffer Lands Certificate of  
Registration and Lease Agreement**



P.O. Box 130  
21 Queen Street  
Ripley, ON  
N0G 2R0

Phone: (519) 395-3735  
Fax: (519) 395-4107

email: hurontwp@hurontel.on.ca

**FACSIMILE**

To: Pryde, Schropp, McComb From: Hugh Nichol  
 Attn: Jim Scott Pages: 10 (Incl. cover)  
 Fax: 1-519-389-4728 Date: September 11, 2007  
 Re: Kinloss Waste Disposal Site

**Comments:**

As per your request, please find attached the lease agreement.

**RECEIVED**  
SEP 11 2007


CR14 00941

cc g Scott by email.



09/11/2007

18:19 TWP. OF HURON KINLOSS



# Document General

(FAX) 519 395 4107

P.002/010

Form 4 - Land Registration Return Act, 1986

**D**

FOR OFFICE USE ONLY

Number **264927**  
CERTIFICATE OF REGISTRATION

90 FEB 28 P 7:21

BRUCE  
No. 3  
WALKERTON

Lane Registrar

(1) Registry  Land Titles  (2) Page 1 of 1 pages   
(3) Property Identifier(s) Block Property

(4) Nature of Document  
Lease ~~KCXBNDKX~~

(5) Consideration  
*Twenty Thousand* Dollars *20,000.00*

(6) Description  
Part of Lot 17, Concession 6, in the Township of Kinloss, in the County of Bruce and described as Part 3 on Reference Plan 3R-4858.

New Property Identifier  
Additional See Schedule

Executions  
Additional See Schedule

(7) This Document Contains (a) Redescription New Easement Plan/Sketch  (b) Schedule for: Description  Additional Parties  Other

(8) This Document provides as follows:

See Lease ~~KCXBNDKX~~ attached.

(9) This Document relates to instrument number(s)

Continued on Schedule

(10) Party(ies) (Set out Status or Interest)  
Name(s) (Lessee)

Signature(s)

Date of Signature  
Y M D

THE CORPORATION OF THE TOWNSHIP OF KINLOSS, by their solicitor  
George C. Magwood

1990 02 25

(11) Address for Service

Hollywood, Ontario NOG 2B0

(12) Party(ies) (Set out Status or Interest)  
Name(s) (Lessor)

Signature(s)

Date of Signature  
Y M D

JOHNSTON, Donald  
JOHNSTON, BARRY

(13) Address for Service

*RR#3 Hollywood, Ontario*

(14) Municipal Address of Property

Not assigned

(15) Document Prepared by  
George C. Magwood  
WAECHTER, MAGWOOD,  
VAN DE VYVERE & THOMPSON  
215 Durham Street  
Walkerton, Ontario  
NOG 2V0

FOR OFFICE USE ONLY

Fees and Tax	
Registration Fee	22.00
L.T.T.	100.00
Total	122.00

# This Indenture

made (in duplicate) the 30th day of November  
in the year one thousand nine hundred and eighty-nine  
In Pursuance of the Short Forms of Tenure Act

Between

DONALD JOHNSTON  
and HARRY JOHNSTON

hereinafter called the LESSOR of the FIRST PART

and

THE CORPORATION OF THE TOWNSHIP OF KINLOSS

hereinafter called the LESSEE of the SECOND PART

Witnesseth that in consideration of the Rents, Covenants and Agreements hereinafter respectively reserved and contained on the part of the Lessee, to be respectively paid, observed and performed, the Lessor hath demised and Leased and by these presents DOTH demise and LEASE unto the Lessee ALL THAT parcel or tract of land and premises situate, lying and being in the Township of Kinloss in the County of Bruce containing by admeasurement

30.30 acres, be the same more or less, and being composed of Part of Lot 17, Concession 6, in the Township of Kinloss, in the County of Bruce and more particularly described as Part 3 on Reference Plan 3R-4858.

Farm Lease, p. 2 - 198 - revised 1978

Lessee and to Hold the said demised premises for and during the term of 99  
-----NINETY-NINE----- years  
to be computed from the 1st day of January one thousand  
nine hundred and ninety and thenceforth next ensuing, and  
fully to be complete and ended on the 30th day of December 2039..

YIELDING AND PAYING therefor yearly and every year during the said term hereby  
granted unto the Lessor the sum of TWENTY THOUSAND  
-----(\$20,000.00)----- Dollars, of lawful  
money of Canada, without any deduction, defalcation or abatement whatsoever to be  
payable on the following days and times, that is to say:

The sum of \$20,000.00 to be paid to the lessor on the final  
signing of this agreement by all parties.

THE first of such payments to become due and be made on the  
----- day of -----

THE Lessee COVENANTS with the Lessor to pay rent.  
~~AND to pay taxes, except for local improvements.~~  
~~AND to repair, reasonable wear and tear and damage by fire, lightning and tempest only~~  
~~excepted.~~  
~~AND to keep up fences.~~  
AND to perform all statute labour.  
AND not to cut down timber or trees of any kind whatsoever, except

AND that the Lessor may enter and view state of repair.  
~~AND that the Lessee will repair according to notice in writing, reasonable wear and tear,~~  
~~and damage by fire, lightning and tempest only excepted.~~  
AND will not assign or sub-let without leave; and such consent may, notwithstanding any  
section of the Landlord and Tenant Act of the Province of Ontario, be arbitrarily refused  
by the Lessor in his sole and uncontrolled discretion.  
AND will not carry on any business that shall be deemed a nuisance on said premises.  
AND that he will leave the premises in good repair (reasonable wear and tear and damage  
by fire, lightning and tempest only excepted).

~~PROVIDED that the Lessee may remove his fixtures, if such removal may be and is done~~  
~~without injury to the said premises.~~  
~~PROVIDED that in the event of damage by fire, lightning or tempest, rent shall cease until~~  
~~the premises are rebuilt.~~

THE SAID LESSEES hereby covenants and agrees with the said Lessor, that in considera-  
tion of the premises, and of the leasing and letting by the said Lessor to the said Lessee  
of the lands and premises above named for the term hereby created (and it is upon that  
express understanding that these presents are entered into), that notwithstanding any-  
thing contained in Section 30 of Chapter two hundred and thirty six of the Revised  
Statutes of Ontario, 1978, or in any other section of the said Act, or any other Statute  
which may hereafter be passed to take the place of the said Act or to amend the same,  
that none of the goods or chattels of the said Lessee at any time during the continuance  
of the term hereby created, on said demised premises, shall be exempt from levy by distress  
for rent in arrear by said Lessee as provided for by section or sections of the said Act  
above named, or any amendment or amendments thereto, and that upon any claim being  
made for such exemption by said Lessee or on distress being made by the said Lessor this  
covenant and agreement may be pleaded as an estoppel against the said Lessee in any  
action brought to test the right to the levying upon any such goods as are named as  
exempted in said Section or Sections, or amendment or amendments, thereto. Said Lessee  
under and by virtue of the said Section or Sections of said Act, or any amendment or  
amendments thereto but for the above Covenant.

~~AND the Lessee doth hereby further covenant and agree with the Lessor in manner follow-  
ing, that is to say: THAT the Lessee will during the said term, cultivate, till, manure and  
employ such parts of the said premises as are now or shall hereafter be brought under  
cultivation in a good farmer-like and proper manner, and will in like manner crop the same  
in a regular rotation of crops so as not to impoverish, depreciate or injure the soil, and will  
plough the lands in each year during the said term, and at the end of the said term will  
leave the said land so manured as aforesaid. AND will during the continuance of said  
term mow the grass along the fences and in the fence corners on the said lands, keep down  
all noxious weeds and grasses, which shall grow upon the said premises or on the side of  
the roads or highways adjacent thereto, and will not sow or permit to be sown any grain  
infected by smut or containing any foul seeds or noxious weeds, and will not suffer or  
permit any such foul seeds or noxious weeds to go to seed on the said premises.~~

AND that if at any time during the said term the Lessee shall neglect to pull up or other-  
wise destroy or prevent from going to seed on the said lands any noxious weeds or grasses  
growing thereon, and which are reasonably within the power and duty of the Lessee so to

Farm Lease, p. 3 - 197 - revised 1978

~~pull-up or otherwise destroy, or prevent from going to seed, the Lessee may, by notice in writing, require the Lessee within 48 hours after the service of such notice, to pull up or otherwise destroy or prevent them from going to seed, and on default of the Lessee so doing, the Lessor may enter upon the said lands with laborers and workmen and do the work by the said notice required to be done by the Lessee, and all costs, charges and expenses of or incidental thereto shall be added to the rents hereby reserved, and shall be recoverable in like manner as rent reserved, but this provision shall not in any way impair or abridge the right of re-entry by the Lessor on non-performance of covenants. This clause shall not supersede the provisions contained in The Weed Control Act R.S.O. 1970, Chapter 192 as amended from time to time.~~

AND will keep the mouths of all underdrains on the said premises open and free from obstruction, and in good running order at all times during the said term, and will not suffer or permit such drains, or the water-courses in any open ditches on said premises to become obstructed, but will constantly keep the same free and clear, for the escape of the water flowing therein.

~~AND will carefully protect and preserve all orchard, fruit and shade and ornamental trees on said premises from waste, injury or destruction, and will carefully prune and care for all such trees as often as they require it, and will not suffer or permit any horse, cattle or sheep to have access to the orchard on said premises. And will not allow the manure to be placed or lie against the said buildings on said premises. And will allow any incoming tenant or purchaser to plow the said lands after harvest in the last year of said term, and to have stabling for one team or shelter for one tractor and bedroom for one man, and reasonable privilege and rights of way to do said plowing.~~

PROVIDED also, and it is hereby expressly agreed and understood by the parties hereto that if the term hereby granted or any of the goods or chattels of the Lessee shall be at any time during said term seized or taken in execution, or attachment by any creditor of the Lessee or if the Lessee shall make any Chattel Mortgage or Bill of Sale of any of his crops or other goods and chattels, or any assignment for the benefit of creditors, or becoming bankrupt and insolvent, shall take the benefit of any Act, that may be in force for bankrupt and insolvent debtors, or shall attempt to abandon said premises, to sell and dispose of his farm stock and implements, so that there would not in the event of such sale or disposal be a sufficient distress on said premises for the then accruing rent, of which the Lessor shall be sole judge, then in every such case, the then current and next ensuing year's rent and the taxes for the then current year (to be reckoned upon the rate of the previous year, in case rate shall not have been fixed for current year) shall immediately become due and payable and the term hereby granted shall at the option of the Lessor immediately become forfeited, void and determined, and in every of the above cases such taxes or accrued portion thereof may be recoverable by the Lessor in the same manner as the rent hereby reserved.

PROVIDED also that, in case of removal by the Lessee of his goods and chattels in whole or substantial part from off the said premises, the Lessor may distrain for the rents hereby reserved upon the goods and chattels of the Lessee upon any other premises to which they may have been removed.

~~IN case the Lessor should desire to sell the said lands and premises during the said term, the said term may be determined at any time upon one (1) month's notice by notice to such effect, and that the Lessee will, at the expiration of the time limited by the said notice, peaceably and quietly give up possession of the said lands and premises to the Lessor; provided that upon such earlier determination of the said term, and after the Lessee shall have delivered up possession in manner aforesaid, and paid to the Lessor the full proportion of rent and taxes up to the date of such earlier determination, the Lessee shall be entitled to be compensated for the value of the crops sown and then growing, or of the ploughing done on the said lands in preparing for a crop, the amount of such compensation to be determined by arbitration if the parties cannot agree thereon.~~

IN the event of any misunderstanding or misinterpretation arising out of the lease, the parties herein agree that the matter shall be then settled forthwith in accordance with the provisions contained in The Arbitration Act, R.S.O. 1970, as amended from time to time to be bound by any such decisions obtained as a result thereof.

~~AND it is hereby agreed between the parties hereto that should the Lessee remain in possession of the said lands and premises after the termination of the term hereby granted, without other special agreement, it shall be as a monthly tenant only at a rental of \$ 0.15 per month payable in advance on the 1st day of every month and subject in all other respects to the terms of this lease.~~

ANY notice or other communication required or permitted to be given hereunder shall be in writing and shall be given either by delivering the same to the recipient or mailing the same postage prepaid in a government post box to the recipient at the following address:

If to the Lessor:

If to the Lessee:

9. The benefits and burdens of this lease shall be binding upon the parties hereto and their respective heirs, executors, administrators, successors and assigns.

THE CORPORATION OF THE TOWNSHIP  
OF KINLOSS

*David Eadie*  
Reeve  
Acting

*W. P. Johnston*  
Clerk

*Donald Johnston*  
Donald Johnston

*Barry Johnston*  
Barry Johnston



Form 1 - Land Transfer Tax Act  
Affidavit of Residence and of Value of the Consideration

Refer to all instructions on reverse side.

IN THE MATTER OF THE CONVEYANCE OF Part of Lot 17, Concession 6, Township of Kinloss, County of Bruce being described as Part 1 on Reference Plan 1R-48!

BY Donald Johnston & Barry Johnston

TO The Corporation of the Township of Kinloss

1. George C. Magwood

MAKE OATH AND SAY THAT:

- (a) I am giving a false statement which the sworn deponent has made in the following paragraphs that describe the capacity of the deponent: (see instruction 2)
- (b) A person in trust for whom the land conveyed in the above-described conveyance is being conveyed;
- (c) A transferee named in the above-described conveyance to whom the land is being conveyed;
- (d) The authorized agent or solicitor acting in this transaction for Township of Kinloss The Corporation of the
- (e) The President, Vice President, Manager, Secretary, Director, or Treasurer authorized to act for Township of Kinloss
- (f) A transferee described in paragraph 1 described in paragraph(s) (a), (b), (c) above: (make and reference to applicable paragraph(s) in paragraph 1)

2. (To be completed where the value of the consideration for the conveyance exceeds \$200,000.)  
I have read and considered the definition of "single family residence" set out in clause 1(1)(1) of the Act. The land conveyed in the above-described conveyance

- contains at least one and not more than two single family residences
- does not contain a single family residence.
- contains more than two single family residences. (see instruction 3)

Note: Clause 2(1) (a) imposes an additional tax at the rate of one-half of one per cent upon the value of consideration in excess of \$200,000 where the conveyance contains at least one and not more than two single family residences.

3. I have read and considered the definitions of "non-resident corporation" and "non-resident person" set out respectively in clauses 1(1)(1) and (g) of the Act and each of the following persons to whom or in trust for whom the land is being conveyed in the above-described conveyance is a "non-resident person" as set out in the Act. (see instructions 4 and 5)

4. THE TOTAL CONSIDERATION FOR THIS TRANSACTION IS ALLOCATED AS FOLLOWS

(a) Moneys paid or to be paid in cash		
(b) Mortgages (i) Assumed (after principal and interest to be cancelled against purchase price)	\$ 20,000.00	
(ii) Given back to vendor	\$ nil	
(c) Property transferred in exchange (after taxes)	\$ nil	
(d) Securities transferred to the value of (total value)	\$ nil	
(e) Liens, legacies, annuities and maintenance charges to which transfer is subject	\$ nil	
(f) Other valuable considerations subject to land transfer (see instruction 4)	\$ nil	
(g) VALUE OF LAND, BUILDING, FIXTURES AND GOODWILL SUBJECT TO LAND TRANSFER TAX (Total of (a) to (f))	\$ 20,000.00	\$ 20,000.00
(h) VALUE OF ALL CHATTELS - Items of tangible personal property (listed below) to be included in the value of all chattels unless exempt under the provisions of the "Fixed Sales Tax Act", R.S.O. 1990, c. 44, as amended		
(i) Other considerations for transaction not included in (g) or (h) above		
(j) TOTAL CONSIDERATION		nil
		nil
		\$ 20,000.00

All items must be filed in book "A" where Applicable

- 5. If consideration is nominal, describe relationship between transferor and transferee and state purpose of conveyance. (see instruction 6) n/a
- 6. If the consideration is nominal, is the land subject to any encumbrance? n/a
- 7. Other remarks and explanations, if necessary. n/a

Sworn before me at the Town of Walkerton  
in the County of Bruce  
this 27 day of February 19 90

[Signature]  
A Commissioner for taking Affidavits, etc

JOHN KEP, a Commissioner, etc., Bruce County, for  
Wachtler, Magwood, Van De Vyvere & Thompson,  
Barristers & Solicitors. Expires March 3, 1992.

[Signature]  
Mortgagee

Property Information Record

A. Describe nature of instrument Document General - LASS

B. (i) Address of property being conveyed (if available) Not assigned

(ii) Assessment Roll file # available Not assigned

C. Mailing address for future Notices of Assessment under the Assessment Act for property being conveyed (see instruction 7) Hollywood, Ontario

D. (i) Registration number for last conveyance of property being conveyed (if known) \_\_\_\_\_

(ii) Legal description of property conveyed Same as in D (i) above.

E. Name(s) and address(es) of each transferee's solicitor

George C. Magwood Yes  No  Not known

WACHTLER, MAGWOOD, VAN DE VYVERE

L. THOMPSON

215 Durban Street

Walkerton, Ontario

N0G 2V0

Fee Land Registry Office use only


REGISTRATION NO. \_\_\_\_\_

Land Registry Office No \_\_\_\_\_

Registration Date \_\_\_\_\_

3R-4858

*[Handwritten signature]*



Form Lease, p. 4 - 198 - revised 1978

ANY notice or other communication mailed or delivered as aforesaid shall be deemed to have been given at the date it was personally delivered or if mailed shall be deemed to have been given on the third business day following the date of which it was mailed. Either the Lessor or the Lessee may change his address for service from time to time by giving notice in accordance with the foregoing.

PROVISO for re-entry by the Lessor on non-payment of rent, or non-performance of Covenants.

THE Lessor COVENANTS with the Lessee for quiet enjoyment. The parties further covenant that the terms contained in Schedule A attached hereto shall form part of this lease and be binding on the parties.

IT is hereby declared and agreed that this Indenture shall enure to the benefit of and be binding upon the parties hereto, their heirs, executors, administrators and assigns, respectively.

AND it is further agreed that wherever the singular and masculine are used in this Indenture they shall be construed as if the plural or the neuter or feminine had been used, where the context or the party or parties hereto so require, and the rest of the sentence shall be construed as if the grammatical and terminological changes thereby rendered necessary had been made.

IN WITNESS WHEREOF the said parties hereto have hereunto set their hands and seal.

Signed, Sealed and Delivered  
In the presence of

THE CORPORATION OF THE TOWNSHIP OF  
KINLOSS

*David Edging*  
Reeve  
Acting  
*Donald Johnston*  
Clerk

*Barry Johnston*  
Barry Johnston  
AFFIDAVIT AS TO AGE AND MARITAL STATUS



I/WE  
of the  
in the  
make oath and say: When executed the attached instrument.

I/WE  
at least eighteen years old.  
I was married / divorced / widower  
was my wife / husband.

We were married to each other.

(SEVERALLY) SWORN before me at the

this day of 18

A COMMISSIONER FOR TAKING AFFIDAVITS ETC

\* If attorney  
see footnote  
  
Not to be  
inapplicable  
reason.

\* Where affidavit made by attorney witness: When I executed the attached instrument as attorney for [name], he/she was [married status], and if married, name of spouse, and where he, she executed the power of attorney he/she had attained the age of majority.



SCHEDULE A

To the lease dated November 30, 1989 between the Corporation of the Township of Kinloss as Lessee and Donald and Barry Johnston as Lessors.

1. It is acknowledged by the parties that the demised premises described in this lease will be used by the Lessee as a buffer zone for the purpose of protecting the existing Kinloss Township waste disposal site located on Part Lot 16, Concession 6, Kinloss Township, Bruce County.
2. It is acknowledged that the right to use the land by the Lessee shall include the full right of access at any time by the lessee, its employees, servants and agents, and necessary equipment for the purpose of making inspections and for the purpose of monitoring surface and ground water upon and under the buffer lands, and the lessee agrees to restore, as nearly as may be possible the lands to the extent that they may be altered or disturbed by the exercise of the rights granted in this lease.
3. The Lessor as owners shall have the continued use of the land and access thereto for recreational purposes and shall specifically retain the right to cut timber on the land and to sell any such timber and retain the proceeds therefrom. Provided the Lessors shall not erect any buildings or drill any wells on the said land.
4. It is acknowledged that there is a small spring-fed pond in the southerly portion of the leased land and it is acknowledged that the Lessee will include the pond in the water monitoring program which is required by the Ministry of the Environment as a result of the operation of the adjoining waste disposal site.
5. The Lessor shall be responsible for any real property taxes assessed against the said leased lands and shall pay the taxes so assessed to the Township of Kinloss as they fall due.
6. (a) The Lessee shall indemnify and save harmless the Lessor from all liability whatsoever which may be directly or indirectly attributed to the use of the land by the Lessor as a buffer to its waste disposal site.  
(b) It is acknowledged by the Lessor that the water within the ground may migrate from the adjoining land fill site owned by the Lessee under the surface of the buffer lands, or that surface water may flow across the lands and that such water may not be suitable as drinking water or for other uses and the Lessors agree not to hold the Lessee liable or in any way responsible for a diminution of water quality on the buffer lands.
7. It is acknowledged and agreed by both parties that no further ponds or wells of any type, or the alteration of any existing streams, waterways, or ponds shall be permitted on the said buffer lands, without approval in writing having first been obtained from the Provincial Ministry of the Environment.
8. This agreement and the easements and rights hereby granted are and shall be conditional upon the approval, pursuant to the Environmental Assessment Act and the Environmental Protection Act, of the use of the Township lands for an enlargement and extension of the Township's waste disposal site.

Cont'd

**APPENDIX I**

# Monitoring and Screening Checklist

## Appendix D-Monitoring and Screening Checklist

### General Information and Instructions

**General Information: The checklist is to be completed, and submitted with the Monitoring Report.**

**Instructions:** A complete checklist consists of:

- (a) a completed and signed checklist, including any additional pages of information which can be attached as needed to provide further details where indicated.
- (b) completed contact information for the Competent Environmental Practitioner (CEP)
- (c) self-declaration that CEP(s) meet(s) the qualifications as set out below and in Section 1.2 of the Technical Guidance Document.

**Definition of Groundwater CEP:**

For groundwater, the CEP must have expertise in hydrogeology and meet one of the following:

- (a) the person holds a licence, limited licence or temporary licence under the *Professional Engineers Act*; or
- (b) the person holds a certificate of registration under the *Professional Geoscientists Act, 2000* and is a practicing member, temporary, member or limited member of the Association of Professional Geoscientists of Ontario. O. Reg. 66/08, s. 2..

**Definition of Surface water CEP:**

A CEP for surface water assessments is a scientist, professional engineer or professional geoscientist as described in (a) and (b) above with demonstrated experience and post-secondary education, either a diploma or degree, in hydrology, aquatic ecology, limnology, aquatic biology, physical geography with specialization in surface water, and/or water resource management.

The type of scientific work that a CEP performs must be consistent with that person's education and experience. If an individual has appropriate training and credentials in both groundwater and surface water and is responsible for both areas of expertise, the CEP may then complete and validate both sections of the checklist.

<b>Monitoring Report and Site Information</b>	
<b>Waste Disposal Site Name</b>	Kinloss Waste Disposal Site
<b>Location (e.g. street address, lot, concession)</b>	Part Lot 16, Concession 6, in the Former Township of Kinloss, Township of Huron-Kinloss, County of Bruce
<b>GPS Location (taken within the property boundary at front gate/ front entry)</b>	463575 m E, 4871980 m N
<b>Municipality</b>	Township of Huron-Kinloss
<b>Client and/or Site Owner</b>	Township of Huron-Kinloss
<b>Monitoring Period (Year)</b>	2023
This Monitoring Report is being submitted under the following:	
<b>Certificate of Approval No.:</b>	A272801
<b>Director's Order No.:</b>	
<b>Provincial Officer's Order No.:</b>	
<b>Other:</b>	

<b>Report Submission Frequency</b>	<input checked="" type="radio"/> <b>Annual</b> <input type="radio"/> <b>Other</b>	Specify (Type Here):
<b>The site is:</b>	<input type="radio"/> <b>Active</b> <input checked="" type="radio"/> <b>Inactive</b> <input type="radio"/> <b>Closed</b>	
<b>If closed, specify C of A, control or authorizing document closure date:</b>		N/A
<b>Has the nature of the operations at the site changed during this monitoring period?</b>	<input type="radio"/> <b>Yes</b> <input checked="" type="radio"/> <b>No</b>	
<b>If yes, provide details:</b>	Type Here	
<b>Have any measurements been taken since the last reporting period that indicate landfill gas volumes have exceeded the MOE limits for subsurface or adjacent buildings? (i. e. exceeded the LEL for methane)</b>	<input type="radio"/> <b>Yes</b> <input checked="" type="radio"/> <b>No</b>	

## Groundwater WDS Verification:

Based on all available information about the site and site knowledge, it is my opinion that:

### Sampling and Monitoring Program Status:

<p>1) The monitoring program continues to effectively characterize site conditions and any groundwater discharges from the site. All monitoring wells are confirmed to be in good condition and are secure:</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No</p>	
<p>2) All groundwater, leachate and WDS gas sampling and monitoring for the monitoring period being reported on was successfully completed as required by Certificate(s) of Approval or other relevant authorizing/control document(s):</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No <input type="radio"/> Not Applicable</p>	<p>If no, list exceptions below or attach information.</p>

Groundwater Sampling Location	Description/Explanation for change (change in name or location, additions, deletions)	Date

<b>3) a) Some or all groundwater, leachate and WDS gas sampling and monitoring requirements have been established or defined outside of a ministry C of A, authorizing, or control document.</b>		<input type="radio"/> Yes <input checked="" type="radio"/> No <input type="radio"/> Not Applicable
<b>b) If yes, the sampling and monitoring identified under 3(a) for the monitoring period being reported on was successfully completed in accordance with established protocols, frequencies, locations, and parameters developed as per the Technical Guidance Document:</b>		<input type="radio"/> Yes <input type="radio"/> No <input checked="" type="radio"/> Not Applicable
<b>Groundwater Sampling Location</b>		<b>Date</b>
<b>Description/Explanation for change (change in name or location, additions, deletions)</b>		
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
<b>4) All field work for groundwater investigations was done in accordance with standard operating procedures as established/outlined per the Technical Guidance Document (including internal/external QA/QC requirements) (Note: A SOP can be from a published source, developed internally by the site owner's consultant, or adopted by the consultant from another organization):</b>		<input checked="" type="radio"/> Yes <input type="radio"/> No  If no, specify (Type Here):

## Sampling and Monitoring Program Results/WDS Conditions and Assessment:

<p>5) The site has an adequate buffer, Contaminant Attenuation Zone (CAZ) and/or contingency plan in place. Design and operational measures, including the size and configuration of any CAZ, are adequate to prevent potential human health impacts and impairment of the environment.</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No</p>		
<p>6) The site meets compliance and assessment criteria.</p>	<p><input type="radio"/> Yes <input checked="" type="radio"/> No</p>	RUC exceedances discussed in Section 3.5 of the AMR.	
<p>7) The site continues to perform as anticipated. There have been no unusual trends/ changes in measured leachate and groundwater levels or concentrations.</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No</p>		
<p>1) Is one or more of the following risk reduction practices in place at the site:</p> <p>(a) There is minimal reliance on natural attenuation of leachate due to the presence of an effective waste liner and active leachate collection/treatment; or</p> <p>(b) There is a predictive monitoring program in-place (modeled indicator concentrations projected over time for key locations); or</p> <p>(c) The site meets the following two conditions (typically achieved after 15 years or longer of site operation):</p> <p><i>i.</i> The site has developed stable leachate mound(s) and stable leachate plume geometry/concentrations; and</p> <p><i>ii.</i> Seasonal and annual water levels and water quality fluctuations are well understood.</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No</p>	<p>Note which practice(s):</p>	<p><input type="checkbox"/> (a) <input type="checkbox"/> (b) <input checked="" type="checkbox"/> (c)</p>
<p>9) Have trigger values for contingency plans or site remedial actions been exceeded (where they exist):</p>	<p><input type="radio"/> Yes <input type="radio"/> No <input checked="" type="radio"/> Not Applicable</p>	<p>If yes, list value(s) that are/have been exceeded and follow-up action taken (Type Here):</p>	

## Groundwater CEP Declaration:

I am a licensed professional Engineer or a registered professional geoscientist in Ontario with expertise in hydrogeology, as defined in Appendix D under Instructions. Where additional expertise was needed to evaluate the site monitoring data, I have relied on individuals who I believe to be experts in the relevant discipline, who have co-signed the compliance monitoring report or monitoring program status report, and who have provided evidence to me of their credentials.

I have examined the applicable Certificate of Approval and any other environmental authorizing or control documents that apply to the site. I have read and followed the Monitoring and Reporting for Waste Disposal Sites Groundwater and Surface Water Technical Guidance Document (MOE, 2010, or as amended), and associated monitoring and sampling guidance documents, as amended from time to time. I have reviewed all of the data collected for the above-referenced site for the monitoring period(s) identified in this checklist. Except as otherwise agreed with the ministry for certain parameters, all of the analytical work has been undertaken by a laboratory which is accredited for the parameters analysed to *ISO/IEC 17025:2005 (E)- General requirements for the competence of testing and calibration laboratories*, or as amended from time to time by the ministry.

If any exceptions or potential concerns have been noted in the questions in the checklist attached to this declaration, it is my opinion that these exceptions and concerns are minor in nature and will be rectified for the next monitoring/reporting period. Where this is not the case, the circumstances concerning the exception or potential concern and my client's proposed action have been documented in writing to the Ministry of the Environment District Manager in a letter from me dated:

## Recommendations:

Based on my technical review of the monitoring results for the waste disposal site:

No changes to the monitoring program are recommended

The following change(s) to the monitoring program is/are recommended:

No Changes to site design and operation are recommended

The following change(s) to the site design and operation is/are recommended:



<b>Name:</b>	Sarah Hutchesson, M.Sc., P.Eng.		
<b>Seal:</b>	Add Image		
<b>Signature:</b>		<b>Date:</b>	26-Mar-2024
<b>CEP Contact Information:</b>	121 Commerce Park Drive, Unit L Barrie, ON L9Y 8X1		
<b>Company:</b>	WSP Canada Inc.		
<b>Address:</b>	121 Commerce Park Drive, Unit L Barrie, ON L9Y 8X1		
<b>Telephone No.:</b>	(705) 441-6016	<b>Fax No. :</b>	(705) 441-6016
<b>E-mail Address:</b>	sarah.hutchesson@wsp.com		
<b>Co-signers for additional expertise provided:</b>			
<b>Signature:</b>	<input type="text"/>	<b>Date:</b>	Select Date
<b>Signature:</b>	<input type="text"/>	<b>Date:</b>	Select Date

## Surface Water WDS Verification:

Provide the name of surface water body/bodies potentially receiving the WDS effluent and the approximate distance to the waterbody (including the nearest surface water body/bodies to the site):

Name (s)	Tributary of Kinloss Creek
Distance(s)	235 m east of landfill

Based on all available information and site knowledge, it is my opinion that:

### Sampling and Monitoring Program Status:

1) The current surface water monitoring program continues to effectively characterize the surface water conditions, and includes data that relates upstream/background and downstream receiving water conditions:	<input checked="" type="radio"/> Yes <input type="radio"/> No	
2) All surface water sampling for the monitoring period being reported was successfully completed in accordance with the Certificate(s) of Approval or relevant authorizing/control document(s) (if applicable):	<input checked="" type="radio"/> Yes <input type="radio"/> No <input type="radio"/> Not applicable (No C of A, authorizing / control document applies)	If no, specify below or provide details in an attachment.

Surface Water Sampling Location	Description/Explanation for change (change in name or location, additions, deletions)	Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date

<p>3) a) Some or all surface water sampling and monitoring program requirements for the monitoring period have been established outside of a ministry C of A or authorizing/control document.</p>	<p><input type="radio"/> Yes</p> <p><input checked="" type="radio"/> No</p> <p><input type="radio"/> Not Applicable</p>		
<p>b) If yes, all surface water sampling and monitoring identified under 3 (a) was successfully completed in accordance with the established program from the site, including sampling protocols, frequencies, locations and parameters) as developed per the Technical Guidance Document:</p>	<p><input type="radio"/> Yes</p> <p><input type="radio"/> No</p> <p><input checked="" type="radio"/> Not Applicable</p>	<p>If no, specify below or provide details in an attachment.</p>	
Surface Water Sampling Location	Description/Explanation for change (change in name or location, additions, deletions)		Date
Type Here	Type Here		Select Date
Type Here	Type Here		Select Date
Type Here	Type Here		Select Date
Type Here	Type Here		Select Date
<p>4) All field work for surface water investigations was done in accordance with standard operating procedures, including internal/external QA/QC requirements, as established/ outlined as per the Technical Guidance Document, MOE 2010, or as amended. (Note: A SOP can be from a published source, developed internally by the site owner's consultant, or adopted by the consultant from another organization):</p>	<p><input checked="" type="radio"/> Yes</p> <p><input type="radio"/> No</p>	<p>If no, specify (Type Here):</p>	

## Sampling and Monitoring Program Results/WDS Conditions and Assessment:

5) The receiving water body meets surface water-related compliance criteria and assessment criteria: i.e., there are no exceedances of criteria, based on MOE legislation, regulations, Water Management Policies, Guidelines and Provincial Water Quality Objectives and other assessment criteria (e.g., CWQGs, APVs), as noted in Table A or Table B in the Technical Guidance Document (Section 4.6):

- Yes  
 No

If no, list parameters that exceed criteria outlined above and the amount/percentage of the exceedance as per the table below or provide details in an attachment:

Parameter	Compliance or Assessment Criteria or Background	Amount by which Compliance or Assessment Criteria or Background Exceeded
e.g. Nickel	e.g. C of A limit, PWQO, background	e.g. X% above PWQO
As outlined in Section 3.4 of report	As outlined in Section 3.4 of report	As outlined in Section 3.4 of report

6) In my opinion, any exceedances listed in Question 5 are the result of non-WDS related influences (such as background, road salting, sampling site conditions)?

- Yes  
 No

As outlined in Section 3.4 of report, the pattern indicates that the landfill site does not have a measurable effect on the water quality of the creek.

<p>7) <b>All monitoring program surface water parameter concentrations fall within a stable or decreasing trend. The site is not characterized by historical ranges of concentrations above assessment and compliance criteria.</b></p>	<p><input checked="" type="radio"/> <b>Yes</b></p> <p><input type="radio"/> <b>No</b></p>	<p>If no, list parameters and stations that is outside the expected range. Identify whether parameter concentrations show an increasing trend or are within a high historical range (Type Here)</p>
<p>8) <b>For the monitoring program parameters, does the water quality in the groundwater zones adjacent to surface water receivers exceed assessment or compliance criteria (e.g., PWQOs, CWQGs, or toxicity values for aquatic biota (APVs)):</b></p>	<p><input type="radio"/> Yes</p> <p><input checked="" type="radio"/> <b>No</b></p> <p><input type="radio"/> Not Known</p> <p><input type="radio"/> Not Applicable</p>	<p>If yes, provide details and whether remedial measures are necessary (Type Here)</p>
<p>9) <b>Have trigger values for contingency plans or site remedial actions been exceeded (where they exist):</b></p>	<p><input type="radio"/> Yes</p> <p><input type="radio"/> No</p> <p><input checked="" type="radio"/> <b>Not Applicable</b></p>	<p>If yes, list value(s) that are/have been exceeded and follow-up action taken (Type Here)</p>

## Surface Water CEP Declaration:

I, the undersigned hereby declare that I am a Competent Environmental Practitioner as defined in Appendix D under Instructions, holding the necessary level of experience and education to design surface water monitoring and sampling programs, conduct appropriate surface water investigations and interpret the related data as it pertains to the site for this monitoring period.

I have examined the applicable Certificate of Approval and any other environmental authorizing or control documents that apply to the site. I have read and followed the Monitoring and Reporting for Waste Disposal Sites Groundwater and Surface Water Technical Guidance Document (MOE, 2010, or as amended) and associated monitoring and sampling guidance documents, as amended from time to time. I have reviewed all of the data collected for the above-referenced site for the monitoring period(s) identified in this checklist. Except as otherwise agreed with the ministry for certain parameters, all of the analytical work has been undertaken by a laboratory which is accredited for the parameters analysed to *ISO/IEC 17025:2005 (E)- General requirements for the competence of testing and calibration laboratories*, or as amended from time to time by the ministry.

If any exceptions or potential concerns have been noted in the questions in the checklist attached to this declaration, it is my opinion that these exceptions and concerns are minor in nature or will be rectified for future monitoring events. Where this is not the case, the circumstances concerning the exception or potential concern and my client's proposed action have been documented in writing to the Ministry of the Environment District Manager in a letter from me dated:

## Recommendations:

Based on my technical review of the monitoring results for the waste disposal site:

<p><input checked="" type="radio"/> No Changes to the monitoring program are recommended</p> <p><input type="radio"/> The following change(s) to the monitoring program is/are recommended:</p>	<p>Type Here</p>
<p><input checked="" type="radio"/> No changes to the site design and operation are recommended</p> <p><input type="radio"/> The following change(s) to the site design and operation is/are recommended:</p>	<p>Type Here</p>

<b>CEP Signature</b>		
<b>Relevant Discipline</b>	Engineer	
<b>Date:</b>	26-Mar-2024	
<b>CEP Contact Information:</b>	Sarah Hutchesson, M.Sc., P.Eng	
<b>Company:</b>	WSP Canada Inc.	
<b>Address:</b>	121 Commerce Park Drive, Unit L Barrie, ON L9Y 8X1	
<b>Telephone No.:</b>	(705) 441-6016	
<b>Fax No. :</b>		
<b>E-mail Address:</b>	sarah.hutchesson@wsp.com	
<b>Save As</b>		<b>Print Form</b>

wsp

wsp.com